

TECHNICAL MEMORANDUM

Contract No.: 1000090 (Award No. 61251)
Test Report No.: TM 479070-1
Project Name: Crash Testing for Hawaii DOT Typical Cement Rubble Masonry
Guardrail Walls at MASH Test Levels One and Two
Sponsor: Hawaii Department of Transportation
DATE: February 6, 2013
TO: Dean Takiguchi
Hawaii Department of Transportation
COPY TO: Michele Lacey, TAMU Office of Sponsored Research Services
Erlinda Olivarez, TTI RDO
D. L. Bullard, Jr., Head, TTI Roadside Safety & Physical Security Division
Rebecca Haug, TTI Roadside Safety & Physical Security Division
FROM: Michael S. Brackin, M.S.C.E., E.I.T., Associate Transportation
Researcher, TTI Roadside Safety & Physical Security Division
Dean C. Alberson, P.E., Research Engineer, TTI Roadside Safety &
Physical Security Division
PREPARED BY: Wanda L. Menges, Research Specialist, TTI Proving Ground
FOR MORE INFORMATION:
Name: Michael S. Brackin
Phone: 979-845-2019
Email: m-brackin@ttimail.tamu.edu

SUMMARY REPORT:

DISCLAIMER:

The contents of this report reflect the views of the authors who are solely responsible for the facts and accuracy of the data, findings and conclusions presented herein. The contents do not necessarily reflect the official views or policies of the Hawaii Department of Transportation, The Texas A&M University System, or Texas A&M Transportation Institute. This report does not constitute a standard, specification, or regulation. In addition, the above listed agencies assume no liability for its contents or use thereof. The names of specific products or manufacturers listed herein do not imply endorsement of those products or manufacturers. The results reported herein apply only to the article being tested. The test was performed according to TTI Proving Ground quality procedures and according to AASHTO *MASH*.

TEST ARTICLE DESIGN AND CONSTRUCTION

The Hawaii Masonry Wall is a cement rubble masonry wall that is intended to serve as a longitudinal barrier according to the provisions of American Association of State Highway and Transportation Officials (AASHTO) *Manual for Assessing Safety Hardware (MASH)* Test Levels One and Two. The wall is constructed using stacked limestone with mortar joints. The Hawaii Masonry Wall was installed at the TTI Proving Ground facility by R. W. Pfeffer Masonry, Inc. of Bryan, TX.

Approximate overall dimensions for the installation, above grade, were 24 inches wide at the base, 16 inches wide at the top, and 24 inches tall. The overall length of the installation was 100 ft. The limestone used to construct the wall was clean, hard, sound, and durable. The individual stones had a minimum thickness not less than 6 inches and minimum width not less than 1-1/2 times the thickness and not less than 12 inches. With the exception of header stones, the minimum length was 1-1/2 times the stone's width. The largest stones were used on the bottom course, after which the stones were graded to decrease in width from bottom to top of the wall. The fascia stones were uniformly distributed by size. The wall was finished with a 2-inch mortar cap.

The stones were fully embedded in mortar. The mortar mix contained 1 part cement and 2 parts sand and/or fine aggregate by volume. The mortar was placed within 30 minutes of water being added. A minimum overlap of 6 inches was specified where the stones overlapped. On the day of testing, the average mortar compressive strength was 6530 psi.

The wall was installed in a bed of crushed limestone, 72 inches wide by 20 inches deep. The crushed limestone used was Georgetown Superflex with 100 percent compaction and a moisture content of 10.1, measured on the day of testing. The wall was keyed into the crushed limestone bedding 12 inches and was centered along the width. The approximate overall dimensions of the wall were 28 inches wide at the base, 16 inches wide at the top, and 36 inches tall. The wall side opposite impact had a positive slope of 12V:3H. The impact side had a positive slope of 12V:1H.

Photographs of the Hawaii Masonry Wall are shown in figure 1. Refer to Attachment A for further details of the test article.

TEST DESIGNATION AND ACTUAL TEST CONDITIONS

MASH test 1-11 involves a 2270P vehicle weighing 5000 lb \pm 100 lb and impacting the Hawaii Masonry Wall at an impact speed of 31 mi/h \pm 2.5 mi/h and an angle of 25 degrees \pm 1.5 degrees. The target impact point was the quarter point of the installation. The 2008 Dodge Ram 1500 pickup truck used in the test weighed 5039 lb and the actual impact speed and angle were 31.1 mi/h and 25.4 degrees, respectively. The actual impact point was 26 ft downstream of end of the wall.

TEST VEHICLE

A 2008 Dodge Ram 1500 pickup truck, shown in figure 2, was used for the crash test. Test inertia weight of the vehicle was 5039 lb, and its gross static weight was 5039 lb. The height to the lower edge of the vehicle front bumper was 13.75 inches, and the height to the upper edge of the front bumper was 25.375 inches. The height to the center of gravity was 28.0 inches. Additional information on the vehicle is provided in Attachment B.



Figure 1. Hawaii Masonry Wall prior to test 479070-1.



Figure 2. Test vehicle prior to test 479070-1.

SOIL AND/OR WEATHER CONDITIONS

The crash test was performed the morning of November 13, 2012. Weather conditions at the time of testing were: Wind speed: 6 mi/h; wind direction: 47 degrees with respect to the vehicle (vehicle was traveling in a southwesterly direction); temperature: 57°F; relative humidity: 36 percent.

BRIEF TEST DESCRIPTION

The 2008 Dodge Ram 1500 pickup truck, traveling at an impact speed of 31.1 mi/h, impacted the Hawaii Masonry Wall 26 ft downstream of the end of the wall at an impact angle of 25.4 mi/h. At 0.040 s after impact, the vehicle began to redirect, and at 0.048 s, the mortar cap on top of the wall began to crack in the horizontal direction and the right front tire blew out. The top row of stones began to deflect toward the field side at 0.062 s, and the mortar cap began to crack longitudinally at 0.079 s. As the vehicle continued forward, the stones continued to fall off to the field side, and as the vehicle exited the film, it remained in contact with the wall. The brakes on the vehicle were not applied and the vehicle came to rest 83.5 ft downstream of impact and adjacent to the traffic face of the wall. Sequential photographs of the test period are presented in Attachment C.

TEST ARTICLE/COMPONENT DAMAGE

A portion of the mortar cap (a length of 30 ft) and a portion of the first layer of rock (a length of 10 ft) was displaced toward the field side of the installation as shown in figure 3. .



Figure 3. Hawaii Masonry Wall after test 479070-1.

TEST VEHICLE DAMAGE

The right front upper and lower ball joints, right front tie rod end, and the right front spindle, rotor and caliper were deformed. Also damaged were the front bumper, right front fender, right front door, right rear door and the right front tire and wheel rim, as shown in figure 4. Maximum exterior crush to the vehicle was 9.0 inches. The floor pan was deformed 0.75 inch in the firewall/toe pan area in the front passenger position.




Figure 4. Test vehicle after test 479070-1.


OCCUPANT RISK VALUES

Data from the accelerometer, located at the vehicle center of gravity, were digitized for evaluation of occupant risk. In the longitudinal direction, the occupant impact velocity was 11.5 ft/s at 0.157 s, the highest 0.010-s occupant ridedown acceleration was 6.5 Gs from 0.262 to 0.272 s, and the maximum 0.050-s average acceleration was -5.1 Gs between 0.032 and 0.082 s. In the lateral direction, the occupant impact velocity was 10.2 ft/s at 0.157 s, the highest 0.010-s occupant ridedown acceleration was 4.5 Gs from 0.264 to 0.274 s, and the maximum 0.050-s average was -4.6 Gs between 0.032 and 0.082 s. Theoretical Head Impact Velocity (THIV) was 16.3 km/h or 4.5 m/s at 0.150 s; Post-Impact Head Decelerations (PHD) was 7.2 Gs between 0.262 and 0.272 s; and Acceleration Severity Index (ASI) was 0.68 between 0.032 and 0.082 s. These data and other pertinent information from the test are summarized in figure 5. Vehicle angular displacements and accelerations are shown graphically in Attachment D.

SUMMARY AND CONCLUSIONS

The Hawaii Masonry Wall contained and redirected the 2270P vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was not obtainable. A portion of the mortar cap and first layer of stones in a section of the wall broke off and were lying on the field side of the installation. This debris did not penetrate or show potential for penetrating the occupant compartment, or present hazard to others in the area. Maximum occupant compartment deformation was 0.75 inch in the firewall/toe pan area on the front passenger side. The 2270P vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 12 degrees and 4 degrees, respectively. Occupant risk factors were within the limits specified in *MASH*. The 2270P vehicle exited within the exit box.

The Hawaii Masonry Wall performed acceptably for *MASH* test 1-11, as shown in table 1.

**General Information**

Test Agency..... Texas A&M Transportation Institute (TTI)
 Test Standard Test No. AASHTO MASH 1-11
 Test Agency Test No. 479070-1
 Test Date 2012-11-13

Test Article

Type..... Longitudinal Barrier
 Name Hawaii Masonry Wall
 Installation Length 100 ft
 Material or Key Elements Cement rubble masonry
Soil Type and Condition..... Crushed Limestone, dry

Test Vehicle

Designation..... 2270P
 Model..... 2008 Dodge Ram 1500 pickup
 Mass
 Curb..... 4761 lb
 Test Inertial..... 5039 lb
 Dummy No dummy
 Gross Static..... 5039 lb

Impact Conditions

Speed31.1 mi/h
 Angle25.4 degrees
 Impact Location26 ft dwnstrm from end

Exit Conditions

SpeedOut of view
 AngleOut of view

Occupant Risk Values

Impact Velocity
 Longitudinal11.5 ft/s
 Lateral10.2 ft/s
 THIV16.3 km/h
 Ridedown Accelerations
 Longitudinal6.5 G
 Lateral4.5 G
 PHD7.2 G
 ASI0.68
 Max. 0.050-s Average
 Longitudinal-5.1 G
 Lateral-4.6 G
 Vertical2.8 G

Post-Impact Trajectory

Stopping Distance 83.5 ft dwnstrm
 Adjacent to wall

Vehicle Stability

Maximum Yaw Angle..... 22 degrees
 Maximum Pitch Angle..... 4 degrees
 Maximum Roll Angle 12 degrees
 Vehicle Snagging No
 Vehicle Pocketing No

Test Article Deflections

Dynamic Not Obtainable
 Permanent..... None
 Working Width 83.8 inches
 Vehicle Intrusion..... 26.8 inches

Vehicle Damage

VDS 01RFQ2
 CDC..... 01FREW2
 Max. Exterior Deformation..... 9.0 inches
 OCDI RF0010000
 Max. Occupant Compartment
 Deformation..... 0.75 inch

Figure 5. Summary of results for *MASH* test 1-11 on the Hawaii Masonry Wall.

Table 1. Performance evaluation summary for MASH test 1-11 on the Hawaii Masonry Wall.

Test Agency: Texas A&M Transportation Institute

Test No.: 479070-1


Test Date: 2012-11-13

NCHRP MASH Test 1-11 Evaluation Criteria	Test Results	Assessment
Structural Adequacy		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The Hawaii Masonry Wall contained and redirected the 2270P vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was not measureable.	Pass
Occupant Risk		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	A portion of the cap and first layer of stones in a section of the wall broke off and were lying on the field side of the installation. This debris did not penetrate or show potential for penetrating the occupant compartment, or present hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.3 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 0.75 inch in the firewall/toe pan area on the front passenger side.	Pass
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 2270P vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 12 degrees and 4 degrees, respectively.	Pass
H. <i>Longitudinal and lateral occupant impact velocities should fall below the preferred value of 29.5ft/s, or at least below the maximum allowable value of 39.4 ft/s.</i>	Longitudinal occupant impact velocity was 11.5 ft/s, and lateral occupant impact velocity was 10.2 ft/s.	Pass
I. <i>Longitudinal and lateral occupant ridedown accelerations should fall below the preferred value of 15.0 Gs, or at least below the maximum allowable value of 20.0 Gs.</i>	Longitudinal ridedown acceleration was 6.5 G, and lateral ridedown acceleration was 4.5 G.	Pass
Vehicle Trajectory		
<i>For redirective devices, the vehicle shall exit the barrier within the exit box (not less than 32.8 ft).</i>	The 2270P vehicle exited within the exit box.	Pass


ATTACHMENT A: TEST ARTICLE DETAILS

H:\479070 Hawaii Masonry Wall\Drafting\Hawaii Drawing



TEST INSTALLATION




ELEVATION VIEW



DETAIL A
SCALE 1 : 20

		Proving Ground - Roadside Safety and Physical Security Division		
Project	479070	Hawaii Masonry Wall		
Drawn By	GES	Scale 1:150	Sheet 1 of 2	Installation
Approved:		Date:		
Dean Alberson:				2012-09-03



CROSS-SECTION

2a. Georgetown Superflex, compacted to 90% of standard proctor density. Dimensions are approximate.
 2b. Limestone rock. Texture on drawing is for illustration only. See attachment for rock, mortar, and construction specifications. (Sections 5.01 - 5.03 apply for this test installation, disregard other sections regarding payment.)



Roadside Safety and
Physical Security Division -
Proving Ground

Project 479070	Hawaii Masonry Wall	2012-09-03
Drawn By GES	Scale 1:10	Sheet 2 of 2 Cross Section

T:\2012-2013\479070 Hawaii Masonry Wall\Drafting\Hawaii Drawing

SECTION 508 - CEMENT RUBBLE MASONRY

508.01 Description. This section describes constructing cement rubble masonry.

508.02 Materials.

Structural Concrete	601
Portland Cement	701.01
Fine Aggregate for Concrete	703.01
Water	712.01

Stones shall be clean, hard, sound, and durable. Except stones for filling voids, stones shall have thickness of not less than 6 inches and width of not less than 1-1/2 times the thickness, but not less than 12 inches. Except headers, stones shall have length of not less than 1-1/2 times its width.

Face stones shall have volume of not less than 0.75 cubic foot, and heart stones shall have volume of not less than 0.5 cubic foot.

Mortar shall consist of 1 part cement to 2 parts of fine aggregate or sand by volume. Water shall be added to make mortar easy to handle and spread with trowel. Mortar shall be prepared by mixing fine aggregate and cement in a tight container or mixing machine until mixture assumes uniform color. As mixing continues, water shall be added until proper consistency is attained. Mortar that has not been placed within 30 minutes after water has been added will be rejected. Retempering of mortar will not be allowed.

Mortar for pointing shall consist of 1 part cement to 1 part fine aggregate or sand by volume.

508.03 Construction. Excavate and backfill in accordance with Section 206 - Excavation and Backfill for Drainage Facilities.

Prepare foundation bed to be firm and normal to, or in steps normal to, face of wall. Compact foundation bed to minimum 90 percent compaction. Clean bearing surface of foundation masonry and adjust moisture to saturated, surface dry condition when mortar bed is spread. Clean and saturate stone with water before setting. Clean and moisten bed to receive mortar. Set face stones in random bond. Uniformly distribute stones by size, weathering, color, or texture. Use large stones at corners. Use large, flat stones for bottom courses. Use selected stones, roughly squared and pitched to lines at angles and ends of walls. Grade stones to decrease in size from bottom to top of work.

Bed stones fully in mortar. Overlap stones at joints at least 6 inches and form

508-1

508.03

firm bond.

Distribute headers uniformly throughout walls of structures to form at least 1/5 of exposed faces. Extend headers at least 12 inches through face wall into backing. Where wall is less than 24 inches in thickness, extend headers through wall from front face to back face.

Build interior of walls so stones are bonded without open spaces. Make horizontal joints in face not more than 1 inch in thickness and vertical joints not more than 2 inches in width. Bed face stones without spalls. Construct weep holes in wall where indicated in the contract documents. After mortar has set, loose stone and surrounding mortar shall be removed and relaid with fresh mortar.

Finish wall with 2-inch mortar capping. Mortar capping consists of 1 part cement to 2 parts fine aggregate or sand.

Use Class A concrete for copings and back walls. Make copings in sections. Extend at least full width of wall, not less than 8 inches thick, and in sections from 5 feet to 8 feet long. Cast-in-place or mold sections and set in full mortar beds.

After laying stones, clean exposed joints thoroughly of mortar to depth of 1 inch. Wet exposed joints and point with mortar for pointing. Cure pointed masonry and mortar capping for not less than 3 days after completion of wall.

508.04 Measurement. Cement rubble masonry will be paid on a lump sum basis. Measurement for payment will not apply.

508.05 Payment. The Engineer will pay for accepted cement rubble masonry on a contract lump sum basis. Payment will be full compensation for work prescribed in this section and the contract documents.

The Engineer will pay for the following pay item when included in the proposal schedule:

Pay Item	Pay Unit
Cement Rubble Masonry	Lump Sum

The Engineer will pay for excavation and backfill in accordance with and under Section 206 - Excavation and Backfill for Drainage Facilities.

END OF SECTION 508

508-2

ATTACHMENT B: TEST VEHICLE DETAILS

Table B1. Vehicle properties for test

Date: 2012-11-13 Test No.: 479070-1 VIN No.: 17DHA18N88537744
 Year: 2008 Make: Dodge Model: Ram 1500
 Tire Size: P265/70R17 Tire Inflation Pressure: 35 psi
 Tread Type: Highway Odometer: 117369

Note any damage to the vehicle prior to test: _____

- Denotes accelerometer location.

NOTES: _____

Engine Type: V-8
 Engine CID: 4.7 liter

Transmission Type:
☒ Auto or ☐ Manual
☐ FWD ☒ RWD ☐ 4WD

Optional Equipment: _____

Dummy Data:
 Type: No dummy
 Mass: _____
 Seat Position: _____

Geometry: inches

A	<u>78.25</u>	F	<u>36.00</u>	K	<u>20.50</u>	P	<u>2.88</u>	U	<u>28.50</u>
B	<u>75.00</u>	G	<u>28.00</u>	L	<u>29.12</u>	Q	<u>31.25</u>	V	<u>29.50</u>
C	<u>223.75</u>	H	<u>63.10</u>	M	<u>68.50</u>	R	<u>18.38</u>	W	<u>61.50</u>
D	<u>47.25</u>	I	<u>13.75</u>	N	<u>68.00</u>	S	<u>12.00</u>	X	<u>78.00</u>
E	<u>140.50</u>	J	<u>25.38</u>	O	<u>44.50</u>	T	<u>77.50</u>		<u>----</u>
Wheel Center Height Front		<u>14.75</u>	Wheel Well Clearance (Front)		<u>5.00</u>	Bottom Frame Height - Front		<u>17.125</u>	
Wheel Center Height Rear		<u>14.75</u>	Wheel Well Clearance (Rear)		<u>10.25</u>	Bottom Frame Height - Rear		<u>24.75</u>	

RANGE LIMIT: A=78 ±2 inches; C=237 ±13 inches; E=148 ±12 inches; F=39 ±3 inches; G = > 28 inches; H = 63 ±4 inches; O=43 ±4 inches; M+N/2=67 ±1.5 inches

GVWR Ratings:		Mass: lb	Curb	Test Inertial	Gross Static
Front	<u>3700</u>	M_{front}	<u>2822</u>	<u>2776</u>	<u>----</u>
Back	<u>3900</u>	M_{rear}	<u>1939</u>	<u>2263</u>	<u>----</u>
Total	<u>6700</u>	M_{Total}	<u>4761</u>	<u>5036</u>	<u>----</u>

(Allowable Range for TIM and GSM = 5000 lb ±110 lb)

Mass Distribution:

lb LF: 1389 RF: 1387 LR: 1110 RR: 1153




Table B2. Vehicle CG measurements for test 479070-1.

Date: 2012-11-13 Test No.: 479070-1 VIN: 17DHA18N88537744

Year: 2008 Make: Dodge Model: Ram 1500

Body Style: Quad Cab Mileage: 117369

Engine: 4.7 liter V-8 Transmission: Automatic

Fuel Level: Empty Ballast: 322 lb (440 lb max)

Tire Pressure: Front: 35 psi Rear: 35 psi Size: P265/70R17

Measured Vehicle Weights: (lb)

LF: 1389 RF: 1387 Front Axle: 2776

LR: 1110 RR: 1153 Rear Axle: 2263

Left: 2499 Right: 2540 Total: 5039

5000 ±110 lb allowed

Wheel Base: 140.5 inches Track: F: 68.5 inches R: 68 inches

148 ±12 inches allowed

Track = (F+R)/2 = 67 ±1.5 inches allowed

Center of Gravity, SAE J874 Suspension Method

X: 63.10 in Rear of Front Axle (63 ±4 inches allowed)

Y: 0.28 in Left - Right + of Vehicle Centerline

Z: 28 in Above Ground (minimum 28.0 inches allowed)

Hood Height: 44.50 inches Front Bumper Height: 25.375 inches

43 ±4 inches allowed

Front Overhang: 36.00 inches Rear Bumper Height: 29.125 inches

39 ±3 inches allowed

Overall Length: 223.75 inches

237 ±13 inches allowed

Table B3. Vehicle crush measurements for test 479070-1.

Date:	<u>2012-11-13</u>	Test No.:	<u>479070-1</u>	VIN No.:	<u>17DHA18N88537744</u>
Year:	2008	Make:	Dodge	Model:	Ram 1500

VEHICLE CRUSH MEASUREMENT SHEET¹

Complete When Applicable	
End Damage	Side Damage
Undeformed end width _____	Bowing: B1 _____ X1 _____
Corner shift: A1 _____	B2 _____ X2 _____
A2 _____	
End shift at frame (CDC)	Bowing constant
(check one)	$\frac{X1 + X2}{2} = \underline{\hspace{2cm}}$
< 4 inches _____	
≥ 4 inches _____	

Note: Measure C₁ to C₆ from Driver to Passenger side in Front or Rear impacts – Rear to Front in Side Impacts.

[illegible]

¹Table taken from National Accident Sampling System (NASS).

*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.

****Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).**




***Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

Table B4. Occupant compartment measurements for test 479070-1.

Date: 2012-11-13 Test No.: 479070-1 VIN No.: 17DHA18N88537744

Year: 2008 Make: Dodge Model: Ram 1500




*Lateral area across the cab from driver's side kickpanel to passenger's side kickpanel.


OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT

	Before (inches)	After (inches)
A1	64.50	64.50
A2	64.25	64.25
A3	65.00	65.00
B1	45.25	45.25
B2	39.12	39.12
B3	45.25	45.25
B4	42.12	42.12
B5	45.00	45.00
B6	42.12	42.12
C1	29.50	29.50
C2	----	----
C3	27.25	26.50
D1	12.75	12.75
D2	----	----
D3	11.50	11.50
E1	62.75	62.50
E2	64.50	64.12
E3	64.00	64.00
E4	64.50	64.50
F	60.00	60.00
G	60.00	60.00
H	39.00	39.00
I	39.00	39.00
J*	62.00	62.00


ATTACHMENT C: SEQUENTIAL PHOTOGRAPHS




0.000 s



0.075 s



0.150 s



0.225 s



Figure C1. Sequential photographs for test 479070-1 (overhead and frontal views).



0.300 s



0.450 s



0.600 s



0.750 s



Figure C1. Sequential photographs for test 479070-1
(overhead and frontal views) (continued).

Roll, Pitch, and Yaw Angles




Figure D1. Vehicle angular displacements for test 479070-1.




Figure D2. Longitudinal vehicle acceleration trace for test 479070-1 (accelerometer located at center of gravity).




Figure D3. Lateral vehicle acceleration trace for test 479070-1
(accelerometer located at center of gravity).




Figure D4. Vertical vehicle acceleration trace for test 479070-1
(accelerometer located at center of gravity).




Figure D5. Longitudinal vehicle acceleration trace for test 479070-1
(accelerometer located at rear of center of gravity).




Figure D6. Lateral vehicle acceleration trace for test 479070-1
(accelerometer located at rear of center of gravity).




Figure D7. Vertical vehicle acceleration trace for test 479070-1
(accelerometer located at rear of center of gravity).