



*Research Project Number SPR-1(17)M068
NDOT Sponsoring Agency Code RPFP-SG-05*

DEVELOPMENT AND TESTING OF A BRIDGE RAIL FOR LOW-VOLUME ROADS



Submitted by

Scott K. Rosenbaugh, M.S.C.E., E.I.T.
Research Engineer

Jacob A. DeLone, B.S.C.E., E.I.T.
Former Graduate Research Assistant

Ronald K. Faller, Ph.D., P.E.
MwRSF Director & Research Professor

Robert W. Bielenberg, M.S.M.E., E.I.T.
Research Engineer

MIDWEST ROADSIDE SAFETY FACILITY

Nebraska Transportation Center
University of Nebraska-Lincoln

Main Office

Prem S. Paul Research Center at Whittier School
Room 130, 2200 Vine Street
Lincoln, Nebraska 68583-0853
(402) 472-0965

Outdoor Test Site

4630 N.W. 36th Street
Lincoln, Nebraska 68524

Submitted to

NEBRASKA DEPARTMENT OF TRANSPORTATION

1500 Nebraska Highway 2
Lincoln, Nebraska 68502

MwRSF Research Report No. TRP-03-407-20

September 3, 2020

TECHNICAL REPORT DOCUMENTATION PAGE

| | | | |
|--|---|---|------------------|
| 1. Report No. TRP-03-407-20 | 2. Government Accession No. | 3. Recipient's Catalog No. | |
| 4. Title and Subtitle Development and Testing of a Bridge Rail for Low-Volume Roads | | 5. Report Date September 3, 2020 | |
| | | 6. Performing Organization Code | |
| 7. Author(s) Rosenbaugh, S.K., DeLone, J.A., Faller R.K., and Bielenberg, R.W. | | 8. Performing Organization Report No. TRP-03-407-20 | |
| 9. Performing Organization Name and Address Midwest Roadside Safety Facility (MwRSF) Nebraska Transportation Center University of Nebraska-Lincoln Main Office: Prem S. Paul Research Center at Whittier School Room 130, 2200 Vine Street Lincoln, Nebraska 68583-0853 Outdoor Test Site: 4630 NW 36th Street Lincoln, Nebraska 68524 | | 10. Work Unit No. | |
| | | 11. Contract SPR-1(17)-M098 | |
| 12. Sponsoring Agency Name and Address Nebraska Department of Transportation 1500 Nebraska Highway 2 Lincoln, Nebraska 68502 | | 13. Type of Report and Period Covered Final Report: 2017 – 2020 | |
| | | 14. Sponsoring Agency Code RPFP – SG-05 | |
| 15. Supplementary Notes Prepared in cooperation with U.S. Department of Transportation, Federal Highway Administration. | | | |
| 16. Abstract <p>A new steel bridge rail was developed for use on low-volume bridges. The railing consisted 31-in. tall, 12-gauge W-beam guardrail mounted on S3x5.7 posts, which were supported by steel square-tube sockets attached to the side of the bridge deck. The sockets were to be attached to the steel C-channel that is typically placed along the edges of rural bridge decks in the state of Nebraska. The bridge railing was developed for use on both 7-in. thick cast in place decks and 12-in. thick pre-stressed concrete beam slabs.</p> <p>Various welded and bolted socket-to-channel attachment designs were evaluated through dynamic bogie testing on both deck types. Posts were impacted both laterally and longitudinally to evaluate the strength of the attachments and the potential for deck damage during vehicle impacts. Upon reviewing the bogie testing results, the project sponsor selected the bolted attachment using embedded coupling nuts and threaded rods as the desired attachment design for full-scale testing.</p> <p>Full-scale crash testing was conducted according to test designation no. 2-11 of the American Association of State Highway Transportation Officials (AASHTO) <i>Manual for Assessing Safety Hardware (MASH 2016)</i>. The 2270P vehicle impacted the bridge rail at 25.5 degrees and 44.2 mph and was successfully contained and redirected. Damage to the bridge rail consisted of bent posts and deformed guardrail. No damage to the deck or sockets was observed. Thus, the tests passed all evaluation criteria of MASH 2016 test designation no. 2-11. The new railing was deemed MASH TL-2 crashworthy with a post spacing of 75 in. and MASH TL-3 crashworthy with a post spacing of 37.5 in. BARRIER VII simulations showed that the new railing could be directly connected to the Midwest Guardrail System (MGS) without a transition. Guidance was provided pertaining to the length of guardrail required adjacent to the bridge rail.</p> | | | |
| 17. Key Words Highway Safety, Crash Test, Bridge Rail, Compliance Test, MASH 2016, TL-2, TL-3, Side-Mounted, W-Beam, MGS, Low-Volume Roads, Guardrail | | 18. Distribution Statement No restrictions. This document is available through the National Technical Information Service. 5285 Port Royal Road, Springfield, VA 22161 | |
| 19. Security Classification (of this report) Unclassified | 20. Security Classification (of this page) Unclassified | 21. No. of Pages 307 | 22. Price |

DISCLAIMER STATEMENT

The contents of this report reflect the views of the authors, who are responsible for the facts and the accuracy of the information presented herein. The contents do not necessarily reflect the official views or policies neither of the Nebraska Department of Transportations nor the University of Nebraska-Lincoln. This report does not constitute a standard, specification, or regulation. Trade or manufacturers' names, which may appear in this report, are cited only because they are considered essential to the objectives of the report.

The United States (U.S.) government and the State of Nebraska do not endorse products or manufacturers. This material is based upon work supported by the Federal Highway Administration under SPR-1(17)M068. Any opinions, findings and conclusions or recommendations expressed in this publication are those of the author(s) and do not necessarily reflect the views of the Federal Highway Administration.”

UNCERTAINTY OF MEASUREMENT STATEMENT

The Midwest Roadside Safety Facility (MwRSF) has determined the uncertainty of measurements for several parameters involved in standard full-scale crash testing and non-standard testing of roadside safety features. Information regarding the uncertainty of measurements for critical parameters is available upon request by the sponsor and the Federal Highway Administration. Test nos. N2B-1 through N2B-6 were non-certified component tests conducted for research and development purposes only and are outside the scope of the MwRSF's A2LA Accreditation.

INDEPENDENT APPROVING AUTHORITY

The Independent Approving Authority for the data contained herein was Dr. Jennifer Rasmussen, Research Associate Professor.

ACKNOWLEDGEMENTS

The authors wish to acknowledge several sources that made a contribution to this project:
(1) Nebraska Department of Transportation for sponsoring the project and providing guidance;
and (2) MwRSF personnel for constructing the bridge rail and conducting the crash tests.

Acknowledgement is also given to the following individuals who contributed to the completion of this research project.

Midwest Roadside Safety Facility

J.D. Reid, Ph.D., Professor
J.C. Holloway, M.S.C.E., Research Engineer & Assistant Director –Physical Testing Division
K.A. Lechtenberg, M.S.M.E., E.I.T., Research Engineer
J.D. Rasmussen, Ph.D., P.E., Research Associate Professor
C.S. Stolle, Ph.D., E.I.T., Research Assistant Professor
J.S. Steelman, Ph.D., P.E., Associate Professor
M. Asadollahi Pajouh, Ph.D., P.E., Research Assistant Professor
A.T. Russell, B.S.B.A., Testing and Maintenance Technician II
E.W. Krier, B.S., Construction and Testing Technician II
S.M. Tighe, Construction and Testing Technician I
D.S. Charroin, Construction and Testing Technician I
R.M. Novak, Construction and Testing Technician I
T.C. Donahoo, Construction and Testing Technician I
J.T. Jones, Construction and Testing Technician I
J.E. Kohtz, B.S.M.E., CAD Technician
E.L. Urbank, B.A., Research Communication Specialist
Z.Z. Jabr, Engineering Technician
Undergraduate and Graduate Research Assistants

Nebraska Department of Transportation

Mark Traynowicz, P.E., State Bridge Engineer
Fouad Jaber, P.E., Assistant State Bridge Engineer
Phil TenHulzen, P.E., Design Standards Engineer
Jim Knott, P.E., State Roadway Design Engineer
Mark Osborn, P.E., Secondary Roads Engineer
Jodi Gibson, Research Coordinator
Mark Fischer, PE, PMP, Research Program Manager
Lieska Halsey, Research Project Manager

| SI* (MODERN METRIC) CONVERSION FACTORS | | | | |
|---|-----------------------------|----------------------------|-----------------------------|---------------------|
| APPROXIMATE CONVERSIONS TO SI UNITS | | | | |
| Symbol | When You Know | Multiply By | To Find | Symbol |
| LENGTH | | | | |
| in. | inches | 25.4 | millimeters | mm |
| ft | feet | 0.305 | meters | m |
| yd | yards | 0.914 | meters | m |
| mi | miles | 1.61 | kilometers | km |
| AREA | | | | |
| in ² | square inches | 645.2 | square millimeters | mm ² |
| ft ² | square feet | 0.093 | square meters | m ² |
| yd ² | square yard | 0.836 | square meters | m ² |
| ac | acres | 0.405 | hectares | ha |
| mi ² | square miles | 2.59 | square kilometers | km ² |
| VOLUME | | | | |
| fl oz | fluid ounces | 29.57 | milliliters | mL |
| gal | gallons | 3.785 | liters | L |
| ft ³ | cubic feet | 0.028 | cubic meters | m ³ |
| yd ³ | cubic yards | 0.765 | cubic meters | m ³ |
| NOTE: volumes greater than 1,000 L shall be shown in m ³ | | | | |
| MASS | | | | |
| oz | ounces | 28.35 | grams | g |
| lb | pounds | 0.454 | kilograms | kg |
| T | short ton (2,000 lb) | 0.907 | megagrams (or "metric ton") | Mg (or "t") |
| TEMPERATURE (exact degrees) | | | | |
| °F | Fahrenheit | 5(F-32)/9 or (F-32)/1.8 | Celsius | °C |
| ILLUMINATION | | | | |
| fc | foot-candles | 10.76 | lux | lx |
| fl | foot-Lamberts | 3.426 | candela per square meter | cd/m ² |
| FORCE & PRESSURE or STRESS | | | | |
| lbf | poundforce | 4.45 | newtons | N |
| lbf/in ² | poundforce per square inch | 6.89 | kilopascals | kPa |
| APPROXIMATE CONVERSIONS FROM SI UNITS | | | | |
| Symbol | When You Know | Multiply By | To Find | Symbol |
| LENGTH | | | | |
| mm | millimeters | 0.039 | inches | in. |
| m | meters | 3.28 | feet | ft |
| m | meters | 1.09 | yards | yd |
| km | kilometers | 0.621 | miles | mi |
| AREA | | | | |
| mm ² | square millimeters | 0.0016 | square inches | in ² |
| m ² | square meters | 10.764 | square feet | ft ² |
| m ² | square meters | 1.195 | square yard | yd ² |
| ha | hectares | 2.47 | acres | ac |
| km ² | square kilometers | 0.386 | square miles | mi ² |
| VOLUME | | | | |
| mL | milliliter | 0.034 | fluid ounces | fl oz |
| L | liters | 0.264 | gallons | gal |
| m ³ | cubic meters | 35.314 | cubic feet | ft ³ |
| m ³ | cubic meters | 1.307 | cubic yards | yd ³ |
| MASS | | | | |
| g | grams | 0.035 | ounces | oz |
| kg | kilograms | 2.202 | pounds | lb |
| Mg (or "t") | megagrams (or "metric ton") | 1.103 | short ton (2,000 lb) | T |
| TEMPERATURE (exact degrees) | | | | |
| °C | Celsius | 1.8C+32 | Fahrenheit | °F |
| ILLUMINATION | | | | |
| lx | lux | 0.0929 | foot-candles | fc |
| cd/m ² | candela per square meter | 0.2919 | foot-Lamberts | fl |
| FORCE & PRESSURE or STRESS | | | | |
| N | newtons | 0.225 | poundforce | lbf |
| kPa | kilopascals | 0.145 | poundforce per square inch | lbf/in ² |

*SI is the symbol for the International System of Units. Appropriate rounding should be made to comply with Section 4 of ASTM E380.

TABLE OF CONTENTS

| | |
|--|------|
| TECHNICAL REPORT DOCUMENTATION PAGE | i |
| DISCLAIMER STATEMENT | ii |
| UNCERTAINTY OF MEASUREMENT STATEMENT | ii |
| INDEPENDENT APPROVING AUTHORITY..... | ii |
| ACKNOWLEDGEMENTS | iii |
| SI* (MODERN METRIC) CONVERSION FACTORS | iv |
| TABLE OF CONTENTS..... | v |
| LIST OF FIGURES | viii |
| LIST OF TABLES | xv |
| 1 INTRODUCTION | 1 |
| 1.1 Problem Statement | 1 |
| 1.2 Background | 1 |
| 1.3 Objective | 3 |
| 1.4 Scope..... | 3 |
| 2 POST-TO-DECK CONNECTION DESIGNS | 5 |
| 2.1 Deck Configurations | 5 |
| 2.2 Socket and Post Sections | 9 |
| 2.3 Welded Socket Attachments | 10 |
| 2.4 Bolted Socket Attachments..... | 14 |
| 3 COMPONENT TESTING CONDITIONS | 16 |
| 3.1 Purpose..... | 16 |
| 3.2 Scope..... | 16 |
| 3.3 Equipment and Instrumentation..... | 44 |
| 3.3.1 Bogie Vehicle..... | 44 |
| 3.3.2 Accelerometers | 46 |
| 3.3.3 Retroreflective Optic Speed Trap | 46 |
| 3.3.4 Digital Photography | 46 |
| 3.4 End of Test Determination..... | 46 |
| 3.5 Data Processing..... | 47 |
| 4 COMPONENT TESTING RESULTS AND DISCUSSION | 48 |
| 4.1 Results..... | 48 |
| 4.1.1 Test No. N2B-1 | 48 |
| 4.1.2 Test No. N2B-2..... | 50 |
| 4.1.3 Test No. N2B-3..... | 52 |
| 4.1.4 Test No. N2B-4..... | 54 |

| | |
|---|-----|
| 4.1.5 Test No. N2B-5 | 56 |
| 4.1.6 Test No. N2B-6 | 58 |
| 4.2 Discussion | 60 |
| 5 DESIGN DETAILS | 67 |
| 5.1 Selection of Critical System Configurations for Testing | 67 |
| 5.2 Test Installation Details | 67 |
| 6 TEST REQUIREMENTS AND EVALUATION CRITERIA | 97 |
| 6.1 Test Requirements | 97 |
| 6.2 Evaluation Criteria | 98 |
| 6.3 Soil Strength Requirements | 99 |
| 7 TEST CONDITIONS | 100 |
| 7.1 Test Facility | 100 |
| 7.2 Vehicle Tow and Guidance System | 100 |
| 7.3 Test Vehicles | 100 |
| 7.4 Simulated Occupant | 105 |
| 7.5 Data Acquisition Systems | 105 |
| 7.5.1 Accelerometers | 105 |
| 7.5.2 Rate Transducers | 106 |
| 7.5.3 Retroreflective Optic Speed Trap | 106 |
| 7.5.4 Load Cells and String Potentiometers | 106 |
| 7.5.5 Digital Photography | 106 |
| 8 FULL-SCALE CRASH TEST NO. N2BR-1 | 109 |
| 8.1 Static Soil Test | 109 |
| 8.2 Weather Conditions | 109 |
| 8.3 Test Description | 109 |
| 8.4 Barrier Damage | 116 |
| 8.5 Vehicle Damage | 121 |
| 8.6 Occupant Risk | 125 |
| 8.7 Discussion | 126 |
| 9 BRIDGE RAIL TRANSITION TO MGS | 128 |
| 9.1 Background and Scope | 128 |
| 9.2 BARRIER VII Model | 128 |
| 9.2.1 Post Models | 129 |
| 9.2.2 Anchor Models | 129 |
| 9.2.3 W-Beam Guardrail Model | 130 |
| 9.2.4 Coefficient of Friction | 130 |
| 9.3 TL-2 Bridge Rail Model Verification | 131 |
| 9.4 MGS Model Validation | 139 |
| 9.4.1 Simulation of MGS at TL-3 | 139 |
| 9.4.2 Simulation of MGS with Missing Post at TL-3 | 139 |
| 9.5 Baseline TL-2 MGS Simulations | 140 |
| 9.6 Simulation of Transition from MGS to TL-2 Bridge Rail | 140 |

| | |
|--|-----|
| 10 MINIMUM GUARDRAIL LENGTH..... | 145 |
| 10.1 Background and Scope | 145 |
| 10.2 Length of Need to Shield Roadside Hazards | 145 |
| 10.3 Terminal Stroke Length | 145 |
| 10.4 Anchorage Requirements..... | 146 |
| 10.5 Compression Terminal Force Resistance..... | 146 |
| 11 SUMMARY, CONCLUSIONS, AND RECOMMENDATIONS | 149 |
| 12 REFERENCES | 171 |
| 13 APPENDICES | 174 |
| Appendix A. Bogie Test Material Specifications..... | 175 |
| Appendix B. Bogie Test Results | 207 |
| Appendix C. Full-Scale Test Material Specifications | 220 |
| Appendix D. Vehicle Center of Gravity Determination | 273 |
| Appendix E. Static Soil Tests..... | 275 |
| Appendix F. Vehicle Deformation Records..... | 278 |
| Appendix G. Accelerometer and Rate Transducer Data Plots, Test No. N2BR-1..... | 285 |
| Appendix H. Example Calculations for Minimum Installation Lengths | 302 |

LIST OF FIGURES

| | |
|---|----|
| Figure 1. MGS Bridge Rail Test Installation [3] | 2 |
| Figure 2. TxDOT T631 Test Installation [4-5] | 3 |
| Figure 3. Example Details for 7-in. Thick CIP Deck | 6 |
| Figure 4. Example Details for 12-in. Thick Precast Beam-Slab Deck | 7 |
| Figure 5. Short Channel Segments Used Within a 12-in. Thick Beam-Slab Deck | 8 |
| Figure 6. Post Assembly and Socket Tube from the MGS Bridge Rail | 10 |
| Figure 7. Post Flange Tearing adjacent to Post Standoffs | 10 |
| Figure 8. Socket Welded Directly to a 7-in. CIP Deck..... | 11 |
| Figure 9. Channel Flange Prying off Deck During Loading | 11 |
| Figure 10. Welded Socket Attachment with (a) Straight Bar Anchorage, (b) U-bar Anchorage, and (c) Gussets and Hook Bar Anchorage | 13 |
| Figure 11. Coupling Nut and Threaded Rod Attachment of Socket Assembly to Deck | 15 |
| Figure 12. Bogie Testing Matrix and Setup, 7-in. Thick Deck System Overview | 19 |
| Figure 13. Bogie Testing Matrix and Setup, 7-in. Thick Concrete Deck in Ground Details | 20 |
| Figure 14. Bogie Testing Matrix and Setup, 12-in. Thick Deck System Overview | 21 |
| Figure 15. Bogie Testing Matrix and Setup, 12-in. Thick Concrete Deck in Ground Details | 22 |
| Figure 16. Bogie Testing Matrix and Setup, 7-in. Thick Deck Reinforcement..... | 23 |
| Figure 17. Bogie Testing Matrix and Setup, 12-in. Thick Deck Reinforcement..... | 24 |
| Figure 18. Bogie Testing Matrix and Setup, Location “A” Deck Section and C-Channel Assembly A..... | 25 |
| Figure 19. Bogie Testing Matrix and Setup, Locations “B” and “C” Deck Section and C- Channel Assembly B..... | 26 |
| Figure 20. Bogie Testing Matrix and Setup, Location “D” Deck Section and C-Channel Assembly C | 27 |
| Figure 21. Bogie Testing Matrix and Setup, Location “E” Deck Section and C-Channel Assembly D..... | 28 |
| Figure 22. Bogie Testing Matrix and Setup, Location “F” Deck Section and C-Channel Assembly E | 29 |
| Figure 23. Bogie Testing Matrix and Setup, Location “G” Deck Section and C-Channel Assembly F | 30 |
| Figure 24. Bogie Testing Matrix and Setup, Location “H” Deck Section and C-Channel Assembly G..... | 31 |
| Figure 25. Bogie Testing Matrix and Setup, C-Channel Assembly Components | 32 |
| Figure 26. Bogie Testing Matrix and Setup, C-Channel Assembly Components | 33 |
| Figure 27. Bogie Testing Matrix and Setup, Post Assembly Details..... | 34 |
| Figure 28. Bogie Testing Matrix and Setup, Post Components..... | 35 |
| Figure 29. Bogie Testing Matrix and Setup, Socket Components..... | 36 |
| Figure 30. Bogie Testing Matrix and Setup, Socket Components..... | 37 |
| Figure 31. Bogie Testing Matrix and Setup, Deck Rebar Details | 38 |
| Figure 32. Bogie Testing Matrix and Setup, C-Channel Assembly Rebar Details..... | 39 |
| Figure 33. Bogie Testing Matrix and Setup, Hardware | 40 |
| Figure 34. Bogie Testing Bill of Materials | 41 |
| Figure 35. Bogie Testing Bill of Materials | 42 |
| Figure 36. Installation Photographs for the (a) 7-in. CIP Deck and (b) 12-in. Precast Beam- Slab | 43 |

| | |
|--|-----|
| Figure 37. Bogie Vehicle with (a) Lateral Impact Head and (b) Longitudinal Impact Head | 45 |
| Figure 38. Time-Sequential and Post-Impact Photographs, Test No. N2B-1 | 49 |
| Figure 39. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-1 | 50 |
| Figure 40. Time-Sequential and Post-Impact Photographs, Test No. N2B-2..... | 51 |
| Figure 41. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-2..... | 52 |
| Figure 42. Time-Sequential and Post-Impact Photographs, Test No. N2B-3..... | 53 |
| Figure 43. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-3..... | 54 |
| Figure 44. Time-Sequential and Post-Impact Photographs, Test No. N2B-4..... | 55 |
| Figure 45. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-4..... | 56 |
| Figure 46. Time-Sequential and Post-Impact Photographs, Test No. N2B-5..... | 57 |
| Figure 47. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-5..... | 58 |
| Figure 48. Time-Sequential and Post-Impact Photographs, Test No. N2B-6..... | 59 |
| Figure 49. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-6..... | 60 |
| Figure 50. Strong Axis, 90-Degree Impacts, Force vs. Deflection Comparison | 63 |
| Figure 51. Strong Axis, 90-Degree Impacts, Energy vs Displacement Comparison..... | 64 |
| Figure 52. Weak Axis, 0-Degree Impacts, Force vs. Deflection Comparison..... | 65 |
| Figure 53. Weak Axis, 0-Degree Impacts, Energy vs Displacement Comparison | 66 |
| Figure 54. Test Installation Layout, Test No. N2BR-1..... | 69 |
| Figure 55. Bridge Deck Cross Section, Test No. N2BR-1 | 70 |
| Figure 56. Concrete Deck Assembly Details, Test No. N2BR-1..... | 71 |
| Figure 57. Concrete Deck Reinforcement, Test No. N2BR-1 | 72 |
| Figure 58. C-Channel and Post Socket Component Details, Test No. N2BR-1 | 73 |
| Figure 59. C-Channel Assembly Details, Test No. N2BR-1 | 74 |
| Figure 60. Deck C-Channel, Test No. N2BR-1 | 75 |
| Figure 61. Deck Reinforcement, Test No. N2BR-1..... | 76 |
| Figure 62. Post Socket Assembly, Test No. N2BR-1 | 77 |
| Figure 63. Plate Washer and Post Socket Components, Test No. N2BR-1 | 78 |
| Figure 64. Bridge Post Assembly and Components, Test No. N2BR-1 | 79 |
| Figure 65. Splice and Post Detail, Test No. N2BR-1 | 80 |
| Figure 66. End Section Details, Test No. N2BR-1 | 81 |
| Figure 67. BCT Anchor Details, Test No. N2BR-1..... | 82 |
| Figure 68. Line Post Components, Test No. N2BR-1 | 83 |
| Figure 69. Foundation Tube and BCT Timber Post Details, Test No. N2BR-1 | 84 |
| Figure 70. BCT Anchor Cable and Load Cell Detail, Test No. N2BR-1 | 85 |
| Figure 71. Modified BCT Anchor Cable, Test No. N2BR-1 | 86 |
| Figure 72. Shackle and Eye Nut Detail, Test No. N2BR-1 | 87 |
| Figure 73. BCT Post Components and Anchor Bracket, Test No. N2BR-1..... | 88 |
| Figure 74. Ground Strut and Bearing Plate, Test No. N2BR-1 | 89 |
| Figure 75. Rail Section Details, Test No. N2BR-1..... | 90 |
| Figure 76. System Hardware, Test No. N2BR-1 | 91 |
| Figure 77. System Hardware, Test No. N2BR-1 | 92 |
| Figure 78. Bill of Materials, Test No. N2BR-1 | 93 |
| Figure 79. Bill of Materials, Test No. N2BR-1 | 94 |
| Figure 80. Bill of Materials, Test No. N2BR-1 | 95 |
| Figure 81. Test Installation Photographs, Test No. N2BR-1 | 96 |
| Figure 82. Test Vehicle, Test No. N2BR-1 | 101 |
| Figure 83. Vehicle Floor Pan and Undercarriage Prior to Test No. N2BR-1 | 102 |

| | |
|--|-----|
| Figure 84. Vehicle Dimensions, Test No. N2BR-1 | 103 |
| Figure 85. Target Geometry, Test No. N2BR-1 | 104 |
| Figure 86. Camera Location Diagram, Test No. N2BR-1 | 107 |
| Figure 87. Impact Location, Test No. N2BR-1 | 110 |
| Figure 88. Sequential Photographs, Test No. N2BR-1 | 112 |
| Figure 89. Additional Sequential Photographs, Test No. N2BR-1 | 113 |
| Figure 90. Documentary Photographs, Test No. N2BR-1 | 114 |
| Figure 91. Vehicle Trajectory Marks and Final Position, Test No. N2BR-1 | 115 |
| Figure 92. System Damage, Test No. N2BR-1 | 117 |
| Figure 93. System Damage, Front-Side Views, Test No. N2BR-1 | 118 |
| Figure 94. System Damage, Back-Side Views, Test No. N2BR-1 | 119 |
| Figure 95. System Damage, Post Bending and Tearing, Test No. N2BR-1 | 120 |
| Figure 96. Vehicle Damage, Test No. N2BR-1 | 122 |
| Figure 97. Vehicle Undercarriage Damage, Test No. N2BR-1 | 123 |
| Figure 98. Vehicle Interior Damage, Test No. N2BR-1 | 124 |
| Figure 99. Summary of Test Results and Sequential Photographs, Test No. N2BR-1 | 127 |
| Figure 100. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1 | 132 |
| Figure 101. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1 | 133 |
| Figure 102. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1 | 134 |
| Figure 103. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1 | 135 |
| Figure 104. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1 | 136 |
| Figure 105. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1 | 137 |
| Figure 106. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1 | 138 |
| Figure 107. Model of Test No. N2BR-1 Post Nos. 1 through 13 | 142 |
| Figure 108. Model of Test No. N2BR-1 Post Nos. 13 through 25 | 143 |
| Figure 109. Model of Test No. N2BR-1 Post Nos. 25 through 37 | 144 |
| Figure 110. Separation of Manufacturer Specified End Terminal Stroke Length and Bridge Rail | 146 |
| Figure 111. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 1, Cross Section | 154 |
| Figure 112. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 1, Channel Assembly | 155 |
| Figure 113. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 1, Embedded Anchorage | 156 |
| Figure 114. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 1, Post Assembly | 157 |
| Figure 115. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 1, Socket Assembly | 158 |
| Figure 116. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 2, Cross Section | 159 |
| Figure 117. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 2, Channel Assembly | 160 |
| Figure 118. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 2, Embedded Anchorage | 161 |
| Figure 119. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 2, Post Assembly | 162 |

| | |
|---|-----|
| Figure 120. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 2, Socket Assembly..... | 163 |
| Figure 121. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 3, Cross Section..... | 164 |
| Figure 122. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 3, Channel Assembly | 165 |
| Figure 123. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 3, Embedded Anchorage..... | 166 |
| Figure 124. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 3, Post Assembly..... | 167 |
| Figure 125. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 3, Socket Assembly..... | 168 |
| Figure 126. Details for 20-in. Long C7x9.8 Channel Assembly for Use on 7-in. CIP decks..... | 169 |
| Figure 127. Details for 20-in. Long C12x20.7 Channel Assembly for Use on 12-in. CIP decks | 170 |
| Figure A-1. Concrete, Test Nos. N2B-1 through N2B-6..... | 178 |
| Figure A-2. C7x9.8, 36-in. Long C-Channel, Test Nos. N2B-1 through N2B-6 | 179 |
| Figure A-3. C7x12.25, 36-in. Long C-Channel, Test Nos. N2B-1 through N2B-6 | 180 |
| Figure A-4. C7x20.7, 36-in. Long C-Channel, Test Nos. N2B-1 through N2B-6 | 181 |
| Figure A-5. 10-in. x 2¾-in. x ¼-in. Plate Washer, Test Nos. N2B-1 through N2B-6..... | 182 |
| Figure A-6. 2-in. x 2-in. x ¼-in. Gusset, Test Nos. N2B-1 through N2B-6 | 183 |
| Figure A-7. HSS4x4x¾ Square Tube, Test Nos. N2B-1 through N2B-6..... | 184 |
| Figure A-8. ½-in. Thick Steel Plate, Test Nos. N2B-1 through N2B-6..... | 185 |
| Figure A-9. S3x5.7 Steel Post, Test Nos. N2B-1 through N2B-6 | 186 |
| Figure A-10. 2¾-in. x 1-in. x ¼-in. Post, Test Nos. N2B-1 through N2B-6 | 187 |
| Figure A-11. ⅝-in. Dia., 5-in. Long Heavy Hex Head Bolt, Test Nos. N2B-1 through N2B-6..... | 188 |
| Figure A-12. ⅝-in. Dia. 5-in. Long Heavy Hex Head Nut, Test Nos. N2B-1 through N2B-6.... | 189 |
| Figure A-13. ¾-in. Dia. 1¾-in. Long Heavy Hex Head Bolt, Test Nos. N2B-1 through N2B-6..... | 190 |
| Figure A-14. ¾-in. Dia. Heavy Hex Coupling Nut, Test Nos. N2B-1 through N2B-6 | 191 |
| Figure A-15. ¾-in. Dia. 30-in. Long Threaded Rod, Test Nos. N2B-1 through N2B-6 | 192 |
| Figure A-16. ⅞-in. Dia. 2-in. Long Heavy Hex Head Bolt, Test Nos. N2B-1 through N2B-6...193 | |
| Figure A-17. ⅞-in. Dia. Hex Coupling Nut, Test Nos. N2B-1 through N2B-6..... | 194 |
| Figure A-18. ⅞-in. Dia. 30-in. Long Threaded Rod, Test Nos. N2B-1 through N2B-6 | 195 |
| Figure A-19. 1-in. Dia. 2-in. Long Heavy Hex Head Bolt, Test Nos. N2B-1 through N2B-6....196 | |
| Figure A-20. 1-in. Dia. Heavy Hex Coupling Nut, Test Nos. N2B-1 through N2B-6 | 197 |
| Figure A-21. 1-in. Dia. Heavy Hex Nut, Test Nos. N2B-1 through N2B-6..... | 198 |
| Figure A-22. 1-in. Dia. 24-in. Long Threaded Rod, Test Nos. N2B-1 through N2B-6 | 199 |
| Figure A-23. 1-in. Dia. Hardened Flat Washer, Test Nos. N2B-1 through N2B-6 | 200 |
| Figure A-24. ⅞-in. Dia. Hardened Flat Washer, Test Nos. N2B-1 through N2B-6 | 201 |
| Figure A-25. ¾-in. Dia. Hardened Flat Washer, Test Nos. N2B-1 through N2B-6 | 202 |
| Figure A-26. No. 4 Rebar Mill Certification, Test Nos. N2B-1 through N2B-6..... | 203 |
| Figure A-27. No. 3 Rebar Mill Certification, Test Nos. N2B-1 through N2B-6..... | 204 |
| Figure A-28. No. 8 Rebar Mill Certification, Test Nos. N2B-1 through N2B-6..... | 205 |
| Figure A-29. No. 4 Rebar Mill Certification, Test Nos. N2B-1 through N2B-6..... | 206 |
| Figure B-1. Test No. N2B-1 Results (SLICE-1)..... | 208 |

| | |
|--|-----|
| Figure B-2. Test No. N2B-1 Results (SLICE-2)..... | 209 |
| Figure B-3. Test no. N2B-2 Results (SLICE-1) | 210 |
| Figure B-4. Test No. N2B-2 Results (SLICE-2)..... | 211 |
| Figure B-5. Test No. N2B-3 Results (SLICE-1)..... | 212 |
| Figure B-6. Test No. N2B-3 Results (SLICE-2)..... | 213 |
| Figure B-7. Test No. N2B-4 Results (SLICE-1)..... | 214 |
| Figure B-8. Test No. N2B-4 Results (SLICE-2)..... | 215 |
| Figure B-9. Test No. N2B-5 Results (SLICE-1)..... | 216 |
| Figure B-10. Test No. N2B-5 Results (SLICE-2)..... | 217 |
| Figure B-11. Test No. N2B-6 Results (SLICE-1)..... | 218 |
| Figure B-12. Test No. N2B-6 Results (SLICE-2)..... | 219 |
| Figure C-1. 6-ft 3-in. 12-Gauge W-Beam MGS Section Material Certification, Test No. N2BR-1 | 224 |
| Figure C-2. 12-ft 6-in. 12-Gauge W-Beam MGS Section Material Certification, Test No. N2BR-1 | 225 |
| Figure C-3. 12-ft 6-in. 12-Gauge W-Beam MGS End Section Material Certification, Test No. N2BR-1 | 226 |
| Figure C-4. 72-in. Long Foundation Tube Material Certification, Test No. N2BR-1 | 227 |
| Figure C-5. BCT Timber Post – MGS Height, Test No. N2BR-1 | 228 |
| Figure C-6. W6x8.5, 72-in. Long Steel Post Certificate of Compliance, Test No. N2BR-1 | 229 |
| Figure C-7. 6-in. x 12-in. x 14¼-in. Timber Blockouts for Steel Posts Certificates of Compliance, Test No. N2BR-1 | 230 |
| Figure C-8. 2¾-in. x 1-in. x ¼-in. Post Standoff Mill Certification, Test No. N2BR-1 | 231 |
| Figure C-9. S3x5.7 Post Mill Certification, Test No. N2BR-1 Mill Certification, Test No. N2BR-1 | 232 |
| Figure C-10. 10-in. x 7-in. x ½-in. Steel Plate Mill Certification, Test No. N2BR-1 | 233 |
| Figure C-11. 10-in. x 2¾-in. x ¼-in. Plate Washer Mill Certification, Test No. N2BR-1 | 234 |
| Figure C-12. HSS4x4x¾, 6⅝-in. Long Square Tube Mill Certification, Test No. N2BR-1 | 235 |
| Figure C-13. 3½-in. x 1-in. x ⅛-in. Plate Mill Certification, Test No. N2BR-1 | 236 |
| Figure C-14. C7x9.8, 225-in. Long C-Channel Mill Certification, Test No. N2BR-1 | 237 |
| Figure C-15. 6⅝-in. x 2-in. x ⅛-in. Shim Plate Mill Certification, Test No. N2BR-1 | 238 |
| Figure C-16. No. 4 Rebar Mill Certification, Test No. N2BR-1 | 239 |
| Figure C-17. No. 4 Rebar Mill Certification, Test No. N2BR-1 | 240 |
| Figure C-18. No. 4 Rebar Mill Certification, Test No. N2BR-1 | 241 |
| Figure C-19. No. 4 Rebar Mill Certification, Test No. N2BR-1 | 242 |
| Figure C-20. ⅝-in. Dia. 14-in. Long Bolt Mill Certification, Test No. N2BR-1 | 243 |
| Figure C-21. ⅝-in. Dia. 10-in. Long Bolt Certificate of Compliance, Test No. N2BR-1 | 244 |
| Figure C-22. ⅝-in. Dia. 1¼-in. Long Heavy Hex Head Bolt Certificate of Conformance, Test No. N2BR-1 | 245 |
| Figure C-23. ⅝-in. Dia. 1¼-in. Long Heavy Hex Head Nut Certificate of Conformance, Test No. N2BR-1 | 246 |
| Figure C-24. ⅝-in. Dia. 5-in. Long Heavy Hex Head Bolt Material Certification, Test No. N2BR-1 | 247 |
| Figure C-25. ⅝-in. Dia. 5-in. Long Heavy Hex Head Nut Material Certification, Test No. N2BR-1 | 248 |
| Figure C-26. ⅞-in. 24-in. Long Threaded Material Certification, Test No. N2BR-1 | 249 |

| | |
|--|-----|
| Figure C-27. 7/8-in. Dia. 2-in. Long Heavy Hex Head Bolt Material Certification, Test No. N2BR-1 | 250 |
| Figure C-28. 7/8-in. Diameter Heavy Hex Coupling Nut Certificate of Conformance, Test No. N2BR-1 | 251 |
| Figure C-29. 7/8-in. Diameter Heavy Hex Nut Material Certification, Test No. N2BR-1..... | 252 |
| Figure C-30. 1-in. Diameter Hex Nut Material Certification, Test No. N2BR-1 | 253 |
| Figure C-31. 5/8-in. Dia. Hex Nut Certificate of Conformance, Test No. N2BR-1 | 254 |
| Figure C-32. 7/8-in. Dia. 8-in. Long Hex Head Bolt and Nut Certificate of Compliance, Test No. N2BR-1 | 255 |
| Figure C-33. 5/8-in. Dia. 1½-in. Long Hex Head Bolt Certificate of Conformance, Test No. N2BR-1 | 256 |
| Figure C-34. 5/16-in. 1¼-in. Long Hex Head Bolt Material Certification, Test No. N2BR-1 | 257 |
| Figure C-35. 5/16-in. Hex Nut Material Certification, Test No. N2BR-1 | 258 |
| Figure C-36. 16D Double Head Nail Certificate of Compliance, Test No. N2BR-1 | 259 |
| Figure C-37. 1¾-in. x 1¾-in. x ½-in. Square Washer, Test No. N2BR-1 | 260 |
| Figure C-38. 7/8-in. Diameter Plain Round Washer Certificate of Compliance, Test No. N2BR-1 | 261 |
| Figure C-39. 7/8-in. Diameter Hardened Flat Washer Material Certification, Test No. N2BR-1 | 262 |
| Figure C-40. BCT Anchor Cable End Swaged Fitting and ¾-in. Diameter 6x19 24½-in. Long IWRC IPS Wire Rope Material Certification, Test No. N2BR-1 | 263 |
| Figure C-41. 8-in. x 8-in. x 5/8-in. Anchor Bearing Plate Material Certification, Test No. N2BR-1 | 264 |
| Figure C-42. 2¾-in. O.D. x 6-in. Long BCT Post Sleeve Material Certification, Test No. N2BR-1 | 265 |
| Figure C-43. Anchor Bracket Assembly Material Certification, Test No. N2BR-1..... | 266 |
| Figure C-44. Ground Strut Assembly Material Certification, Test No. N2BR-1 | 267 |
| Figure C-45. Concrete Deck Material, Test No. N2BR-1 | 268 |
| Figure C-46. Concrete Deck Material, Test No. N2BR-1 | 269 |
| Figure C-47. Grade Beam Concrete, Test No. N2BR-1 | 270 |
| Figure C-48. Concrete Grade Beam Material Certification, Test No. N2BR-1 | 271 |
| Figure C-49. Concrete Deck Material Certification, Test No. N2BR-1 | 272 |
| Figure D-1. Vehicle Mass Distribution, Test No. N2BR-1 | 274 |
| Figure E-1. Soil Strength, Initial Calibration Tests | 276 |
| Figure E-2. Static Soil Test, Test No. N2BR-1..... | 277 |
| Figure F-1. Floor Pan Deformation Data – Set 1, Test No. N2BR-1 | 279 |
| Figure F-2. Floor Pan Deformation Data – Set 2, Test No. N2BR-1 | 280 |
| Figure F-3. Occupant Compartment Deformation Data – Set 1, Test No. N2BR-1..... | 281 |
| Figure F-4. Occupant Compartment Deformation Data – Set 2, Test No. N2BR-1..... | 282 |
| Figure F-5. Exterior Vehicle Crush (NASS) - Front, Test No. N2BR-1 | 283 |
| Figure F-6. Exterior Vehicle Crush (NASS) - Side, Test No. N2BR-1 | 284 |
| Figure G-1. Longitudinal CFC-180 10-msec Extracted Average Acceleration (SLICE-1), Test No. N2BR-1 | 286 |
| Figure G-2. Longitudinal Change in Velocity (SLICE-1), Test No. N2BR-1..... | 287 |
| Figure G-3. Longitudinal Change in Displacement (SLICE-1), Test No. N2BR-1 | 288 |
| Figure G-4. Lateral CFC-180 10-msec Extracted Average Acceleration (SLICE-1), Test No. N2BR-1 | 289 |

| | |
|---|-----|
| Figure G-5. Lateral Change in Velocity (SLICE-1), Test No. N2BR-1 | 290 |
| Figure G-6. Lateral Change in Displacement (SLICE-1), Test No. N2BR-1 | 291 |
| Figure G-7. Vehicle Angular Displacements (SLICE-1), Test No. N2BR-1 | 292 |
| Figure G-8. Acceleration Severity Index (SLICE-1), Test No. N2BR-1..... | 293 |
| Figure G-9. 10-ms Average Longitudinal Deceleration (DTS), Test No. N2BR-1..... | 294 |
| Figure G-10. Longitudinal Occupant Impact Velocity (DTS), Test No. N2BR-1 | 295 |
| Figure G-11. Longitudinal Occupant Displacement (DTS), Test No. N2BR-1 | 296 |
| Figure G-12. 10-ms Average Lateral Deceleration (DTS), Test No. N2BR-1 | 297 |
| Figure G-13. Lateral Occupant Impact Velocity (DTS), Test No. N2BR-1 | 298 |
| Figure G-14. Lateral Occupant Displacement (DTS), Test No. N2BR-1 | 299 |
| Figure G-15. Vehicle Angular Displacements (DTS), Test No. N2BR-1 | 300 |
| Figure G-16. Acceleration Severity Index (DTS), Test No. N2BR-1 | 301 |

LIST OF TABLES

| | |
|---|-----|
| Table 1. Component Testing Details | 18 |
| Table 2. Dynamic Testing Results | 62 |
| Table 3. MASH 2016 TL-2 Crash Test Conditions for Longitudinal Barriers..... | 97 |
| Table 4. MASH 2016 Evaluation Criteria for Longitudinal Barriers | 98 |
| Table 5. Camera Locations, Speeds, and Lens Settings, Test No. N2BR-1 | 108 |
| Table 6. Weather Conditions, Test No. N2BR-1 | 109 |
| Table 7. Sequential Description of Impact Events, Test No. N2BR-1 | 111 |
| Table 8. Maximum Occupant Compartment Deformations by Location, Test No. N2BR-1 | 125 |
| Table 9. Summary of OIV, ORA, THIV, PHD, and ASI Values, Test No. N2BR-1 | 126 |
| Table 10. BARRIER VII Post Input Parameters | 129 |
| Table 11. BARRIER VII Anchor Post Input Parameters | 130 |
| Table 12. Adjusted W-beam Properties in BARRIER VII | 130 |
| Table 13. Comparison of BARRIER VII Results to Test No. N2BR-1 | 131 |
| Table 14. Comparison of BARRIER VII Results to Test No. ILT-1 | 139 |
| Table 15. Comparison of BARRIER VII Results to Test no. MGSMP-1 | 140 |
| Table 16. BARRIER VII Maximum Pocketing Angles, Displacements, and Forces..... | 141 |
| Table 17. TL-2 Bridge Rail and MGS Post Compressive Capacity Loads | 147 |
| Table 18. End Terminal Average Compressive Forces [27]..... | 148 |
| Table 19. Summary of Safety Performance Evaluation..... | 153 |
| Table A-1. Bill of Materials, Test Nos. N2B-1 through N2B-6 | 176 |
| Table A-2. Bill of Materials, Test Nos. N2B-1 through N2B-6, Cont. | 177 |
| Table C-1. Bill of Materials, Test No. N2BR-1..... | 221 |
| Table C-2. Bill of Materials, Test No. N2BR-1, Cont..... | 222 |
| Table C-3. Bill of Materials, Test No. N2BR-1, Cont..... | 223 |

1 INTRODUCTION

1.1 Problem Statement

In 2016, the Nebraska State Legislature passed bill LB960 to adopt the Transportation Innovation Act. A portion of this act created a voluntary county bridge match assistance program intended to aid Nebraska counties in replacing deteriorated bridges. This program was targeted for the numerous bridges located on rural, low-volume roadways that needed immediate attention. With the replacement of these bridges, new bridge rails and approach guardrail systems were also necessary to ensure the safety of the motoring public.

Due to the large number of deficient bridges slated for replacement, these new bridges needed to be constructed in a timely and cost-efficient manner. It was also desired that the associated bridge railings be optimized to minimize costs while satisfying current safety standards. Additionally, side-mounted bridge rails were desired to maximize the traversable width of the bridge, and the bridge railings needed to prevent damage to the deck during an impact event to prevent costly repairs. For convenience, one bridge rail design was desired to treat all future installation sites for these rural bridges. Due to the low traffic volume associated with these bridges (50 – 500 average daily traffic (ADT)), a bridge railing that satisfied the Test Level 2 (TL-2) performance criteria of the 2016 edition of the *Manual for Assessing Safety Hardware* (MASH 2016) [1] was warranted rather than using more expensive TL-3 systems typically used on higher-speed, higher-volume roadways. Thus, a new MASH 2016 TL-2 bridge rail was desired to provide an economical treatment for rural, low volume roads.

1.2 Background

National Cooperative Highway Research Program (NCHRP) project 22-12(03) recently provided guidelines for the selection of bridge rails based on roadway characteristics such as traffic volume, percentage of heavy trucks, speed, lane width, curvature, and perceived risk of a railing failure [2]. In general terms, it was found that a TL-2 system would be warranted for nearly all roadways with a traffic volume less than 1,000 vehicles per day due to the low risk of vehicle encroachment. TL-1 barriers were not considered in the NCHRP analysis. However, the cost difference between a TL-1 and a TL-2 system is often minimal. Thus, bridges located on rural, low-volume roadways would likely warrant a TL-2 bridge railing.

Two W-beam bridge rails have previously been designed for use on low volume roads that satisfy MASH TL-2 and TL-3 safety standards. Both systems utilized a 31-in. tall W-beam rail supported by S3x5.7 weak posts, thereby limiting both the loads transferred to the bridge deck and the associated risk for deck damage. The first system, the Midwest Guardrail System (MGS) Bridge Rail, was a MASH TL-3 side-mounted system that was supported by steel sockets placed adjacent to the side of the deck [3], as shown in Figure 1. The system utilized a 37.5-in. post spacing, and the sockets were attached to the bridge deck with a 1-in. diameter bolt that went through the thickness of the deck. A steel angle was mounted below the deck to provide additional length for the force couple which resisted post bending. The system was full-scale crash tested according to MASH test designation nos. 3-10 and 3-11 with a small car and pickup truck, respectively.



Figure 1. MGS Bridge Rail Test Installation [3]

Texas Department of Transportation's (TxDOT) T631 bridge rail was mounted to the top of the bridge deck with a $\frac{5}{8}$ -in. thick base plate bolted to the top of the bridge deck with four $\frac{5}{8}$ -in. diameter bolts [4-5], as shown in Figure 2. The posts were welded to the base plates with continuous $\frac{1}{4}$ -in. thick fillet welds. The system satisfied MASH TL-2 criteria and was successfully tested under MASH test designation nos. 2-10 and 2-11 with a 75-in. post spacing. A modified version of the system with a 37.5-in. post spacing was also crash tested and satisfied MASH TL-3 criteria. MASH test designation no. 3-11 was conducted on the system with a 75-in. post spacing, but the test resulted in failure due to rail tearing. Thus, the 75-in. post spacing is only crashworthy at MASH TL-2.



Figure 2. TxDOT T631 Test Installation [4-5]

These existing systems required attachment hardware on the top surface of the bridge deck. However, it was believed that a similar system could be developed with the posts and attachment hardware only on the side of the deck, such that the top surface of the deck remained clear of obstructions.

1.3 Objective

The research objectives for this project included the development and full-scale crash testing of a TL-2 bridge railing for use on rural, low-volume roadways. The bridge railing was to be compatible with both 7-in. thick cast-in-place (CIP) decks and 12-in. thick precast beam slabs, and the system needed to limit damage to the bridge deck during impact events. A railing incorporating side-mounted posts was desired to limit encroachment of the system over the bridge deck and maximize the traversable width of the bridge. A detailed analysis of the required length of need was required to identify the minimum length of the guardrail adjacent to the bridge and limit the total installation costs. All crash testing was to be conducted and reported according to the TL-2 safety requirements found in MASH 2016.

1.4 Scope

The development of the optimized MASH 2016 TL-2 bridge rail began with a literature review of previous crash-tested W-beam bridge rails evaluated according to MASH TL-2 and TL-3 were reviewed. The performance of various post attachment designs and anchorage to concrete bridge decks were a focus of this review.

Following this review, multiple design concepts were developed for attaching guardrail support posts to the concrete bridge decks. Efforts were made to mount the posts to the side of the bridge deck, leaving the top surface of the deck clear of any attachment hardware. Several design concepts were then selected for evaluation through dynamic component testing. Simulated bridge decks were constructed, and guardrail posts were mounted to the simulated deck utilizing the selected attachment designs. Each attachment design was subjected to both lateral and longitudinal impacts from a bogie vehicle to evaluate both the strong- and weak-axis performance of the post and anchorage assembly. Evaluations focused on both the strength of the post assembly as well as the damage imparted to the deck. Results from the dynamic bogie testing guided the selection of a bridge rail concept for further evaluation through full-scale crash testing in accordance with MASH TL-2 criteria.

Although MASH 2016 specifies two full-scale crash tests to satisfy TL-2 safety criteria, the greater mass of the 2270P pickup truck was expected to produce higher rail loads and system deflections than the 1100C small car. Additionally, two similar systems had previously been successfully crash tested with the 1100C vehicle, as discussed in Section 1.2. Therefore, test designation no. 2-10 with the small car was not considered critical, and only test designation no. 2-11 was conducted to evaluate the MASH TL-2 bridge rail.

In order to minimize the cost of barrier installations, the run-out-length of the guardrail adjacent to the bridge must also be optimized. After the bridge rail system was proven crashworthy to MASH TL-2, an analysis was conducted to evaluate whether a stiffness transition was necessary between the bridge rail and the adjacent roadside guardrail. Additionally, an analysis was conducted to calculate the minimum length of MGS required adjacent to the bridge railing based on anchorage requirements and guardrail terminal characteristics.

2 POST-TO-DECK CONNECTION DESIGNS

2.1 Deck Configurations

Historically, bridges on rural, low-volume roads in the state of Nebraska were built with CIP decks. However, the use of precast, prestressed beam slabs has become popular in recent years as they allow for rapid construction of the bridge. Thus, the Nebraska Department of Transportation (NDOT) desired the new bridge railing to be compatible with both deck types.

CIP decks in Nebraska are typically 7 to 8 in. thick and are reinforced with upper and lower steel rebar mats. These decks are supported by wide-flange steel girders, and the exterior girders are commonly placed directly below the edges of the deck. As such, there are no overhang or cantilevered portions of deck along the sides of the bridge. Steel channels are commonly placed along the edges of the deck. These channels are tack welded to the tops of the exterior girders and serve as formwork while pouring the deck. Additionally, the channels provided a steel surface along the edge of the deck where bridge rail posts could be welded onto the bridge. Rebar are welded to the inside face of the channel and tied to both the top and bottom steel mats to anchor the channels to the side of the deck. Example details from a typical CIP bridge deck are shown in Figure 3.

Through discussions with NDOT, a 7-in. thick deck reinforced with #4 lateral rebar at 6-in. spacings and #4 longitudinal rebar at 12-in. spacings in both the upper and lower steel mats was selected as a critical CIP deck for use in the development and evaluation of the new bridge railing. This configuration represented the thinnest CIP deck and utilized typical reinforcing steel. A C7x9.8 channel was selected for use along the deck edge as it was the weakest of the standard 7-in. C-channels.

Precast, pre-stressed, beam-slabs can be fabricated in a variety of sizes and configurations, but they have a minimum thickness of 12 in. and are typically around 3 ft to 4 ft wide. Similar to the CIP decks, steel channels are embedded into the sides of the precast beam-slabs to provide a steel surface for the attachment of bridge rail posts. However, since the channels are not needed as formwork, the side channels in beam-slab may be continuous along the edge or used intermittently only at post locations. Example details from a typical beam-slab bridge are shown in Figure 4, while pictures of short channel segments used in a recent bridge deck are shown in Figure 5. Through discussions with NDOT, a 12-in. thick beam-slab reinforced with #3 stirrups at 5-in. spacings, three #4 longitudinal rebar at the top, a combination of prestressing strands and rebar at the bottom, and a C12x20.7 side channel was selected as the critically small/weak beam-slab configuration for use in development and evaluation of the new bridge rail.

[illegible]

The diagram illustrates a cross-section of a bridge deck, labeled as being "Symmetric about C Bridge". The total width of the deck is 6'-3" Post Spacing (Typ.). The deck is divided into sections by vertical lines representing the centerlines of the rail posts. The dimensions are as follows:

- From the "End of Floor" to the first rail post centerline: 1'-1"
- Between the first and second rail post centerlines: 10 1/2"
- Between the second and third rail post centerlines: 3'-0"
- Between the fourth and fifth rail post centerlines: 2'-0"
- Between the sixth and seventh rail post centerlines: 10 1/2"
- Between the seventh and eighth rail post centerlines: 3'-0"
- From the eighth rail post centerline to the right edge: 3"

The rail posts are shown as vertical lines with circular bases. The centerline of the bridge is marked with a "C" and the label "C Bridge". The centerline of a rail post is marked with a "C" and the label "C Rail Post".

EDGE CHANNEL AT MAIN SPAN

6




Figure 4. Example Details for 12-in. Thick Precast Beam-Slab Deck



Figure 5. Short Channel Segments Used Within a 12-in. Thick Beam-Slab Deck

2.2 Socket and Post Sections

It was desired for the new bridge rail to be a side-mounted, weak-post system with a socketed post-to-deck attachment. As such, the same steel post and socket sections used in the previously developed, MASH TL-3, MGS bridge rail were selected for use in the new system. The posts were S3x5.7 sections and the sockets consisted of HSS4x4x $\frac{3}{8}$ sections, as shown in Figure 6. The post standoffs, or shims, welded to the sides of the post within the socket were desired for use in the new bridge railing as well. These standoffs created a tighter fit for the post within the socket and prevented posts from leaning to the side. Additionally, the welded connections of the standoffs to the post create a stress concentrator that causes the post flanges to tear when a vehicle bumper impacts a post and bends it over longitudinally, as shown in Figure 7. With the flanges torn, a post will bend over easily and will not spring back upward to contact and potentially tear the vehicle floor pan, as observed in previous tests with S3x5.7 posts.

The socket assembly from the MGS bridge rail was to be reconfigured for use on the selected bridge decks. The only components that were to remain the same were the HSS square tube section and the keeper bolt that ran longitudinally through the center of the post's web to prevent the post from pulling out of the socket during impact events. In previous socketed systems utilizing S3x5.7 posts, like the MGS bridge rail and weak-post MGS attachments to concrete culverts [3, 6-7], the sockets extended 2 in. above the deck/ground surface. However, the CIP decks discussed in Section 2.1 are often poured with the paver running on top of the C-channel and extending off the edge of the deck. Thus, the top of the socket was desired to be slightly below the surface of the deck to prevent interference with this construction technique. Subsequently, all sockets designed and evaluated herein stopped $\frac{3}{8}$ in. below the surface of the deck.

Two different socket-to-deck attachment methods were to be explored: (1) a welded attachment with the socket welded directly to the deck's side C-channel, and (2) a bolted attachment with the socket assembly bolted to the side of the deck. These attachment methods and their corresponding socket assemblies are discussed in the following sections.




Figure 6. Post Assembly and Socket Tube from the MGS Bridge Rail [3]




Figure 7. Post Flange Tearing adjacent to Post Standoffs [3]

2.3 Welded Socket Attachments

A welded attachment of the tube socket to the side channel of the deck was an option explored for use in the new bridge railing design. Directly welding the socket to the channel, as shown in Figure 8, minimized the number of components in the socket assembly by eliminating the need for an attachment plate. Also, many of the installers that work on rural bridges have experience with welding posts to deck edges. Thus, a welded attachment would provide a simple and cost-efficient mechanism for attaching the sockets to the bridge deck.



Figure 8. Socket Welded Directly to a 7-in. CIP Deck

A few concerns were identified with field welding the sockets. First, field welds require black, or galvanized, steel components. As such, both the socket and the side channel could not be galvanized and would be susceptible to rusting. Second, field welding would take longer to assemble the bridge railing compared to a bolted attachment. Finally, a welded attachment results in all of the impact load being transferred to the side channel of the deck. Even though the new bridge rail system used weak S3x5.7 posts, the impact loads could pry the top flange of the channel away from the bridge deck if the channel was not sufficiently anchored to the deck. This concern is illustrated in Figure 9.





Figure 9. Channel Flange Prying off Deck During Loading

To mitigate the concerns of the channel being pried from the side of the bridge deck during impacts, multiple reinforcement configurations were developed to anchor the side channel to the deck. These anchorage configurations are shown in Figure 10. The first anchorage option utilized straight #4 rebar segments welded to the inside face of the channel that extended into the deck and tied into the upper and lower steel mats. ASTM A615 steel is the most common steel material used for rebar, but there were concerns that the butt welds at the end of the rebar to the channel would not fully develop the strength of the rebar. Thus, ASTM A706 steel rebar was also investigated for use in the channel anchorage as its chemical properties were designed to enhance weldability.


The second anchorage option utilized a #5 U-bar with its base located at the upper corner of the channel and its legs extending diagonally down and into the deck. Flare-bevel welds would be used to attach the base of the U-bar to the flange and web of the channel. This welded connection has significantly increased strength over the butt welds from the previous anchorage option and would be more likely to develop the full capacity of the U-bar. A few straight #4 rebar were also used in this anchorage option to help further anchor the channel and tie into the deck reinforcing steel.

The third anchorage option used gusset plates to reinforce the top flange and web of the channel, and #4 rebar were welded to the gussets using the stronger flare-bevel welds. The interior ends of the rebar were hooked down at 90 degrees to increase the anchorage capacity of the bars. A few straight #4 rebar were still used at the bottom of the channel to tie in with the lower steel mat of the deck. This anchorage design was considered the strongest of the options and would only be used if the other options failed to adequately anchor the channel to the edge of the deck.

Straight Bars
Fillet Welded



U-Bars
Flare Bevel Welded



Hooked Bars
Gussets,
Flare Bevel Welded




Figure 10. Welded Socket Attachment with (a) Straight Bar Anchorage, (b) U-bar Anchorage, and (c) Gussets and Hook Bar Anchorage

2.4 Bolted Socket Attachments

A bolted socket-to-deck attachment was desired to address many of the concerns raised with a welded attachment. Bolted attachments can use all galvanized components, thereby minimizing the risk of rusting. To create a bolted socket-to-deck attachment, the socket had to first be welded to a mounting plate. However, this socket assembly could be welded in the shop and galvanized prior to installation. Bolted attachments can also be assembled quickly on site and do not require the skilled/certified labor or extra equipment associated with welding. Finally, damaged components are much easier to replace in a bolted attachment in comparison to welded joints.

One of the objectives of the project was that the deck edge remained smooth without any hardware extending outward that would interfere with formwork. Thus, the socket assembly had to be bolted on from the outside with an internally threaded component cast within the deck. To satisfy these constraints, a new post-to-deck attachment method was developed using coupling nuts and threaded rods. Coupling nuts are commonly used to connect the ends of threaded hardware and directly transfer loads from one component to the other. For the new bolted attachment, holes were drilled in the web of the channel and coupling nuts were placed on the inside surface of the channel. Threaded rods were partially inserted into the coupling nuts and extended into the deck. These components would be embedded into the bridge deck when the concrete is poured. This allows the socket assemblies to be easily attached to the edge of the deck by bolting through the mounting plate and side channel and into the coupling nut, as shown in Figure 11.

During an impact, this new post-to-deck attachment design directly transfers the tensile loads from the attachment bolts through the coupling nuts and into the threaded rod anchors. The impact loads are never transferred to the channels (except for compression as part of the force couple resisting the moment created from post bending), so there would be minimal risk of damage to the side channels or the deck. Finally, the coupling nuts, threaded rods, and bolts would all be standard hardware, so only the socket assembly would need to be fabricated as part of the socket-to-deck attachment.




Figure 11. Coupling Nut and Threaded Rod Attachment of Socket Assembly to Deck

3 COMPONENT TESTING CONDITIONS

3.1 Purpose

Several side-mounted, post-to-deck connections were evaluated with dynamic component tests in order to evaluate the strength and behavior of the connections as well as potential damage to both deck types during an impact event.

3.2 Scope

Six dynamic component tests were conducted on S3x5.7 steel posts mounted to the side of simulated bridge decks with various socket-to-deck attachment designs. The socket-to-deck attachments consisted of the welded and bolted options discussed in Sections 2.3 and 2.4, respectively. A total of eight different socket-to-deck attachment designs were constructed on two simulated bridge decks, and each design, or location on the simulated decks, was denoted with a letter, as shown in Figures 12 through 35. Designs A through F were located on a simulated 7-in. thick, CIP deck and spaced at 51-in. intervals, on-center. Designs G and H were located on a simulated 12-in. thick, precast concrete beam-slab and were spaced 48 in. apart. Each of the socket-to-deck attachment designs had a unique combination of deck type, socket welds, bolt and threaded rod diameter, and internal reinforcement welded to the inside of the channel. Differences in the socket and post length were only due to the thickness of the deck and not necessarily a design feature desired for evaluation.

All of the socket-to-deck attachments were constructed on short channel segments embedded into the simulated decks. The short segments were utilized instead of a continuous channel so that any damage to a particular attachment location would not affect the adjacent locations. Additionally, testing short channel segments was seen as a worst-case scenario for anchoring the channel to the deck as a continuous channel should have increased strength and resistance to damage. Thus, if the component tests were successful with short channel segments, designs with continuous channels along the deck edge would also be acceptable.

Although eight test installations were constructed, only six dynamic component tests were conducted. Testing was conducted using an iterative approach where the design selected for evaluation in a specific test was based on the results of the previous tests. Eight different designs were constructed so that the researchers had design options available for continued testing without having to construct new test articles. Thus, the extra test articles provided multiple testing possibilities and a construction time savings at minimal additional installation costs.

Two different impact conditions were used. The first involved a lateral impact (90-degree impact angle) on the post at a height of 25 in. subjecting it to strong-axis bending. These impact conditions were selected to match the height to the center of the W-beam rail and represent maximum lateral loading into the guardrail system. Similar impact conditions are routinely used to observe the performance of guardrail posts installed in soil. The second critical test condition involved a longitudinal impact (0-degree impact angle) where a post was subjected to weak-axis bending. The longitudinal impacts were conducted with a load height of 12 in. to simulate a small car bumper impacting posts during a redirection. This second impact was deemed critical because it induces high shear loads into the socket and may cause the socket to rotate. The target impact speed for both test conditions was 20 mph. These two critical impact conditions have previously

been used to evaluate socket attachments to culverts for weak-post MGS installations [6-7]. Table 1 shows the design/location and impact conditions for each of the six dynamic component tests conducted during the study.

The simulated concrete decks were designed to replicate typical CIP and pre-stressed concrete beam-slabs used on rural Nebraska roadways. Note, the simulated concrete beam-slab was not pre-stressed and only utilized standard rebar reinforcement. This change saved on installation costs without affecting the results of the component tests. Both concrete decks had a targeted minimum compressive strength of 6,000 psi. The actual concrete compressive strength was 5,660 psi. Design details for the test installations are shown in Figures 12 through 35, and installation photographs are shown in Figure 36. Material specifications, mill certifications, and certificates of conformity for the simulated decks, posts, and attachment hardware used for the component tests are shown in Appendix A.

Table 1. Component Testing Details

| Test No. | Target Impact Speed mph | Impact Angle degrees | Impact Height in. | Deck | Deck Location | Attachment Type | Attachment Details | C-Channel Section | C-Channel Assembly |
|----------|-------------------------|----------------------|-------------------|-----------------------|---------------|-----------------|--------------------------|-------------------|--------------------|
| N2B-1 | 20 | 90 | 25 | 7" CIP | A | Bolted | 1-in. diameter fasteners | C7x9.8 | A |
| N2B-2 | 20 | 90 | 25 | 12" Precast Beam-Slab | G | Bolted | ¾-in. diameter fasteners | C12x20.7 | F |
| N2B-3 | 20 | 90 | 25 | 7" CIP | B | Welded | Straight A706 rebar | C7x9.8 | B |
| N2B-4 | 20 | 90 | 25 | 7" CIP | E | Welded | #5 U-bar | C7x9.8 | D |
| N2B-5 | 20 | 0 | 12 | 12" Precast Beam-Slab | G | Bolted | ¾-in. diameter fasteners | C12x20.7 | F |
| N2B-6 | 20 | 0 | 12 | 7" CIP | C | Welded | Straight A615 rebar | C7x9.8 | B |




Figure 12. Bogie Testing Matrix and Setup, 7-in. Thick Deck System Overview




Figure 13. Bogie Testing Matrix and Setup, 7-in. Thick Concrete Deck in Ground Details




Figure 14. Bogie Testing Matrix and Setup, 12-in. Thick Deck System Overview




Figure 15. Bogie Testing Matrix and Setup, 12-in. Thick Concrete Deck in Ground Details




Figure 16. Bogie Testing Matrix and Setup, 7-in. Thick Deck Reinforcement




Figure 17. Bogie Testing Matrix and Setup, 12-in. Thick Deck Reinforcement




Figure 18. Bogie Testing Matrix and Setup, Location "A" Deck Section and C-Channel Assembly A




Figure 19. Bogie Testing Matrix and Setup, Locations "B" and "C" Deck Section and C-Channel Assembly B




Figure 20. Bogie Testing Matrix and Setup, Location "D" Deck Section and C-Channel Assembly C




Figure 21. Bogie Testing Matrix and Setup, Location "E" Deck Section and C-Channel Assembly D




Figure 22. Bogie Testing Matrix and Setup, Location "F" Deck Section and C-Channel Assembly E




Figure 23. Bogie Testing Matrix and Setup, Location "G" Deck Section and C-Channel Assembly F




Figure 24. Bogie Testing Matrix and Setup, Location "H" Deck Section and C-Channel Assembly G




Figure 25. Bogie Testing Matrix and Setup, C-Channel Assembly Components




Figure 26. Bogie Testing Matrix and Setup, C-Channel Assembly Components




Figure 27. Bogie Testing Matrix and Setup, Post Assembly Details




Figure 28. Bogie Testing Matrix and Setup, Post Components




Figure 29. Bogie Testing Matrix and Setup, Socket Components




Figure 30. Bogie Testing Matrix and Setup, Socket Components




Figure 31. Bogie Testing Matrix and Setup, Deck Rebar Details




Figure 32. Bogie Testing Matrix and Setup, C-Channel Assembly Rebar Details





Figure 33. Bogie Testing Matrix and Setup, Hardware

| Item No. | QTY. | Description | Material Spec | Galvanization Spec | Hardware Guide |
|---|------|---|--|--|----------------|
| a1 | 2 | Concrete | Min. $f'_c = 6,000$ psi [41.4 MPa] NE Mix 47BD | — | — |
| b1 | 1 | C7x9.8 [C178x14.3], 36" [914] Long C-Channel | ASTM A36 | — | — |
| b2 | 3 | C7x9.8 [C178x14.3], 36" [914] Long C-Channel | ASTM A36 | — | — |
| b3 | 2 | C7x12.25 [C178x18.2], 36" [914] Long C-Channel | ASTM A36 | — | — |
| b4 | 1 | C12x20.7 [C305x30.8], 20" [508] Long C-Channel | ASTM A36 | — | — |
| b5 | 1 | C12x20.7 [C305x30.8], 20" [508] Long C-Channel | ASTM A36 | — | — |
| b6 | 1 | 10"x2 3/4"x1/4" [254x70x6] Plate Washer | ASTM A36 | ASTM A123 | — |
| b7 | 4 | 2x2x1/4" [51x51x6] Gusset | ASTM A36 | ASTM A123* | — |
| c1 | 6 | HSS4x4x3/8" [102x102x10], 6 5/8" [168] Long Square Tube | ASTM A500 Gr. B | ASTM A123* | — |
| c2 | 2 | HSS4x4x3/8" [102x102x10], 11 5/8" [295] Long Square Tube | ASTM A500 Gr. B | ASTM A123* | — |
| c3 | 1 | 10"x7"x1/2" [254x178x13] Steel Plate | ASTM A572 Gr. 50 | ASTM A123* | — |
| c4 | 1 | 12"x10"x1/2" [305x254x13] Steel Plate | ASTM A572 Gr. 50 | ASTM A123* | — |
| c5 | 1 | 12"x10"x1/2" [305x254x13] Steel Plate | ASTM A572 Gr. 50 | ASTM A123* | — |
| e1 | 6 | S3x5.7 [S76x8.5], 39" [991] Long Steel Post | ASTM A992 | ASTM A123* | — |
| e2 | 2 | S3x5.7 [S76x8.5], 44" [1118] Long Steel Post | ASTM A992 | ASTM A123* | — |
| e3 | 32 | 2 3/4"x1"x1/4" [70x25x6] Post Standoff | ASTM A36 | ASTM A123* | — |
| f1 | 8 | 5/8" [16] Dia. UNC, 5" [127] Long Heavy Hex Head Bolt and Nut | Bolt — ASTM F3125 Gr. A325 Type 1 Nut — ASTM A563DH | ASTM A153 or B633 or B695 Class 55 or F1136 Gr. 3 or F1941 or F2329 or F2833 Gr. 1 | FBX16b |
| f2 | 2 | 3/4" [19] Dia. UNC, 1 3/4" [44] Long Heavy Hex Head Bolt | ASTM A449 | ASTM A153 or B695 Class 55 or F2329 | FBX20b |
| f3 | 2 | 3/4" [19] Dia. Heavy Hex Coupling Nut | ASTM A563DH or A194 Gr. 2H | ASTM A153 or B633 or B695 Class 55 or F1941 or F2329 | — |
| f4 | 2 | 3/4" [19] Dia., 30" [762] Long Threaded Rod | ASTM A449 | ASTM A153 or B695 Class 55 or F2329 | FRR20b |
| f5 | 2 | 7/8" [22] Dia. UNC, 2" [51] Long Heavy Hex Head Bolt | ASTM A449 | ASTM A153 or B695 Class 55 or F2329 | FBX22b |
| f6 | 2 | 7/8" [22] Dia. Hex Coupling Nut | ASTM A563DH or A194 Gr. 2H | ASTM A153 or B633 or B695 Class 55 or F1941 or F2329 | — |
| <div> <div>  <div> <div>Midwest Roadside Safety Facility</div> </div> </div> <div> <div>TL-2 Bridge Rail for Low-Volume Roads</div> <div>Bill of Materials</div> </div> <div> <div>DWG. NAME: TL2BR_BogieDeck_R11</div> <div>SCALE: 1:96 UNITS: in./mm</div> <div> <div>SHEET: 23 of 24</div> <div>DATE: 2/19/2018</div> <div>DRAWN BY: KJW/JEK/ DTM/JWB</div> <div>REV. BY: JEK/SKR/ KAL/JCH</div> </div> </div> </div> | | | | | |

* Galvanization should occur after welding.

Figure 34. Bogie Testing Bill of Materials


| Item No. | QTY. | Description | Material Spec | Galvanization Spec | Hardware Guide |
|---|------|--|----------------------------|--|----------------|
| f7 | 2 | 7/8" [22] Dia., 30" [762] Long Threaded Rod | ASTM A449 | ASTM A153 or B695 Class 55 or F2329 | — |
| f8 | 2 | 1" [24] Dia. UNC, 2" [51] Long Heavy Hex Head Bolt | ASTM A449 | ASTM A153 or B695 Class 55 or F2329 | FBX24b |
| f9 | 2 | 1" [25] Dia. Heavy Hex Coupling Nut | ASTM A563DH or A194 Gr. 2H | ASTM A153 or B633 or B695 Class 55 or F1941 or F2329 | — |
| f10 | 4 | 1" [29] Dia. Heavy Hex Nut | ASTM A563DH or A194 Gr. 2H | ASTM A153 or B633 or B695 Class 55 or F1941 or F2329 | FNX24b |
| f11 | 2 | 1" [25] Dia., 24" [610] Long Threaded Rod | ASTM A449 | ASTM A153 or B695 Class 55 or F2329 | FRR24b |
| f12 | 2 | 1" [25] Dia. Hardened Flat Washer | ASTM F436 | ASTM A153 or B695 Class 55 or F1136 Gr. 3 or F2329 | FWC24b |
| f13 | 2 | 7/8" [22] Dia. Hardened Flat Washer | ASTM F436 | ASTM A153 or B695 Class 55 or F1136 Gr. 3 or F2329 | FWC22b |
| f14 | 2 | 3/4" [19] Dia. Hardened Flat Washer | ASTM F436 | ASTM A153 or B695 Class 55 or F1136 Gr. 3 or F2329 | FWC20b |
| g1 | 5 | #4 [13] Bar, 287 1/2" [7,303] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934)** | — |
| g2 | 1 | #4 [13] Bar, 251 1/2" [6,388] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934)** | — |
| g3 | 1 | #4 [13] Bar, 200 1/2" [5,093] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934)** | — |
| g4 | 1 | #4 [13] Bar, 63" [1,600] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934)** | — |
| g5 | 2 | #4 [13] Bar, 48" [1,219] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934)** | — |
| g6 | 98 | #4 [13] Bar, 32" [813] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934)** | — |
| g7 | 70 | #4 [13] Bar, 20" [508] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934)** | — |
| g8 | 19 | #3 [10] Bar, 86 7/8" [2,207] Long Unbent | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934)** | — |
| g9 | 5 | #4 [13] Bar, 90 3/8" [2,296] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934)** | — |
| g10 | 8 | #8 [25] Bar, 90 3/8" [2,296] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934)** | — |
| g11 | 47 | #4 [13] Bar, 18" [457] Long | ASTM A706 Gr. 60 | — | — |
| g12 | 4 | #4 [13] Bar, 23 11/16" [602] Long Unbent | ASTM A706 Gr. 60 | — | — |
| g13 | 2 | #4 [13] Bar, 40" [1,016] Long Unbent | ASTM A706 Gr. 60 | — | — |
| g14 | 1 | #5 [16] Bar, 52 3/16" [1,325] Long Unbent | ASTM A706 Gr. 60 | — | — |
| g15 | 10 | #4 [13] Bar, 18" [457] Long | ASTM A615 Gr. 60 | — | — |
| <div> <div>  <div> <div>Midwest Roadside Safety Facility</div> </div> </div> <div> <div>TL-2 Bridge Rail for Low-Volume Roads</div> <div>Bill of Materials</div> </div> <div> <div> <div>SHEET: 24 of 24</div> <div>DATE: 2/19/2018</div> <div>DRAWN BY: KJW/JEK/DTM/JWB</div> <div>REV. BY: JEK/SKR/KAL/JCH</div> </div> <div> <div>DWG. NAME: TL2BR_BogieDeck_R11</div> <div>SCALE: 1:96</div> <div>UNITS: in./mm</div> </div> </div> </div> | | | | | |
| ** Component does not need to be epoxy-coated for testing purposes. | | | | | |

Figure 35. Bogie Testing Bill of Materials



(a)



(b)

Figure 36. Installation Photographs for the (a) 7-in. CIP Deck and (b) 12-in. Precast Beam-Slab

3.3 Equipment and Instrumentation

Equipment and instrumentation utilized to collect and record data during the dynamic bogie tests included a bogie vehicle, accelerometers, a retroreflective speed trap, and high-speed and standard-speed digital video cameras.

3.3.1 Bogie Vehicle

A rigid-frame bogie was used to impact the post and socket assemblies. Two different impact heads were used in the testing. For lateral impacts, the bogie head was constructed of 8-in. diameter, ½-in. thick standard steel pipe, with ¾-in. neoprene belting wrapped around the pipe. The lateral impact head was bolted to the bogie vehicle at a height of 25 in. for test nos. N2B-1 through N2B-4. The combined weight of the bogie used in test nos. N2B-1 through N2B-4, with the addition of the mountable impact head and accelerometers, was 1,786 lb. For longitudinal impacts, the bogie head consisted of a 2½-in. x 2½-in. x 5/16-in. square tube mounted on the outside flange of a W6x25 steel beam with reinforcing gussets. The longitudinal impact head was bolted to the bogie vehicle at a height of 12 in. for test nos. N2B-5 and N2B-6. The combined weight of the bogie used in test nos. N2B-5 and N2B-6, with the addition of the mountable impact head and accelerometers, was 1,690 lb. Photographs of the bogie with both impact heads are shown in Figure 37.

The tests were conducted using a steel corrugated beam guardrail to guide the bogie vehicle. A pickup truck was used to push the bogie vehicle to the required impact velocity. After reaching the target velocity, the push vehicle braked, allowing the bogie to be free rolling as it came off the track. A remote braking system was installed on the bogie allowing it to be brought safely to rest after the test.



(a) Lateral Impact Head - Test Nos. N2B-1 Through N2B-4



(b) Longitudinal Impact Head - Test Nos. N2B-5 and N2B-6

Figure 37. Bogie Vehicle with (a) Lateral Impact Head and (b) Longitudinal Impact Head

3.3.2 Accelerometers

Two environmental shock and vibration sensor/recorder systems were used to measure the accelerations in the longitudinal, lateral, and vertical directions. All of the accelerometer systems were mounted near the center of gravity (c.g.) of the bogie vehicle.

The two systems, the SLICE-1 and SLICE-2 units, were modular data acquisition systems manufactured by Diversified Technical Systems, Inc. (DTS) of Seal Beach, California. The acceleration sensors were mounted inside the body of a custom-built, SLICE 6DX event data recorder and recorded data at 10,000 Hz to the onboard microprocessor. The SLICE 6DX was configured with 7 GB of non-volatile flash memory, a range of ± 500 g's, a sample rate of 10,000 Hz, and a 1,650 Hz (CFC 1000) anti-aliasing filter. The "SLICEWare" computer software program and a customized Microsoft Excel worksheet were used to analyze and plot the accelerometer data.

3.3.3 Retroreflective Optic Speed Trap

The retroreflective optic speed trap was used to determine the speed of the bogie vehicle before impact. Three retroreflective targets, spaced at approximately 18-in. intervals, were applied to the side of the vehicle. When the emitted beam of light was reflected by the targets and returned to the Emitter/Receiver, a signal was sent to the data acquisition computer, recording at 10,000 Hz, as well as the external LED box activating the LED flashes. The speed was then calculated using the spacing between the retroreflective targets and the time between the signals. LED lights and high-speed digital video analysis are only used as a backup in the event that vehicle speeds cannot be determined from the electronic data.

3.3.4 Digital Photography

One AOS high-speed digital video camera and three GoPro digital video cameras were used to document each test. The AOS high-speed camera had a frame rate of 500 frames per second and the GoPro video camera had a frame rate of 120 frames per second. The cameras were placed laterally from the post, with a view perpendicular to the bogie's direction of travel. A digital still camera was also used to document pre- and post-test conditions for all tests.

3.4 End of Test Determination

When the impact head initially contacts the test article, the force exerted by the surrogate test vehicle is directly perpendicular. However, as the post rotates, the surrogate test vehicle's orientation and path moves further from perpendicular. This introduces two sources of error: (1) the contact force between the impact head and the post has a vertical component and (2) the impact head slides upward along the test article. Therefore, only the initial portion of the accelerometer trace should be used since variations in the data become significant as the system rotates and the surrogate test vehicle overrides the system. Additionally, guidelines were established to define the end of test time using the high-speed video of the impact. The first occurrence of either of the following events was used to determine the end of the test: (1) the test article fractures; or (2) the surrogate vehicle overrides/loses contact with the test article.

3.5 Data Processing

The electronic accelerometer data obtained in dynamic testing was filtered using the SAE Class 60 Butterworth filter conforming to the SAE J211/1 specifications [8]. The pertinent acceleration signal was extracted from the bulk of the data signals. The processed acceleration data was then multiplied by the mass of the bogie to get the impact force using Newton's Second Law. Next, the acceleration trace was integrated to find the change in velocity versus time. Initial velocity of the bogie, calculated from the retroreflective optic speed trap data, was then used to determine the bogie velocity, and the calculated velocity trace was integrated to find the bogie's displacement. Combining the previous results, a force vs. deflection curve was plotted for each test. Finally, integration of the force vs. deflection curve provided the energy vs. deflection curve for each test.

4 COMPONENT TESTING RESULTS AND DISCUSSION

4.1 Results

A total of six dynamic component tests were conducted with the bogie vehicle impacting posts and socket assemblies attached to simulated bridge decks. Descriptions of each test, including sequential and post-test photographs, are contained in the following sections. The accelerometer data for each test was processed to obtain acceleration, velocity, and deflection curves, as well as force vs. deflection and energy vs. deflection curves. Although the individual transducers produced similar results, the values described herein were calculated from the SLICE-1 data curves in order to provide common basis for comparing results from multiple tests. Test results for all transducers are provided in Appendix B.

4.1.1 Test No. N2B-1

The test article for test no. N2B-1 used Deck Location A and Channel Assembly A. The test article consisted of a bolted socket attachment utilizing 1-in. diameter bolts and a 7-in. thick simulated CIP bridge deck. See Section 3.2 for further details. Test no. N2B-1 was conducted with the bogie impacting the S3x5.7 post at a height of 25 in. and an angle of 90 degrees (through the strong axis of the post) at a speed of 21.2 mph. The impact caused the post to deflect backward as a plastic hinge formed in the post near the top of the socket and the post twisted. The bogie ultimately overrode the post at a displacement of 30.2 in. No damage occurred to the bridge deck, socket assembly, or attachment hardware. Time sequential photographs and post-test photographs are shown in Figure 38.

Force-displacement and energy-displacement curves were created from the accelerometer data and are shown in Figure 39. A peak force of 7.0 kips occurred at a displacement of 9.8 in., and an average force of 5.6 kips occurred through 20 in. of displacement. The test article had absorbed 138.9 k-in. of energy at the time the bogie overrode the post.



Figure 38. Time-Sequential and Post-Impact Photographs, Test No. N2B-1




Figure 39. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-1

4.1.2 Test No. N2B-2

The test article for test no. N2B-2 used Deck Location G and Channel Assembly F. The test article consisted of a bolted socket attachment utilizing $\frac{3}{4}$ -in. diameter bolts and a 12-in. thick simulated precast beam-slam bridge deck. See Section 3.2 for further details. Test no. N2B-2 was conducted with the bogie impacting the S3x5.7 post at a height of 25 in. and an angle of 90 degrees (through the strong axis of the post) at a speed of 21.4 mph. The impact caused the post to deflect backward as a plastic hinge formed in the post near the top of the socket and the post twisted. The bogie ultimately overrode the post at a displacement of 29.6 in. No damage occurred to the deck, socket assembly, or attachment hardware. Time sequential photographs and post-test photographs are shown in Figure 40.

Force-displacement and energy-displacement curves were created from the accelerometer data and are shown in Figure 41. A peak force of 7.1 kips on the system occurred at a displacement of 2.6 in., and the average force through 20 in. of displacement was 5.2 kips. The test article had absorbed 124.5 k-in. of energy at the time the bogie overrode the post.



IMPACT



0.050 sec



0.100 sec



0.150 sec



0.200 sec



0.250 sec




Figure 40. Time-Sequential and Post-Impact Photographs, Test No. N2B-2




Figure 41. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-2

4.1.3 Test No. N2B-3

The test article for test no. N2B-3 used Deck Location B and Channel Assembly B. The test article consisted of a welded socket attachment to the 7-in. thick simulated CIP bridge deck. The channel was anchored to the deck using straight segments of ASTM A706 rebar. See Section 3.2 for further details. Test no. N2B-3 was conducted with the bogie impacting the S3x5.7 post at a height of 25 in. and an angle of 90 degrees (through the strong axis of the post) at a speed of 21.2 mph. The impact caused the post to deflect backward as a plastic hinge formed in the post near the top of the socket. The bogie ultimately overrode the post at a displacement of 30.6 in. Due to the impact loads, the top flange of the socket had begun to pry away from the deck, and a 1/8-in. wide crack was found between the channel and the concrete. Additionally, some concrete spalling was found on the top edge of the deck adjacent to the channel. The socket and welds remained undamaged. Time sequential photographs and post-test photographs are shown in Figure 42.

Force-displacement and energy-displacement curves were created from the accelerometer data and are shown in Figure 43. A peak force of 7.4 kips on the system occurred at a displacement of 12.2 in., and the average force through 20 in. of displacement was 5.2 kips. The test article had absorbed 148.9 k-in. of energy at the time the bogie overrode the post.




Figure 42. Time-Sequential and Post-Impact Photographs, Test No. N2B-3




Figure 43. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-3

4.1.4 Test No. N2B-4

The test article for test no. N2B-4 used Deck Location E and Channel Assembly D. The test article consisted of a welded socket attachment to the 7-in. thick simulated CIP bridge deck. The channel was anchored to the deck using a U-bar welded to the upper bend of the channel and additional #4 straight bars. See Section 3.2 for further details. Test no. N2B-4 was conducted with the bogie impacting the S3x5.7 post at a height of 25 in. and an angle of 90 degrees (through the strong axis of the post) at a speed of 21.5 mph. The impact caused the post to deflect backward as a plastic hinge formed in the post near the top of the socket. The bogie ultimately overrode the post at a displacement of 30.8 in. No damage was observed to the bridge deck or socket assembly. Time sequential photographs and post-test photographs are shown in Figure 44.

Force-displacement and energy-displacement curves were created from the accelerometer data and are shown in Figure 45. A peak force of 7.5 kips on the system occurred at a displacement of 11.5 in., and the average force through 20 in. of displacement was 5.9 kips. The test article had absorbed 156.6 k-in. of energy at the time the bogie overrode the post.




Figure 44. Time-Sequential and Post-Impact Photographs, Test No. N2B-4




Figure 45. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-4

4.1.5 Test No. N2B-5

The test article for test no. N2B-5 used Deck Location G and Channel Assembly F. The test article consisted of a bolted socket attachment utilizing $\frac{3}{4}$ -in. diameter bolts and a 12-in. thick simulated precast beam-slab bridge deck. See Section 3.2 for further details. Test no. N2B-5 was conducted with the bogie impacting the S3x5.7 post at a height of 12 in. and an angle of 0 degrees (through the weak axis of the post) at a speed of 20.1 mph. The impact caused the post to deflect downstream as a plastic hinge formed in the post near the top of the socket. The bogie overrode the post at 34.0 in. of displacement. No damage occurred to the deck, socket assembly, or attachment hardware. Time sequential photographs and post-test photographs are shown in Figure 46.

Force-displacement and energy-displacement curves were created from the accelerometer data and are shown in Figure 47. A peak force of 10.3 kips on the system occurred at a displacement of 2.5 in., and the average force through 20 in. of displacement was 4.0 kips. The test article had absorbed 100.5 k-in. of energy at the time the bogie overrode the post.



Figure 46. Time-Sequential and Post-Impact Photographs, Test No. N2B-5




Figure 47. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-5

4.1.6 Test No. N2B-6

The test article for test no. N2B-6 used Deck Location C and Channel Assembly B. The test article consisted of a welded socket attachment to the 7-in. thick simulated CIP bridge deck. The channel was anchored to the deck using straight segments of ASTM A615 rebar. See Section 3.2 for further details. Test no. N2B-6 was conducted with the bogie impacting the S3x5.7 post at a height of 12 in. and an angle of 0 degrees (through the strong axis of the post) at a speed of 21.6 mph. The impact caused the post to deflect downstream as a plastic hinge formed in the post near the top of the socket. The bogie ultimately overrode the post at a displacement of 33.6 in. No damage was observed on the bridge deck or socket assembly. Time sequential photographs and post-test photographs are shown in Figure 48.

Force-displacement and energy-displacement curves were created from the accelerometer data and are shown in Figure 49. A peak force of 9.4 kips on the system occurred at a displacement of 3.2 in., and the average force through 20 in. of displacement was 4.1 kips. The test article had absorbed 103.7 k-in. of energy at the time the bogie overrode the post.




Figure 48. Time-Sequential and Post-Impact Photographs, Test No. N2B-6




Figure 49. Force vs. Displacement and Energy vs. Displacement, Test No. N2B-6

4.2 Discussion

The results from all six component tests are summarized in Table 2. The impact speeds remained consistent throughout all the tests, and all tests resulted in plastic bending of the posts at the top of the sockets. Force displacement and energy displacement curves for the lateral impacts are shown in Figures 50 and 51, respectively. In all four tests, the force increased sharply to about 7 kips over the first 2.5 to 5 in. of displacement. The forces held steady around 6 to 7 kips until a displacement of about 15 in. and then began to gradually decrease to zero. The peak forces and the average forces calculated during the impact events were all very similar for the lateral impact tests, as would be expected with consistent post bending observed in each test. Test no. N2B-2 showed a slightly reduced resistance after about 12 in. of capacity. This was likely due to increased twisting of the post during the impact event as compared to the other test articles.

Force displacement and energy displacement curves for the longitudinal impacts are shown in Figures 52 and 53, respectively. In both tests, the force peaked sharply over the first few inches of displacement before quickly falling to around 5 kips. The forces declined steadily over the rest of the impact event. The peak forces and the average forces calculated during the impact events were all very similar for the lateral impact tests, as would be expected when both tests resulted in weak-axis bending of the posts. Plastic hinges formed near the top of the sockets in both tests. Both the deck and socket assemblies remained free from damage during the longitudinal tests.

Throughout all six tests, only test no. N2B-3, where the top flange of the channel was pulled outward $\frac{1}{8}$ in. and minor concrete spalling was observed adjacent to the channel, resulted in any damage to the simulated decks. Thus, the straight rebar anchorage design did not provide

adequate anchorage strength to the side channel for a welded socket-to-channel attachment. If a welded attachment was desired, the side channels should be anchored with the angled U-bars evaluated in test no. N2B-4.

After the bogie testing program was completed, NDOT and contractors specializing in rural bridges reviewed the results and selected the bolted attachment as the optimal attachment design. The bolted attachment was desired for its rapid and simple installation method, the ability for all components to be galvanized, and due to the direct transition of impact loads from the bolts to the threaded anchors thereby minimizing the risk of deck damage during an impact event. Therefore, the new bridge rail using a bolt, coupling nut, and threaded anchor attachment design was selected for further evaluation through full-scale crash testing.

Table 2. Dynamic Testing Results

| Test No. | Attachment Details | Deck | Impact Velocity mph | Impact Angle deg. | Average Force kips | | | Peak Force kips | Damage Description |
|--|--------------------------------------|-----------------------|---------------------|-------------------|--------------------|------|------|-----------------|--|
| | | | | | @10" | @15" | @20" | | |
| Lateral Impacts with 25-in. Impact Height | | | | | | | | | |
| N2B-1 | Bolted: 1-in. diameter fasteners | 7" CIP | 21.2 | 90 | 5.1 | 5.6 | 5.6 | 7.0 | N/A |
| N2B-2 | Bolted: ¾-in. diameter fasteners | 12" Precast Beam-Slab | 21.4 | 90 | 5.6 | 5.7 | 5.2 | 7.1 | N/A |
| N2B-3 | Welded: #4 straight bar ASTM A706 | 7" CIP | 21.2 | 90 | 5.3 | 5.8 | 5.8 | 7.4 | ⅛-in. crack along top edge of channel, concrete spalling |
| N2B-4 | Welded: #5 U-bar ASTM A615 | 7" CIP | 21.5 | 90 | 5.2 | 5.8 | 5.9 | 7.5 | N/A |
| Longitudinal Impacts with 12-in. Impact Height | | | | | | | | | |
| N2B-5 | Bolted: ¾-in. diameter fasteners | 12" Precast Beam-Slab | 20.2 | 0 | 4.8 | 4.3 | 4.0 | 10.3 | N/A |
| N2B-6 | Welded: #4 straight bar ASTM A615 | 7" CIP | 21.6 | 0 | 4.9 | 4.5 | 4.1 | 9.4 | N/A |




Figure 50. Strong Axis, 90-Degree Impacts, Force vs. Deflection Comparison




Figure 51. Strong Axis, 90-Degree Impacts, Energy vs Displacement Comparison




Figure 52. Weak Axis, 0-Degree Impacts, Force vs. Deflection Comparison




Figure 53. Weak Axis, 0-Degree Impacts, Energy vs Displacement Comparison

5 DESIGN DETAILS

5.1 Selection of Critical System Configurations for Testing

The new TL-2 bridge railing was to be compatible with both CIP and precast, beam-slab decks. After reviewing both deck types, a 7-in. thick CIP deck was identified as the thinnest and weakest of the bridge decks, which made it more susceptible to damage and anchor pullout than the thicker and stronger decks. Thus, a simulated 7-in. thick CIP deck was selected for use in full-scale crash testing. Component testing demonstrated the ability of the new coupling nut and threaded anchor attachment design to directly transfer impact loads to the interior of the deck and prevent damage to the edge of the deck, even with short channel segments at post locations. Thus, a continuous C7x9.8 channel was installed along the edge of the simulated bridge deck to represent the most common configuration for 7-in. thick decks. Note, a C7x9.8 represented the thinnest and weakest of the standard 7-in. C-channels, so use of any other 7-in. channel would also be acceptable.

As mentioned previously, CIP bridges on rural roads in Nebraska are typically constructed with the side channel located directly above the exterior bridge girders. In fact, the channels are often tack welded to the steel girders and used as formwork for pouring the deck. In recognition of this design characteristic, the full-scale test installation was constructed without a deck overhang. Instead, the edge of the simulated bridge deck was installed on a small concrete grade beam meant to represent a bridge girder. Bridges utilizing precast beam-slabs would not be directly supported at the edges the bridge. However, the increased thickness and reinforcement of precast beam-slabs results in significantly higher bending, shear, torsion, and anchor breakout strength compared to the thinner CIP decks. Therefore, precast beam-slabs would be expected to have the strength to support the new bridge rail as well.

Component testing of the bolted attachments on 7-in. CIP decks utilized 1-in. diameter bolts and threaded rods. However, an analysis of the loads observed during the component tests and the attachment design revealed that smaller $\frac{7}{8}$ -in. diameter hardware was strong enough to resist the impact loads. Subsequently, the attachment design was modified to use $\frac{7}{8}$ -in. diameter bolts, threaded rods, and coupling nuts.

5.2 Test Installation Details

A 75-ft long section of the new bridge railing was placed in the middle of a 182 ft – $3\frac{1}{2}$ in. long MGS test installation, which included guardrail anchorages at both ends, as shown in Figures 54 through 81. The bridge railing consisted of 31-in. tall, 12-gauge, W-beam guardrail supported by S3x5.7 posts spaced at 75 in. on-center. A $\frac{5}{16}$ -in. diameter hex bolt and a $1\frac{3}{4}$ -in. square washer were used to attach the guardrail to the posts. The side-mounted posts were inserted into socket assemblies consisting of HSS4x4x $\frac{3}{8}$ tube sockets and a 10-in. x 7-in. mounting plate. Standoff plates were welded to the bottom of the posts to create a tighter fit between the post and the socket and force the posts to stand vertical after installation. A 1-in. wide steel strap was welded to the bottom of each socket to prevent the post from falling through the socket during installation. A $\frac{5}{8}$ -in. diameter keeper bolt was used to prevent the post from pulling out of the socket during impact events.

The socket assemblies were attached to the deck using two $\frac{7}{8}$ -in. diameter bolts that threaded into coupling nuts embedded into the side of the bridge deck. All-thread steel rods were threaded into the opposite side of the coupling nuts and extended into the simulated deck where they were secured to a $\frac{1}{4}$ -in. thick plate washer. The mounting plates of the socket assembly contained vertical slots to allow for slight height adjustments to the system during installation.

The simulated 7-in. thick, CIP bridge deck was 75 ft long, 36 in. wide, and was reinforced with #4 rebar in both the lateral and longitudinal directions for both the upper and lower steel mats. A C7x9.8 steel channel was cast into the outer edge of the deck. The channel assembly contained #4 rebar welded to the inside of its web that extended into the deck and tied into the upper and lower steel mats. The edge of the deck was supported by an unreinforced 8-in. x 12-in. grade beam meant to replicate an exterior bridge girder. The interior of the bridge deck was anchored to the existing tarmac by #4 rebar dowels. The concrete deck was constructed with a targeted minimum compressive strength of 6,000 psi. The concrete's actual 29-day compressive strength was 5,795 psi.

Standard MGS, consisting of 31-in. tall W-beam guardrail and W6x8.5 posts spaced at 75 in. on-center, was installed on both sides of the bridge railing. The systems were connected with adjacent S3x5.7 bridge posts and W6x8.5 MGS posts spaced 75 in. apart. Thus, a constant post spacing was used throughout the entire test installation.

A guardrail anchorage system typically utilized as a trailing end terminal was utilized to anchor the upstream end of the test installation. The guardrail anchorage system was originally designed to simulate the strength of other crashworthy end terminals. The anchorage system consisted of timber posts, foundation tubes, anchor cables, bearing plates, rail brackets, and channel struts, which closely resembled the hardware used in the Modified BCT system. The guardrail anchorage system has been MASH TL-3 crash tested as a downstream trailing end terminal [9-12]. Material specifications, mill certifications, and certificates of conformity for the full-scale test installation are shown in Appendix C.

The original design intent was for 12-in. backup plates to be installed behind the W-beam at every bridge post location, as shown in Figures 55 and 75. Due to an oversight, these backup plates were not installed within the test installation. Although the test was conducted without backup plates, it is still recommended they be utilized in non-blocked, weak-post guardrail systems to prevent the rail tearing observed in other full-scale crash tests on similar systems [4-5, 13].




Figure 54. Test Installation Layout, Test No. N2BR-1




Figure 55. Bridge Deck Cross Section, Test No. N2BR-1




Figure 56. Concrete Deck Assembly Details, Test No. N2BR-1




Figure 57. Concrete Deck Reinforcement, Test No. N2BR-1




Figure 58. C-Channel and Post Socket Component Details, Test No. N2BR-1




Figure 59. C-Channel Assembly Details, Test No. N2BR-1




Figure 60. Deck C-Channel, Test No. N2BR-1




Figure 61. Deck Reinforcement, Test No. N2BR-1




Figure 62. Post Socket Assembly, Test No. N2BR-1




Figure 63. Plate Washer and Post Socket Components, Test No. N2BR-1




Figure 64. Bridge Post Assembly and Components, Test No. N2BR-1




Figure 65. Splice and Post Detail, Test No. N2BR-1




Figure 66. End Section Details, Test No. N2BR-1




Figure 67. BCT Anchor Details, Test No. N2BR-1




Figure 68. Line Post Components, Test No. N2BR-1




Figure 69. Foundation Tube and BCT Timber Post Details, Test No. N2BR-1




Figure 70. BCT Anchor Cable and Load Cell Detail, Test No. N2BR-1




Figure 71. Modified BCT Anchor Cable, Test No. N2BR-1




Figure 72. Shackle and Eye Nut Detail, Test No. N2BR-1




Figure 73. BCT Post Components and Anchor Bracket, Test No. N2BR-1




Figure 74. Ground Strut and Bearing Plate, Test No. N2BR-1




Figure 75. Rail Section Details, Test No. N2BR-1




Figure 76. System Hardware, Test No. N2BR-1




Figure 77. System Hardware, Test No. N2BR-1


| Item No. | QTY. | Description | Material Specification | Treatment Specification | Hardware Guide | |
|----------|------|---|--|-------------------------------------|-------------------------------|---|
| a1 | 1 | 6'-3" [1,905] 12-gauge [2.7] W-Beam MGS Section | AASHTO M180 | ASTM A123 or A653 | RWM04a | |
| a2 | 12 | 12'-6" [3,810] 12-gauge [2.7] W-Beam MGS Section | AASHTO M180 | ASTM A123 or A653 | RWM04a | |
| a3 | 2 | 12'-6" [3,810] 12-gauge [2.7] W-Beam MGS End Section | AASHTO M180 | ASTM A123 or A653 | RWM14a | |
| a4 | 12 | 1' [305] 12-gauge [2.7] W-Beam MGS Section | AASHTO M180 | ASTM A123 or A653 | RWM04a | |
| b1 | 4 | 72" [1,829] Long Foundation Tube | ASTM A500 Gr. B | ASTM A123 | PTE06 | |
| b2 | 4 | BCT Timber Post – MGS Height | SYP Grade No. 1 or better (No knots 18" [457] above or below ground tension face) | – | – | |
| b3 | 13 | W6x8.5 [W152x12.6] or W6x9 [W152x13.4], 72" Long [1,829] Steel Post | ASTM A992 Gr. 50 | ASTM A123 | PWE06 | |
| b4 | 13 | 6"x12"x14 1/4" [152x305x368] Timber Blockout for Steel Posts | SYP Grade No.1 or better | – | PDB10a | |
| b5 | 48 | 2 3/4"x1"x1/4" [70x25x6] Post Standoff | ASTM A36 | – | – | |
| b6 | 12 | S3x5.7 [S76x8.5], 39" [991] Long Steel Post | ASTM A992 Gr. 50 | – | – | |
| c1 | 12 | 10"x7"x1/2" [254x178x13] Steel Plate | ASTM A572 Gr. 50 | – | – | |
| c2 | 12 | 10"x2 3/4"x1/4" [254x70x6] Plate Washer | ASTM A36 | ASTM A123 | – | |
| c3 | 12 | HSS4"x4"x3/8" [102x102x10], 6 5/8" [168] Long Square Tube | ASTM A500 Gr. B | – | – | |
| c4 | 12 | 3 1/2"x1"x1/8" [89x25x4] | ASTM A36 | – | – | |
| c5 | 4 | C7x9.8 [C178x14.3], 225" [5,715] Long C-Channel | ASTM A36 | – | – | |
| c6 | 24* | 6 5/8"x2"x1/8" [168x51x3] Shim Plate | ASTM A36 | ASTM A123 | – | |
| d1 | 7 | #4 [13] Bar, 896 1/2" [22,771] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934) | – | |
| d2 | 302 | #4 [13] Bar, 32" [813] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934) | – | |
| d3 | 76 | #4 [13] Bar, 16" [406] Long | ASTM A615 Gr. 60 | Epoxy Coated (ASTM A775 or A934) | – | |
| d4 | 128 | #4 [13] Bar, 18" [457] Long | ASTM A706 Gr. 60 | – | – | |
| e1 | 13 | 5/8"-11 UNC [M16x2], 14" [356] Long Guardrail Bolt and Nut | Bolt – ASTM A307 Gr. A Nut – ASTM A563A | ASTM A153 or B695 Class 55 or F2329 | FBB06 | |
| e2 | 4 | 5/8"-11 UNC [M16x2], 10" [254] Long Guardrail Bolt and Nut | Bolt – ASTM A307 Gr. A Nut – ASTM A563A | ASTM A153 or B695 Class 55 or F2329 | FBB03 | |
| e3 | 112 | 5/8"-11 UNC [M16x2], 1 1/4" [32] Long Guardrail Bolt and Nut | Bolt – ASTM A307 Gr. A Nut – ASTM A563A | ASTM A153 or B695 Class 55 or F2329 | FBB01 | |
| | | |  Midwest Roadside Safety Facility | TL-2 Bridge Rail Test No. N2BR-1 | | SHEET: 25 of 27 |
| | | | | Bill of Materials | | DATE: 8/4/2020 |
| | | | | DWG. NAME: NDOR_TL2BR_R11 | SCALE: None UNITS: in.[mm] | DRAWN BY: MES/JEK/S BW REV. BY: JK/SR/RB/ RF/KL/JH |

Figure 78. Bill of Materials, Test No. N2BR-1

| Item No. | QTY. | Description | Material Specification | Treatment Specification | Hardware Guide |
|----------|------|--|--|---|----------------|
| e4 | 12 | 5/8"—11 UNC [M16x2], 5" [127] Long Heavy Hex Head Bolt and Nut | Bolt — ASTM F3125 Gr. A325 Type 1 or Equivalent Nut — ASTM A563DH or Equivalent | ASTM A153 or B695 Class 55 or F1136 Gr. 3 or F2329 or F2833 Gr. 1 | FBX16b |
| e5 | 24 | 7/8"—9 UNC [M22x2.5], 24" [610] Long Threaded Rod | ASTM A449 or Equivalent | ASTM A153 or B695 Class 55 or F2329 | — |
| e6 | 24 | 7/8"—9 UNC [M22x2.5], 2" [51] Long Heavy Hex Head Bolt | ASTM A449 or Equivalent | ASTM A153 or B695 Class 55 or F2329 | FBX22b |
| e7 | 24 | 7/8" [22] Dia. Heavy Hex Coupling Nut | ASTM A563DH or Equivalent | ASTM A153 or B695 Class 55 or F2329 | — |
| e8 | 48 | 7/8" [22] Dia. Heavy Hex Nut | ASTM A563DH or Equivalent | ASTM A153 or B695 Class 55 or F2329 | FNX22b |
| e9 | 4 | 1" [25] Dia. Hex Nut | ASTM A563A | ASTM A153 or B695 Class 55 or F2329 | FBX24a |
| e10 | 4 | 5/8"—11 UNC [M16x2], 10" [254] Long Hex Head Bolt and Nut | Bolt — ASTM A307 Gr. A or Equivalent Nut — ASTM A563A or Equivalent | ASTM A153 or B695 Class 55 or F2329 | FBX16a |
| e11 | 4 | 7/8"—9 UNC [M22x2.5], 8" [203] Long Hex Head Bolt and Nut | Bolt — ASTM A307 Gr. A or Equivalent Nut — ASTM A563A or Equivalent | ASTM A153 or B695 Class 55 or F2329 | — |
| e12 | 16 | 5/8"—11 UNC [M16x2], 1 1/2" [38] Long Hex Head Bolt and Nut | Bolt — ASTM A307 Gr. A or Equivalent Nut — ASTM A563A or Equivalent | ASTM A153 or B695 Class 55 or F2329 | FBX16a |
| e13 | 12 | 5/16"—18 UNC [M8x1.25], 1 1/4" [32] Long Hex Head Bolt and Nut | Bolt — ASTM A307 Gr. A or Equivalent Nut — ASTM A563A or Equivalent | ASTM A153 or B695 Class 55 or F2329 | FBX08a |
| e14 | 15 | 16D Double Head Nail | — | — | — |
| f1 | 12 | 1 3/4"x1 3/4"x1/8" [44x44x3] Square Washer | ASTM A36 | ASTM A123 | FWR01 |
| f2 | 8 | 7/8" [22] Dia. Plain Round Washer | ASTM F844 | ASTM A123 or A153 or F2329 | — |
| f3 | 44 | 5/8" [16] Dia. Plain Round Washer | ASTM F844 | ASTM A123 or A153 or F2329 | FWC16a |
| f4 | 24 | 7/8" [22] Dia. Hardened Flat Washer | ASTM F436 | ASTM A153 or B695 Class 55 or F1136 Gr. 3 or F2329 | FWC24b |
| f5 | 4 | 1" [25] Dia. Plain Round Washer | ASTM F844 | ASTM A123 or A153 or F2329 | FWC24a |
| g1 | 2 | BCT Anchor Cable End Swaged Fiting | Fitting — ASTM A576 Gr. 1035 Stud — ASTM F568 Class C | Fitting — ASTM A153 Stud — ASTM A153 or B695 | — |
| g2 | 2 | 3/4" [190] Dia. 6x19, 24 1/2" [622] Long IWRC IPS Wire Rope | IPS | ASTM A741 Type II Class A | — |
| g3 | 4 | 115—HT Mechanical Splice — 3/4" [19] Dia. | As Supplied | — | — |
| g4 | 4 | Crosby Heavy Duty HT — 3/4" [19] Dia. Cable Thimble | Stock No. 1037773 | As Supplied | — |


| | | |
|---|-------------------------------------|---|
|  Midwest Roadside Safety Facility | TL—2 Bridge Rail Test No. N2BR—1 | SHEET: 26 of 27 DATE: 8/4/2020 DRAWN BY: MES/JEK/SBW |
| | Bill of Materials | |
| | DWG. NAME: NDOR_TL2BR_R11 | SCALE: None UNITS: in./mm |

Figure 79. Bill of Materials, Test No. N2BR-1


| Item No. | QTY. | Description | Material Specification | Treatment Specification | Hardware Guide |
|--|------|---|--|-------------------------|----------------|
| g5 | 4 | Crosby G2130 or S2130 Bolt Type Shackle – 1 1/4" [32] Dia. with thin head bolt, nut, and cotter pin, Grade A, Class 3 | Stock Nos. 1019597 and 1019604 – As Supplied | – | – |
| g6 | 4 | Chicago Hardware Drop Forged Heavy Duty Eye Nut – Drilled and Tapped 1 1/2" [38] Dia. – UNC 6 [M36x4] | Stock No. 107 – As Supplied | – | – |
| g7 | 2 | TLL–50K–PTB Load Cell | – | – | – |
| g8 | 2 | 8"x8"x5/8" [203x203x16] Anchor Bearing Plate | ASTM A36 | ASTM A123 | FPB01 |
| g9 | 2 | 2 3/8" [60] O.D. x 6" [152] Long BCT Post Sleeve | ASTM A53 Gr. B Schedule 40 | ASTM A123 | FMM02 |
| h1 | 2 | Anchor Bracket Assembly | ASTM A36 | ASTM A123 | FPA01 |
| h2 | 2 | Ground Strut Assembly | ASTM A36 | ASTM A123 | PFP02 |
| i1 | 1 | Grade Beam | Min f'c = 4,000 psi [27.6 MPa] | – | – |
| – | 1 | Concrete | Min. f'c = 6,000 psi [41.4 MPa] NE Mix 47BD | – | – |
| <div>  <div> <div> TL–2 Bridge Rail Test No. N2BR–1 </div> <div> Bill of Materials </div> </div> <div> <div> DWG. NAME: NDOR_TL2BR_R11 </div> <div> SCALE: None UNITS: in.[mm] </div> <div> REV. BY: JL/SR/RB/ RF/KL/JH </div> </div> <div> SHEET: 27 of 27 DATE: 8/4/2020 DRAWN BY: MES/JEK/S BW </div> </div> | | | | | |

Figure 80. Bill of Materials, Test No. N2BR-1



Figure 81. Test Installation Photographs, Test No. N2BR-1

6 TEST REQUIREMENTS AND EVALUATION CRITERIA

6.1 Test Requirements

Longitudinal barrier systems, such as bridge rails, must satisfy impact safety standards in order to be declared eligible for federal reimbursement by the Federal Highway Administration (FHWA) for use on the National Highway System (NHS). For new hardware, these safety standards consist of the guidelines and procedures published in MASH 2016 [1]. Note that there are no differences between MASH 2009 and MASH 2016 for longitudinal barriers, such as the bridge rail developed herein, except that additional occupant compartment deformation measurements, photographs, and documentation are required by MASH 2016. According to TL-2 of MASH 2016, longitudinal barrier systems must be subjected to two full-scale vehicle crash tests, as summarized in Table 3.

Table 3. MASH 2016 TL-2 Crash Test Conditions for Longitudinal Barriers

| Test Article | Test Designation No. | Test Vehicle | Vehicle Weight lb | Impact Conditions | | Evaluation Criteria ¹ |
|----------------------|----------------------|--------------|-------------------|-------------------|-------------|----------------------------------|
| | | | | Speed, mph | Angle, deg. | |
| Longitudinal Barrier | 2-10 | 1100C | 2,425 | 44 | 25 | A,D,F,H,I |
| | 2-11 | 2270P | 5,000 | 44 | 25 | A,D,F,H,I |

¹ Evaluation Criteria Explained in Table 4

Although MASH requires two full-scale crash tests, testing with the 1100C test vehicle was not deemed critical for the evaluation of the new bridge rail. Previous MASH crash testing has been conducted with both the 2270P and the 1100C vehicles on the MGS Bridge Rail and the TxDOT T631 bridge rail [3-5]. Similar to the NDOT TL-2 Bridge Rail developed herein, both of these previous bridge rails consist of 31-in. tall, 12-gauge, W-beam guardrail supported by S3x5.7 posts. Further, all three bridge rails were designed to absorb impact energy through bending of the weak S3x5.7 posts while the attachment of the post to the deck remains rigid and intact. The TxDOT T631 bridge rail was successfully tested to MASH test designation nos. 2-10 and 2-11 with a 75-in. post spacing, which is the same as the new NDOT TL-2 bridge rail. Additionally, the MGS Bridge Rail was successfully tested to MASH test designation nos. 3-10 and 3-11 with a 37.5-in. post spacing utilizing the same post assembly and HSS4x4x $\frac{3}{8}$ steel sockets incorporated into the new NDOT TL-2 bridge rail. Thus, if the socket assembly remained undamaged and intact throughout an impact event, the new TL-2 bridge rail would be expected to perform very similarly to the TL-2 version of the TxDOT T631. The increased mass of the 2270P test vehicle results in a higher impact severity, higher impact loads, and higher system deflections than observed during tests with the 1100C test vehicle. Therefore, MASH test designation no. 2-11 was deemed necessary to evaluate the post-to-deck connection strength of the new system, and MASH test designation no. 2-10 was determined to be non-critical. Should future knowledge gained from testing of this bridge rail or similar systems raise concerns regarding the new bridge railing's performance with small cars, it may become necessary to evaluate the bridge rail with the MASH 1100C vehicle.

6.2 Evaluation Criteria

Evaluation criteria for full-scale vehicle crash testing are based on three appraisal areas: (1) structural adequacy; (2) occupant risk; and (3) vehicle trajectory after collision. Criteria for structural adequacy are intended to evaluate the ability of the bridge railing to contain and redirect impacting vehicles. In addition, controlled lateral deflection of the test article is acceptable. Occupant risk evaluates the degree of hazard to occupants in the impacting vehicle. Post-impact vehicle trajectory is a measure of the potential of the vehicle to result in a secondary collision with other vehicles and/or fixed objects, thereby increasing the risk of injury to the occupants of the impacting vehicle and/or other vehicles. These evaluation criteria are summarized in Table 4 and defined in greater detail in MASH 2016. The full-scale vehicle crash test was conducted and reported in accordance with the procedures provided in MASH 2016.

In addition to the standard occupant risk measures, the Post-Impact Head Deceleration (PHD), the Theoretical Head Impact Velocity (THIV), and the Acceleration Severity Index (ASI) were determined and reported. Additional discussion on PHD, THIV and ASI is provided in MASH 2016.

Table 4. MASH 2016 Evaluation Criteria for Longitudinal Barriers

| | | | | |
|---------------------|----|---|-----------|-----------|
| Structural Adequacy | A. | Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underide, or override the installation although controlled lateral deflection of the test article is acceptable. | | |
| Occupant Risk | D. | Detached elements, fragments or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone. Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH 2016. | | |
| | F. | The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees. | | |
| | H. | Occupant Impact Velocity (OIV) (See Appendix A, Section A5.2.2 of MASH 2016 for calculation procedure) should satisfy the following limits: | | |
| | | Occupant Impact Velocity Limits | | |
| | | Component | Preferred | Maximum |
| | | Longitudinal and Lateral | 30 ft/s | 40 ft/s |
| | I. | The Occupant Ridedown Acceleration (ORA) (see Appendix A, Section A5.2.2 of MASH 2016 for calculation procedure) should satisfy the following limits: | | |
| | | Occupant Ridedown Acceleration Limits | | |
| | | Component | Preferred | Maximum |
| | | Longitudinal and Lateral | 15.0 g's | 20.49 g's |

6.3 Soil Strength Requirements

In accordance with Chapter 3 and Appendix B of MASH 2016, foundation soil strength must be verified before any full-scale crash testing can occur. During the installation of a soil dependent system, W6x16 posts are installed near the impact region utilizing the same installation procedures as the system. Prior to full-scale testing, a dynamic impact test must be conducted to verify a minimum dynamic soil resistance of 7.5 kips at post deflections between 5 and 20 in. measured at a height of 25 in. If dynamic testing near the system is not desired, MASH 2016 permits a static test to be conducted instead and compared against the results of a previously established baseline test. In this situation, the soil must provide a resistance of at least 90% of the static baseline test at deflections of 5, 10, and 15 in. Further details can be found in Appendix B of MASH 2016.

7 TEST CONDITIONS

7.1 Test Facility

The Outdoor Test Site is located at the Lincoln Air Park on the northwest side of the Lincoln Municipal Airport and is approximately 5 miles northwest of the University of Nebraska-Lincoln.

7.2 Vehicle Tow and Guidance System

A reverse-cable, tow system with a 1:2 mechanical advantage was used to propel the test vehicle. The distance traveled and the speed of the tow vehicle were one-half that of the test vehicle. The test vehicle was released from the tow cable before impact with the barrier system. A digital speedometer on the tow vehicle increased the accuracy of the test vehicle impact speed.

A vehicle guidance system developed by Hinch [14] was used to steer the test vehicle. A guide flag, attached to the left-front wheel and the guide cable, was sheared off before impact with the barrier system. The $\frac{3}{8}$ -in. diameter guide cable was tensioned to approximately 3,500 lb and supported both laterally and vertically every 100 ft by hinged stanchions. The hinged stanchions stood upright while holding up the guide cable, but as the vehicle was towed down the line, the guide flag struck and knocked each stanchion to the ground.

7.3 Test Vehicles

For test no. N2BR-1, a 2011 Dodge Ram 1500 was used as the test vehicle. The curb, test inertial, and gross static vehicle weights were 5,111 lb, 4,999 lb, and 5,160 lb, respectively. The test vehicle is shown in Figures 82 and 83, and vehicle dimensions are shown in Figure 84. Note that the test vehicle was within six model years of the 2017 research project contract date.

The longitudinal component of the center of gravity (c.g.) was determined using the measured axle weights. The Suspension Method [15] was used to determine the vertical component of the c.g. for the pickup truck. This method is based on the principle that the c.g. of any freely suspended body is in the vertical plane through the point of suspension. The vehicle was suspended successively in three positions, and the respective planes containing the c.g. were established. The intersection of these planes pinpointed the final c.g. location for the test inertial condition. The location of the final c.g. is shown in Figures 84 and 85. Data used to calculate the location of the c.g. and ballast information are shown in Appendix D.

Square, black- and white-checked targets were placed on the vehicle for reference to be viewed from the high-speed digital video cameras and aid in the video analysis, as shown in Figure 85. Round, checked targets were placed on the c.g. on the left-side door, the right-side door, and the roof of the vehicle.





Figure 82. Test Vehicle, Test No. N2BR-1



Figure 83. Vehicle Floor Pan and Undercarriage Prior to Test No. N2BR-1

| | | | | | |
|------------------------------|--|--|--|----------------------------------|--|
| Date: <u>4/12/2018</u> | | Test Name: <u>2NBR-1</u> | | VIN No: <u>1D7RB1DG4BS514230</u> | |
| Year: <u>2011</u> | | Make: <u>Dodge</u> | | Model: <u>Ram 1500</u> | |
| Tire Size: <u>P265/79R17</u> | | Tire Inflation Pressure: <u>40 Psi</u> | | Odometer: <u>152320</u> | |



Test Inertial CG

Vehicle Geometry - in. (mm)
Target Ranges listed below

| | |
|--|--|
| A: <u>76</u> (1930) <small>78±2 (1950±50)</small> | B: <u>74 3/4</u> (1899) |
| C: <u>229 1/2</u> (5829) <small>237±13 (6020±325)</small> | D: <u>42 3/8</u> (1076) <small>39±3 (1000±75)</small> |
| E: <u>140 3/8</u> (3566) <small>148±12 (3760±300)</small> | F: <u>46 3/4</u> (1187) |
| G: <u>28 1/4</u> (718) <small>min: 28 (710)</small> | H: <u>60 7/8</u> (1546) <small>63±4 (1575±100)</small> |
| I: <u>12</u> (305) | J: <u>25 1/4</u> (641) |
| K: <u>20 1/2</u> (521) | L: <u>29 1/4</u> (743) |
| M: <u>67 3/4</u> (1721) <small>67±1.5 (1700±38)</small> | N: <u>67 3/4</u> (1721) <small>67±1.5 (1700±38)</small> |
| O: <u>44</u> (1118) <small>43±4 (1100±75)</small> | P: <u>4 1/2</u> (114) |
| Q: <u>31 1/2</u> (800) | R: <u>18 1/2</u> (470) |
| S: <u>14 1/2</u> (368) | T: <u>76 1/2</u> (1943) |

U (impact width): 36 1/2 (927)

| |
|---|
| Wheel Center Height (Front): <u>15</u> (381) |
| Wheel Center Height (Rear): <u>15 1/8</u> (384) |
| Wheel Well Clearance (Front): <u>34 3/4</u> (883) |
| Wheel Well Clearance (Rear): <u>38</u> (965) |
| Bottom Frame Height (Front): <u>18</u> (457) |
| Bottom Frame Height (Rear): <u>25 3/4</u> (654) |

Engine Type: Gasoline

Engine Size: 5.7L

Transmission Type: automatic

Drive Type: RWD

Cab Style: Quad Cab

Bed Length: 67"

| Mass Distribution lb (kg) | | | |
|---------------------------|----------------------|----------------------|--|
| Gross Static | LF <u>1459</u> (662) | RF <u>1469</u> (666) | |
| | LR <u>1096</u> (497) | RR <u>1136</u> (515) | |


| Weights lb (kg) | Curb | Test Inertial | Gross Static |
|-----------------|--------------------|---|---|
| W-front | <u>2894</u> (1313) | <u>2831</u> (1284) | <u>2928</u> (1328) |
| W-rear | <u>2217</u> (1006) | <u>2168</u> (983) | <u>2232</u> (1012) |
| W-total | <u>5111</u> (2318) | <u>4999</u> (2268) <small>5000±110 (2270±50)</small> | <u>5160</u> (2341) <small>5165±110 (2343±50)</small> |

| GVWR Ratings lb | | Surrogate Occupant Data | |
|-----------------|-------------|-------------------------|--------------------|
| Front | <u>3700</u> | Type: | <u>Hybrid II</u> |
| Rear | <u>3900</u> | Mass: | <u>159 lb</u> |
| Total | <u>6700</u> | Seat Position: | <u>Right Front</u> |

Note any damage prior to test: Minor hail dents all over

Figure 84. Vehicle Dimensions, Test No. N2BR-1

Date: 4/12/2018 Test Name: 2NBR-1 VIN: 1D7RB1DG4BS514230
Year: 2011 Make: Dodge Model: Ram 1500



TARGET GEOMETRY-- in. (mm)

| | | |
|-------------------------|--------------------------|-------------------------|
| A: <u>71 1/2</u> (1816) | E: <u>63 5/16</u> (1608) | J: <u>39</u> (991) |
| B: <u>29 3/8</u> (746) | F: <u>63 3/8</u> (1610) | K: <u>28 1/4</u> (718) |
| C: <u>70 7/8</u> (1800) | G: <u>44 1/16</u> (1119) | L: <u>42 1/4</u> (1073) |
| D: <u>39</u> (991) | H: <u>60 7/8</u> (1546) | M: <u>61</u> (1549) |
| | I: <u>76 1/2</u> (1943) | |

Figure 85. Target Geometry, Test No. N2BR-1

The front wheels of the test vehicle were aligned to vehicle standards except the toe-in value was adjusted to zero such that the vehicles would track properly along the guide cable. A 5B flash bulb was mounted under the vehicle's right-side windshield wiper and was fired by a retroreflective optic speed trap mounted at the impact corner of the bumper. The flash bulb was fired upon initial impact with the test article to create a visual indicator of the precise time of impact on the high-speed digital videos. A radio-controlled brake system was installed in the test vehicle so the vehicle could be brought safely to a stop after the test.

7.4 Simulated Occupant

For test no. N2BR-1, a Hybrid II 50th-Percentile, Adult Male Dummy equipped with footwear was placed in the right-front seat of the test vehicle with the seat belt fastened. The simulated occupant had a final weight of 159 lb. As recommended by MASH 2016, the simulated occupant was not included in calculating the c.g. location.

7.5 Data Acquisition Systems

7.5.1 Accelerometers

Two environmental shock and vibration sensor/recorder systems were used to measure the accelerations in the longitudinal, lateral, and vertical directions. Both accelerometer systems were mounted near the c.g. of the test vehicle. The electronic accelerometer data obtained in dynamic testing was filtered using the SAE Class 60 and the SAE Class 180 Butterworth filters conforming to the SAE J211/1 specifications [8].

The primary system, the SLICE-1 unit, was a modular data acquisition system manufactured by Diversified Technical Systems, Inc. (DTS) of Seal Beach, California. The SLICE-1 unit was designated as the primary system. The acceleration sensors were mounted inside the body of a custom-built, SLICE 6DX event data recorder and recorded data at 10,000 Hz to the onboard microprocessor. The SLICE 6DX was configured with 7 GB of non-volatile flash memory, a range of ± 500 g's, a sample rate of 10,000 Hz, and a 1,650 Hz (CFC 1000) anti-aliasing filter. The "SLICEWare" computer software program and a customized Microsoft Excel worksheet were used to analyze and plot the accelerometer data.

The second accelerometer system, the DTS unit, was a two-arm piezoresistive accelerometer system manufactured by Endevco of San Juan Capistrano, California. Three accelerometers were used to measure each of the longitudinal, lateral, and vertical accelerations independently at a sample rate of 10,000 Hz. The accelerometers were configured and controlled using a system developed and manufactured by DTS of Seal Beach, California. More specifically, data was collected using a DTS Sensor Input Module (SIM), Model TDAS3-SIM-16M. The SIM was configured with 16 MB SRAM and 8 sensor input channels with 250 kB SRAM/channel. The SIM was mounted on a TDAS3-R4 module rack. The module rack was configured with isolated power/event/communications, 10BaseT Ethernet and RS232 communication, and an internal backup battery. Both the SIM and module rack were crashworthy. The "DTS TDAS Control" computer software program and a customized Microsoft Excel worksheet were used to analyze and plot the accelerometer data.

7.5.2 Rate Transducers

An angular rate sensor system mounted inside the body of the SLICE-event data recorder was used to measure the rates of rotation of the test vehicle. Each SLICE MICRO Triax ARS had a range of 1,500 degrees/sec in each of the three directions (roll, pitch, and yaw) and recorded data at 10,000 Hz to the onboard microprocessors. The raw data measurements were then downloaded, converted to the proper Euler angles for analysis, and plotted. The “SLICEWare” computer software program and a customized Microsoft Excel worksheet were used to analyze and plot the angular rate sensor data.

A second angular rate sensor, the DTS ARS-1500, with a range of 1,500 degrees/sec in each of the three directions (roll, pitch, and yaw) was used to measure the rates of rotation of the test vehicles. The angular rate sensor was mounted on an aluminum block inside the test vehicle near the c.g. and recorded data at 10,000 Hz to the DTS SIM. The raw data measurements were then downloaded, converted to the proper Euler angles for analysis, and plotted. The “DTS TDAS Control” computer software program and a customized Microsoft Excel worksheet were used to analyze and plot the angular rate sensor data.

7.5.3 Retroreflective Optic Speed Trap

The retroreflective optic speed trap was used to determine the speed of the test vehicle before impact. Five retroreflective targets, spaced at approximately 18 in. intervals, were applied to the side of the vehicle. When the emitted beam of light was reflected by the targets and returned to the Emitter/Receiver, a signal was sent to the data acquisition computer, recording at 10,000 Hz, as well as the external LED box activating the LED flashes. The speed was then calculated using the spacing between the retroreflective targets and the time between the signals. LED lights and high-speed digital video analysis are only used as a backup in the event that vehicle speeds cannot be determined from the electronic data.

7.5.4 Load Cells and String Potentiometers

Load cells were installed in the upstream and downstream anchor cables for test no. N2BR-1 but did not record data due to technical difficulties. The load cells were Transducer Techniques model no. TLL-50K with a load range up to 50 kips. During testing, output voltage signals were sent from the transducers to a National Instruments PCI-6071E data acquisition board, acquired with LabView software, and stored on a personal computer at a sample rate of 10,000 Hz.

7.5.5 Digital Photography

Six high-speed AOS digital video cameras, ten GoPro digital video cameras, and three JVC digital video cameras were utilized to film test no. N2BR-1. Camera details, camera operating speeds, lens information, and a schematic of the camera locations relative to the system are shown in Figure 86 and Table 5. The high-speed videos were analyzed using TEMA Motion and Redlake MotionScope software programs. Actual camera speed and camera divergence factors were considered in the analysis of the high-speed videos. A digital still camera was also used to document pre- and post-test conditions of the system and vehicle.




Figure 86. Camera Location Diagram, Test No. N2BR-1

Table 5. Camera Locations, Speeds, and Lens Settings, Test No. N2BR-1

| No. | Type | Operating Speed frames/sec | Lens | Lens Setting |
|-------|--------------------|-------------------------------|----------------------|--------------|
| AOS-2 | AOS Vitcam CTM | 500 | Kowa 16 mm Fixed | - |
| AOS-5 | AOS Vitcam CTM | 500 | Telesar 135 mm Fixed | - |
| AOS-6 | AOS X PRI Gigabit | 500 | Fujinon 50 mm Fixed | - |
| AOS-7 | AOS X-PRI Gigabit | 500 | Sigma 28-70 #2 | 35 |
| AOS-8 | AOS S-VIT 1531 | 500 | Sigma 28-70 #1 | 28 |
| AOS-9 | AOS X-TRI-VIT 2236 | 1000 | Kowa 12 mm Fixed | - |
| GP-5 | GoPro Hero 3+ | 120 | | |
| GP-6 | GoPro Hero 3+ | 120 | | |
| GP-7 | GoPro Hero 4 | 120 | | |
| GP-8 | GoPro Hero 4 | 240 | | |
| GP-9 | GoPro Hero 4 | 120 | | |
| GP-10 | GoPro Hero 4 | 240 | | |
| GP-15 | GoPro Hero 4 | 120 | | |
| GP-16 | GoPro Hero 4 | 120 | | |
| GP-17 | GoPro Hero 4 | 120 | | |
| GP-18 | GoPro Hero 4 | 120 | | |
| JVC-2 | JVC 2 | 29 | | |
| JVC-3 | JVC 3 | 29 | | |
| JVC-4 | JVC 4 | 29 | | |

8 FULL-SCALE CRASH TEST NO. N2BR-1

8.1 Static Soil Test

Before full-scale crash test no. N2BR-1 was conducted, the strength of the foundation soil was evaluated with a static test, as described in MASH 2016. The static test results, as shown in Appendix E, demonstrated a soil resistance above the baseline test limits. Thus, the soil provided adequate strength, and full-scale crash testing could be conducted on the barrier system.

8.2 Weather Conditions

Test no. N2BR-1 was conducted on April 12, 2018 at approximately 1:15 p.m. The weather conditions as per the National Oceanic and Atmospheric Administration (station 14939/LNK) were reported and are shown in Table 6.

Table 6. Weather Conditions, Test No. N2BR-1

| | |
|------------------------------|---------------------|
| Temperature | 70° F |
| Humidity | 37% |
| Wind Speed | 16 mph |
| Wind Direction | 90° |
| Sky Conditions | Windy Partly Cloudy |
| Visibility | 10.0 Statute Miles |
| Pavement Surface | Dry |
| Previous 3-Day Precipitation | 0 in. |
| Previous 7-Day Precipitation | 0.2 in. |

8.3 Test Description

Initial vehicle impact was to occur 123 in. upstream from the centerline of the splice between post nos. 14 and 15, as shown in Figure 87. This impact point was selected using the CIP plots found in Section 2.3 of MASH 2016. The 4,999-lb pickup truck impacted the new TL-2 bridge rail at a speed of 44.2 mph and at an angle of 25.5 degrees. The actual point of impact was 2.6 in. downstream from the targeted location. During the impact event, the bridge railing contained the pickup truck and smoothly redirected it back onto the bridge. The vehicle's right-front tire extended over the edge of the deck, but the vehicle remained stable with minimal roll. The front-right tire snagged on the socket supporting post no. 17, causing the wheel to disengage. The tire snag resulted in about a 10-g longitudinal acceleration pulse, which remained well within the MASH limits, and only minor pitch and roll displacements. After exiting the system, the brakes were applied, and the vehicle veered back toward the system and impacted the MGS downstream of the bridge rail. The vehicle came to rest adjacent to the downstream anchorage 104 ft – 5 in. downstream from the initial impact point after brakes were applied.

A detailed description of the sequential impact events is contained in Table 7. Sequential photographs are shown in Figures 88 and 89. Documentary photographs of the crash test are shown in Figure 90. The vehicle trajectory and final position are shown in Figure 91.




Figure 87. Impact Location, Test No. N2BR-1

Table 7. Sequential Description of Impact Events, Test No. N2BR-1

| TIME sec | EVENT |
|-------------|--|
| 0.000 | Vehicle's front bumper impacted the system 120.4 in. upstream from the centerline of the splice between post nos. 14 and 15 at 44.2 mph. |
| 0.006 | System began to deflect backward. |
| 0.016 | Vehicle's right-front tire contacted system. |
| 0.030 | Vehicle's hood began to deform and post nos. 13 and 14 began to deflect backward. |
| 0.038 | Post no. 15 began to deflect backward. |
| 0.060 | Vehicle pitched downward. |
| 0.080 | Vehicle's right-front tire passed over the edge of the bridge deck. |
| 0.108 | Vehicle's bumper impacted post no. 14 and bent it downstream. |
| 0.162 | Post no. 16 began to deflect backward. |
| 0.172 | Post no. 17 began to deflect backward. |
| 0.206 | Vehicle's bumper impacted post no. 15 and bent it downstream. |
| 0.218 | Vehicle began to roll toward system. |
| 0.290 | Rear of vehicle impacted rail near post no. 13. |
| 0.310 | Vehicle's right-rear tire passed over the edge of the bridge deck. |
| 0.336 | Vehicle's bumper impacted post no. 16 and bent it downstream. |
| 0.349 | Vehicle was parallel to the system at a velocity of 31.2 mph. |
| 0.380 | Vehicle reached maximum positive roll value of 12.1 degrees and began to roll away from the system. |
| 0.510 | Vehicle's right-front tire impacted the socket supporting post no. 17. |
| 0.548 | Vehicle's right-front tire detached from vehicle. |
| 0.680 | Vehicle's right-front tire was on top of post no. 17, which was bent downstream. |
| 0.723 | Vehicle reached maximum negative roll of -11.2 degrees. |
| 0.846 | Vehicle's left-front tire became airborne. |
| 0.860 | Vehicle became airborne. |
| 0.952 | Vehicle exited system at a velocity of 19.7 mph. |
| 0.970 | Vehicle's right-front tire impacted post and socket no. 18 and bounced backward. |
| 1.064 | Vehicle's right-rear tire contacted ground. |
| 1.120 | Vehicle's left-front tire returned to the ground. |
| 1.270 | Vehicle's right-front corner impacted ground. |
| 1.710 | Vehicle began to yaw and veer toward system. |
| 1.840 | Vehicle's right-front fender contacted system between post nos. 23 and 24. |
| 1.996 | Vehicle yawed away from system. |
| 2.710 | Vehicle exited system again traveling nearly parallel to rail. |
| 3.400 | Vehicle contacted rail near downstream anchorage |
| 5.340 | Vehicle came to a stop. |



0.000 sec



0.250 sec



0.500 sec



0.750sec



1.000 sec



1.250 sec



0.000 sec



0.250 sec



0.500 sec



0.750 sec



1.000 sec



1.250 sec

Figure 88. Sequential Photographs, Test No. N2BR-1



0.000 sec



0.250 sec



0.500 sec



0.750 sec



1.000 sec



1.250 sec



0.000 sec



0.250 sec



0.500 sec



0.750 sec



1.000 sec



1.250 sec

Figure 89. Additional Sequential Photographs, Test No. N2BR-1



Figure 90. Documentary Photographs, Test No. N2BR-1



Figure 91. Vehicle Trajectory Marks and Final Position, Test No. N2BR-1

8.4 Barrier Damage

Damage to the barrier was moderate, as shown in Figures 92 through 95. Barrier damage consisted of contact marks extending from post nos. 13 to 17, as well as rail deformations, post bending and tearing, and guardrail bolt release. The length of vehicle contact along the barrier was approximately 27 ft which spanned from 6½ in. upstream from the impact point to 5 in. downstream from post no. 17. Guardrail scrapes and deformations in the form of kinking and flattening were observed throughout the contact region. Four additional kinks were observed downstream from post no. 17, outside of the contact region. Guardrail bolt fracture occurred in post nos. 13 through 17.

Post no. 12 was bent slightly backward and post no. 13 was bent backward and downstream. Post nos. 14 through 17 were bent downstream approximately 90 degrees, and the upstream flanges of these posts were torn adjacent to the welded post standoffs. Tears extended through the upstream edge of the flange and through the web, with tears in post nos. 14 through 16 extending 1¼ in., and the tear in post no. 17 extending 2 in. Scrapes were located on the upstream edge of the flange and front face of the flange on post nos. 13 through 17, beginning near the base of the post and extending upward.

Little to no damage occurred to the post socket assemblies. Only very minor deformations on the top edges were found on the sockets at post nos. 14 through 17. The sockets at post nos. 14 through 17 were rotated downstream, but not damaged. The tolerance provided by the vertical slots in the mounting plate allowed for the small rotations of these socket assemblies. The attachment bolts and the bridge deck were undamaged. Damage to the test installation due to the secondary impacts was negligible, consisting mostly of contact marks.

The maximum lateral permanent set of the barrier system was 20 in., which occurred on the guardrail located at mid-span between post nos. 14 and 15, as measured in the field. The maximum lateral dynamic barrier deflection was 32.6 in. measured on the guardrail at mid-span between post nos. 14 and 15, as determined from high-speed digital video analysis. The working width of the system was found to be 38.4 in., also determined from high-speed digital video analysis.



Overall System Damage, Upstream View



Overall System Damage, Front View



Overall System Damage, Upstream Behind View



Overall System Damage, Downstream Behind View

Figure 92. System Damage, Test No. N2BR-1



Post Nos. 13 and 14 Damage



Post Nos. 14 and 15 Damage



Post Nos. 15 and 16 Damage




Post Nos 16 and 17 Damage

Figure 93. System Damage, Front-Side Views, Test No. N2BR-1



Post Nos. 13 and 14 Rear Damage



Post Nos. 14 and 15 Rear Damage



Post Nos. 15 and 16 Rear Damage



Post Nos. 16 and 17 Rear Damage

Figure 94. System Damage, Back-Side Views, Test No. N2BR-1



Post No. 14 Tearing



Post No. 15 Tearing



Post No. 16 Tearing



Post No. 17 Tearing

Figure 95. System Damage, Post Bending and Tearing, Test No. N2BR-1

8.5 Vehicle Damage

The damage to the vehicle was moderate, as shown in Figures 96 through 98. The maximum occupant compartment deformations are listed in Table 8 along with the intrusion limits established in MASH 2016 for various areas of the occupant compartment. Complete occupant compartment and vehicle deformations and the corresponding locations are provided in Appendix F. MASH 2016 defines intrusion or deformation as the occupant compartment being deformed and reduced in size with no observed penetration. There were no penetrations into the occupant compartment and none of the established MASH 2016 deformation limits were violated. Outward deformations, which are denoted as negative numbers in Appendix F, are not considered crush toward the occupant, and are not evaluated by MASH 2016 criteria.

The majority of the damage was concentrated on the right-front corner of the vehicle where the impact had occurred. The right-front bumper and fender were crushed inward. The right-front tire and right-front headlight were disengaged from the vehicle, and the bumper bent back and under the vehicle. Scraping was observed along the vehicle's entire right side. Denting was observed on the right-rear fender. Scraps and minor dents were observed to undercarriage components on the right side of the vehicle. Damage to the suspension consisted of scrapes to the right front and right rear shocks, as well as to the lower control arm. The steering knuckle assemblies, tie rod, and lower control arm all disengaged from the right side of the vehicle. Damage to the chassis consisted of minor scrapes on the lower rear end shock mount. The drive train remained undamaged.



Figure 96. Vehicle Damage, Test No. N2BR-1



Figure 97. Vehicle Undercarriage Damage, Test No. N2BR-1




Figure 98. Vehicle Interior Damage, Test No. N2BR-1

Table 8. Maximum Occupant Compartment Deformations by Location, Test No. N2BR-1

| LOCATION | MAXIMUM INTRUSION in. | MASH 2016 ALLOWABLE INTRUSION in. |
|---|-----------------------------|--|
| Wheel Well & Toe Pan | 0.1 | ≤ 9 |
| Floor Pan & Transmission Tunnel | -0.2 | ≤ 12 |
| A-Pillar | 0.1 | ≤ 5 |
| A-Pillar (Lateral) | 0.1 | ≤ 3 |
| B-Pillar | 0.4 | ≤ 5 |
| B-Pillar (Lateral) | 0.4 | ≤ 3 |
| Side Front Panel (in Front of A-Pillar) | 0.2 | ≤ 12 |
| Side Door (Above Seat) | 0.3 | ≤ 9 |
| Side Door (Below Seat) | 0.4 | ≤ 12 |
| Roof | 0 | ≤ 4 |
| Windshield | 0 | ≤ 3 |
| Side Window | Intact | No shattering resulting from contact with structural member of test article |
| Dash | 0.3 | N/A |

Note: Negative values denote outward deformation
N/A – No MASH 2016 criteria exist for this location

8.6 Occupant Risk

The calculated occupant impact velocities (OIVs) and maximum 0.010-sec average occupant ridedown accelerations (ORAs) in both the longitudinal and lateral directions are shown in Table 9. Note that the OIVs and ORAs were within suggested limits, as provided in MASH 2016. The calculated THIV, PHD, and ASI values are also shown in Table 9. The recorded data from the accelerometers and the rate transducers are shown graphically in Appendix G.

Table 9. Summary of OIV, ORA, THIV, PHD, and ASI Values, Test No. N2BR-1

| Evaluation Criteria | | Transducer | | MASH 2016 Limits |
|------------------------------------|--------------|-------------------|--------|------------------|
| | | SLICE-1 (primary) | DTS | |
| OIV ft/s | Longitudinal | -11.52 | -12.50 | ±40 |
| | Lateral | -11.55 | -10.53 | ±40 |
| ORA g's | Longitudinal | -10.98 | -10.34 | ±20.49 |
| | Lateral | 5.74 | -4.93 | ±20.49 |
| MAX. ANGULAR DISPL. deg. | Roll | 12.1 | -11.2 | ±75 |
| | Pitch | 1.9 | 3.2 | ±75 |
| | Yaw | -32.3 | -32.4 | not required |
| THIV ft/s | | 15.58 | 15.55 | not required |
| PHD g's | | 11.66 | 10.74 | not required |
| ASI | | 0.48 | 0.49 | not required |

8.7 Discussion

The analysis of the test results for test no. N2BR-1 showed that the bridge rail adequately contained and redirected the 2270P vehicle with controlled lateral displacements of the barrier. Detached elements, fragments, or other debris from the test article did not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or work zone personnel. Deformations of, or intrusions into the occupant compartment that could have caused serious injury did not occur. The test vehicle did not ride over the barrier and remained upright during and after the collision. Vehicle roll, pitch, and yaw angular displacements, as shown in Appendix G, were deemed acceptable because they did not adversely influence occupant risk nor cause rollover. After impact, the vehicle exited the barrier at an angle of -1.0 degrees, and its trajectory did not violate the bounds of the exit box. Therefore, test no. N2BR-1 was determined to be acceptable according to the MASH 2016 safety performance criteria for test designation no. 2-11. A summary of the test results and sequential photographs are shown in Figure 99.




Figure 99. Summary of Test Results and Sequential Photographs, Test No. N2BR-1

9 BRIDGE RAIL TRANSITION TO MGS

9.1 Background and Scope

Barrier transitions are often required to safely connect longitudinal barrier systems of different components and/or lateral stiffnesses. The new TL-2 bridge rail developed herein utilizes the same guardrail, barrier height, and post spacing as standard MGS. However, the difference between the S3x5.7 bridge rail post and the W6x8.5/W6x9 of the MGS results in a different lateral stiffness. Thus, the connection between the two guardrail systems was required.

To evaluate if a transition was necessary between the MGS and the new TL-2 bridge rail, vehicle crash test simulations were performed with BARRIER VII. BARRIER VII is a computer program used extensively to model and analyze vehicle crashes into guardrail systems [18-19]. In this program, the barrier and vehicle are idealized as two-dimensional structures in the horizontal plane, meaning that vertical displacements of the barrier or the vehicle are not considered. BARRIER VII models post and beam systems using a rail that yields at nodal locations and elastic, perfectly-plastic posts. Thus, component models of W6x9 posts, S3x5.7 posts, anchor posts, and 12-gauge W-beam guardrail were required to perform the analysis. The vehicle was idealized as a rigid body of prescribed shape surrounded by a cushion of discrete springs.

The primary purpose of the transition analysis was to evaluate guardrail pocketing angles at the transition from the weaker S3x5.7 TL-2 bridge rail posts to stiffer W6x9 MGS posts. Large guardrail pocketing angles in front of an impacting vehicle have been associated with vehicle instabilities, vehicle snag, excessive decelerations, high rail loads, and even rail rupture. Pocketing angles less than 30 degrees are typically considered safe for guardrail systems, while pocketing angles greater than 30 degrees run a higher risk of failure [3]. Barrier deflections and forces were also determined through the analysis.

9.2 BARRIER VII Model

To simulate test no. N2BR-1, a BARRIER VII model with a system length of 225 ft was used, consisting of 75 ft of MGS upstream and downstream from a 75-ft section of the TL-2 bridge rail. The upstream and downstream portions of the MGS were intentionally made longer than the full-scale crash test because it was not desired to significantly load the anchor posts due to BARRIER VII's limitations in accurately depicting their behavior. The barrier consisted of a updated 12-gauge W-beam rail model, which spanned the entire length of the system, and four different post sections: 1) a simulated strong anchor post, 2) a second BCT post at upstream and downstream ends of the system, 3) W6x9 posts for the MGS, and 4) S3x5.7 posts for the bridge rail.

Initially, properties for the posts and W-beam were obtained from previous BARRIER VII studies and from nominal cross-section properties of the components. However, after conducting initial simulations and comparing the result to full-scale crash tests, the properties were modified to provide more accurate results. These modifications are described in the following sections.

9.2.1 Post Models

Force versus deflection characteristics observed from previous bogie tests provided the basis for the post models. Data obtained from bogie testing of the S3x5.7 posts determined the initial bending moments about the strong and weak axis at the base of the post were 142.9 and 46.9 kips/in., respectively. These strengths were reduced by a factor of 0.7 to 32.8 and 100 kips/in., respectively, to account for rail twisting commonly observed in guardrail tests, including test no. N2BR-1. Bending strengths for the W6x9 posts were obtained in a similar manner with guidance from previous BARRIER VII models evaluating the MGS. A deflection of 15 in. was established as the failure limit for both posts. Calibrated post parameters for the W6x9 and S3x5.7 posts used in the BARRIER VII simulations are shown in Table 10.

Table 10. BARRIER VII Post Input Parameters

| BARRIER VII Parameters | | W6x9 Input Values | S3x5.7 Input Values |
|---|---------|-------------------|---------------------|
| K_B - Post Stiffness Along B (strong axis) | kip/in. | 5.0 | 2.5 |
| K_A - Post Stiffness Along A (weak axis) | kip/in. | 3.0 | 2.5 |
| M_A - Moment About A (strong axis) | kip-in. | 180.0 | 100.0 |
| M_B - Moment About B (weak axis) | kip-in. | 92.0 | 32.8 |
| δ_A - Failure Displacement Along B | in. | 15 | 15 |
| δ_B - Failure Displacement Along B | in. | 15 | 15 |

9.2.2 Anchor Models

Two modified BCT posts were utilized within the guardrail anchorages positioned at each end of the test installations. These posts were inserted into 6-ft long steel foundation tubes, and a ground line strut was positioned between the anchor posts, and a cable anchor was attached between the end post and the guardrail section.

In BARRIER VII, the ground line strut and cable were not modeled for simplicity. To accommodate for this, the two end anchor posts were modeled with significantly stiffer post parameters to compensate for the lack of the ground line strut and cable [20-21]. Calibrated post parameters for the anchor and BCT posts used in the BARRIER VII simulations are shown in Table 11

Table 11. BARRIER VII Anchor Post Input Parameters

| BARRIER VII Parameters | | Strong Anchor Post Values | Second BCT Post Input Values |
|---|---------|---------------------------|------------------------------|
| K_B - Post Stiffness Along B (strong axis) | kip/in. | 6.0 | 3.0 |
| K_A - Post Stiffness Along A (weak axis) | kip/in. | 6.0 | 3.0 |
| M_A - Moment About A (strong axis) | kip-in. | 180.0 | 225.0 |
| M_B - Moment About B (weak axis) | kip-in. | 92.0 | 150 |
| δF - Failure Displacement Along B | in. | 15 | 15 |

9.2.3 W-Beam Guardrail Model

Previous W-beam guardrail models were based on the material and geometrical properties of undamaged guardrail. However, these nominal values were believed to be the source of error in the simulations. During an impact event, W-beam guardrail is flattened and stretched. Flattened W-beam sections have much less bending strength than undamaged rail due to the change in the cross-section shape. BARRIER VII is incapable of altering the cross-sectional properties of a component during a simulation. As such, the cross section and bending strength of the W-beam in BARRIER VII had to be reduced from the nominal values to better replicate reality. Further, tensile loads in guardrail systems result in the W-beam segments shifting relative to one another at splice locations, effectively elongating the guardrail. BARRIER VII does not model splices, so the cross-sectional area of the W-beam had to be reduced to allow the rail to elongate during impacts. The nominal and adjusted properties for the W-beam guardrail in BARRIER VII are shown in Table 12.

Table 12. Adjusted W-beam Properties in BARRIER VII

| Property | Nominal W-beam Value | Adjusted W-beam Value |
|---------------------|-----------------------|-----------------------|
| Rail I _x | 2.29 in. ⁴ | 0.75 in. ⁴ |
| Rail P _y | 99.5 kip | 99.5 kip |
| Rail M _y | 68.5 kip-in. | 17 kip-in. |
| Rail A | 1.99 in. ² | 0.5 in. ² |

A uniform mesh density was used across the entire length of the guardrail. A node spacing of 9³/₈ in. was used, requiring 289 nodes for the 225-ft long system.

9.2.4 Coefficient of Friction

Contact interfaces between the vehicle and barrier were defined within BARRIER VII with a coefficient of friction. This global coefficient of friction was utilized to account for vehicle-rail friction, vehicle-post friction, and wheel snag during the impact event. The kinetic friction value

was calibrated according to the physical test's exit time, parallel time, and length of contact in order to provide the most accurate results. The selected coefficient of friction was 0.27.

9.3 TL-2 Bridge Rail Model Verification

Validation of the BARRIER VII model was conducted through comparison of BARRIER VII results to that of full-scale crash test no. N2BR-1. The simulated 2270P vehicle was given the same impact speed, impact angle, and impact point as the full-scale test. The model was evaluated on a number of parameters, including vehicle time to parallel, vehicle speed at parallel, maximum displacement, and maximum pocketing angle. Pocketing angles for both the simulation and the physical test were calculated over a 37.5-in. distance, or half post spacing. A comparison of the results is shown in Table 13.

Table 13. Comparison of BARRIER VII Results to Test No. N2BR-1

| Parameter | Test No. N2BR-1 | BARRIER VII Model |
|---|---|---|
| Vehicle Parallel Time Speed | 0.349 sec 31.16 mph | 0.357 sec 32.1 mph |
| Displacement Maximum Location Time | 32.1 in. Post 15 0.290 sec | 32.2 in. Post 15 0.250 sec |
| Pocketing Angle Max. Angle Location Time | 17° Mid-span Post 15-16 0.300 sec | 15° Mid-span Post 15-16 0.280 sec |

The BARRIER VII simulation matched the results of the full-scale crash test rather well over the first 0.400 sec of the impact. The vehicle parallel time and speed were very similar, the system displacements were nearly identical, and the maximum pocketing angles were within 2 degrees. Post failure was defined in the BARRIER VII simulations as post displacements greater than 15 in. BARRIER VII determined 4 posts failed according to this failure criteria, and post nos. 14 through 17 had bent completely over in the physical test. A graphical comparison of the simulation to the physical test is shown in Figures 100 through 106. After approximately 0.400 s, the model began to deviate from the full-scale test. BARRIER VII is known for having difficulties simulating system rebound and restoration forces. As such, the results do not match up as well as the vehicle exits the system. Fortunately, all the evaluation metrics for the simulations (e.g., maximum displacements and pocketing angles) occur before the vehicle reaches parallel and starts to exit the system. Therefore, based on the comparison to the physical test described herein, the model of the new TL-2 bridge rail was considered validated.





Figure 100. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1





Figure 101. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1





Figure 102. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1





Figure 103. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1







Figure 104. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1





Figure 105. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1







Figure 106. Sequential Figures from BARRIER VII Simulation and Test No. N2BR-1

9.4 MGS Model Validation

At the time of this study, there had not been a MASH TL-2 test conducted on a standard MGS installation. Thus, the BARRIER VII MGS model was validated against a TL-3 crash test, test no. ILT-1, which evaluated the MGS placed in front of a breakaway luminaire pole [22]. Additionally, to evaluate the new W-beam properties in a more rigorous test, the new BARRIER VII model components were also validated against test no. MGSMP-1, which was an MGS system with a missing post [23]

9.4.1 Simulation of MGS at TL-3

Test no. ILT-1 was conducted to evaluate the performance of the MGS when a breakaway light pole is placed behind the guardrail [22]. The BARRIER VII model to replicate test no. ILT-1 consisted of 175 ft of W-beam guardrail comprised of 225 nodes spaced at 9³/₈ in. The model had 25 W6x9 posts spaced at 75 in. and was anchored on both ends by two simulated strong BCT anchor posts. All guardrail and anchor post properties used in the validation of the new TL-2 bridge rail remained the same, even the coefficient of friction of 0.27.

The simulation was conducted with the 2270P vehicle impacting the system with the same impact speed, impact angle, and impact point as test no. ILT-1. A comparison of the BARRIER VII results to the physical test is shown in Table 16. Parallel times, pocketing angles, and the locations of the pocketing angle were very similar. The maximum system displacement was also similar, though the location of the displacement and the time of displacement were slightly different. Overall, the simulation results matched well with the crash test.

Table 14. Comparison of BARRIER VII Results to Test No. ILT-1

| Parameter | Test No. ILT-1 | BARRIER VII Model |
|---|---|--|
| Vehicle Parallel Time Speed | 0.323 sec 37.9 mph | 0.308 sec 44.5 mph |
| Displacement Maximum Location Time | 44.1 in. Post 14 0.300 sec | 42.2 in. Mid-span Post 13-14 0.250 sec |
| Pocketing Angle Max. Angle Location Time | 21.2° Mid-span Post 14-15 0.230 sec | 19.6° Mid-span Post 14-15 0.270 sec |

9.4.2 Simulation of MGS with Missing Post at TL-3

Test no. MGSMP-1 was conducted to evaluate the performance of the MGS when one post is not installed at a given point, leaving a 150-in. gap between two posts [23]. The BARRIER VII model used to replicate test no. MGSMP-1 was identical to the model used for replicating test no. ILT-1, except a single post was removed from the model. The simulation was conducted with the

2270P vehicle impacting the system at the same speed, angle, and impact point as the physical test. A comparison of the BARRIER VII results to the physical test is shown in Table 17. Parallel times, pocketing angles, and the locations of the pocketing angle were very similar. The maximum system displacements did not match as well but were still less than 8 percent different. Overall, the simulation results matched well with the crash test.

Table 15. Comparison of BARRIER VII Results to Test no. MGSMP-1

| Parameter | Test No. MGSMP-1 | BARRIER VII Model |
|---|---|--|
| Vehicle Parallel Time Speed | 0.310 sec 43.1 mph | 0.298 sec 46 mph |
| Displacement Maximum Location Time | 49 in. Post 14 0.330 sec | 45.3 in. Mid-span Post 13-14 0.350 sec |
| Pocketing Angle Max. Angle Location Time | 23.8° Mid-span Post 14-15 0.270 sec | 21.3° Mid-span Post 14-15 0.290 sec |

9.5 Baseline TL-2 MGS Simulations

For comparison purposes, baseline simulations were conducted on the validated BARRIER VII models of both the new bridge rail and the standard MGS with the prescribed MASH TL-2 impact conditions. The baseline models were both impacted at the mid span of the guardrail at a speed of 44 mph and an impact angle of 25 degrees. The TL-2 bridge rail had a maximum deflection of 31.01 in., while the MGS only had a deflection of 20.4 in. The MGS baseline produced a maximum pocketing angle of 16.6 degrees between post nos. 14 and 15 at 200 ms, and the TL-2 bridge rail baseline produced a maximum pocketing angle of 15.8 degrees between post nos. 15 and 16. Parallel time in the MGS baseline simulation occurred at 354 ms when the vehicle was traveling at 31.4 mph, and occurred at 326 ms when the vehicle was traveling at 31.1 mph.

9.6 Simulation of Transition from MGS to TL-2 Bridge Rail

Once the BARRIER VII model was validated, simulations were run to evaluate the connection of the new TL-2 bridge rail to standard MGS. Similar to the crash test, the model had a 75-in. spacing between adjacent bridge posts and MGS posts, thus maintaining a constant 75-in. post spacing through the system. A total of 25 impacts over an 18.75-ft long span were simulated with the vehicle impacting the system according to MASH TL-2 conditions. The 25 impact points correspond to nodes nos. 169 to 185 in the BARRIER VII model shown in Figures 107 through 109. These nodes correspond to the mid-span between post nos. 21 and 22 to the midspan between post nos. 24 and 25, with post no. 25 being the first MGS post downstream of the bridge rail. Note, these post numbers do not correlate to the full-scale test installation as the model had a different system length than the test article. All node and post numbers discussed in this section refer only to the model.

The simulations were run with the vehicle impacting the bridge rail and traveling into the MGS. These impact points were chosen because the transition from the less rigid TL-2 bridge rail to the more rigid MGS is the most likely location for large pocketing angles to develop. The results of these simulations are summarized in Table 16.

The pocketing angles do increase from the 15 to 17 degree baseline values to a maximum of 23.5 degrees. As expected, the majority of the maximum pocketing angles occurred just upstream of post no. 25, which is the first W6x9 post adjacent to the bridge rail. None of the pocketing angles in the simulations approached the 30-degree limit where concerns for vehicle snag and instabilities exist. Maximum displacements show a gradual decrease as the impacts are moved closer to and into the MGS region of the model, so system deflections were also deemed acceptable. Finally, the maximum rail tension loads were also documented, but the forces saw only a minimal increase through the 25 simulations. The maximum force of 49.4 kips was only half of the 99-kip tensile yield capacity of 12-gauge W-beam.

As there were no concerns regarding the minor increases in pocketing angle and rail forces, the direct connection of the new TL-2 bridge rail to standard MGS was considered crashworthy. There is no need for a transition between the two systems, and a constant post spacing of 75 in. should be used throughout the installation.

Table 16. BARRIER VII Maximum Pocketing Angles, Displacements, and Forces

| Impact Node | Pocketing Angle | | Displacement | | Force | |
|------------------|-----------------|---------------------|---------------|-----------------|---------|-----------------|
| | Maximum (deg.) | Location (post no.) | Maximum (in.) | Location (node) | Maximum | Location (node) |
| TL-2 BR Baseline | 15.75 | 20 | 31.01 | 142 | 42.65 | 129 |
| 165 | 19.73 | 25 | 32.27 | 179 | 47.55 | 174 |
| 166 | 21.32 | 25 | 32.34 | 180 | 48.18 | 173 |
| 167 | 21.23 | 25 | 29.9 | 180 | 46.71 | 177 |
| 168 | 22.15 | 25 | 29.8 | 181 | 47.69 | 175 |
| 169 | 22.92 | 25 | 30.05 | 182 | 49.11 | 177 |
| 170 | 23.3 | 25 | 30.63 | 183 | 49.42 | 172 |
| 171 | 22.72 | 25 | 29.95 | 184 | 49.42 | 172 |
| 172 | 22.73 | 25 | 30.13 | 185 | 49.17 | 174 |
| 173 | 23.04 | 25 | 30.29 | 186 | 49.35 | 175 |
| 174 | 23.04 | 25 | 29.94 | 186 | 47.9 | 175 |
| 175 | 22.52 | 25 | 27.82 | 187 | 48.88 | 180 |
| 176 | 22.56 | 25 | 28.44 | 188 | 48.22 | 181 |
| 177 | 22.84 | 25 | 27.73 | 189 | 48.11 | 182 |
| 178 | 22.72 | 25 | 27.04 | 190 | 46.75 | 181 |
| 179 | 23.17 | 25 | 27.65 | 191 | 47.42 | 181 |
| 180 | 23.51 | 25 | 27.71 | 192 | 46.1 | 185 |
| 181 | 23.48 | 25 | 27.82 | 193 | 44.51 | 184 |
| 182 | 22.22 | 25 | 25.2 | 194 | 42.73 | 187 |
| 183 | 21.28 | 25 | 25.36 | 195 | 40.6 | 188 |
| 184 | 19.93 | 27 | 25.5 | 196 | 40.04 | 187 |
| 185 | 19.61 | 27 | 25.93 | 198 | 39.28 | 189 |
| 186 | 19.43 | 27 | 26.05 | 199 | 38.72 | 193 |
| 187 | 18.9 | 27 | 25.52 | 200 | 37.32 | 187 |
| 188 | 18.07 | 26 | 22.12 | 200 | 37.85 | 195 |
| 189 | 17.84 | 27 | 21.99 | 200 | 38.68 | 196 |
| MGS Baseline | 16.62 | 18 | 20.4 | 22.82 | 46.4 | 130 |





Figure 107. Model of Test No. N2BR-1 Post Nos. 1 through 13



143

Figure 108. Model of Test No. N2BR-1 Post Nos. 13 through 25




Figure 109. Model of Test No. N2BR-1 Post Nos. 25 through 37

10 MINIMUM GUARDRAIL LENGTH

10.1 Background and Scope

For the new TL-2 bridge rail to function properly, additional guardrail and guardrail anchorage is needed adjacent to the bridge rail on both the upstream and downstream ends, similar to the as-tested configuration. Factors that should be considered to determine the minimum length of guardrail include the guardrail length of need required to shield the hazard, terminal stroke length, guardrail anchorage requirements, and the minimum length needed to resist compression forces from crashworthy end terminals. When determining the minimum length of guardrail required adjacent to the bridge rail, all four of the factors should be considered. Depending on the site conditions, any one factor may control the installation length. These factors are discussed independently in the following sections.

10.2 Length of Need to Shield Roadside Hazards

Roadside hazards within the clear zone require a certain length of guardrail upstream from the hazard to properly shield them from errant motorists. The *AASHTO Roadside Design Guide* (RDG) provides equations for determining the length of guardrail necessary to shield hazards [24]. In addition to these equations, the RDG also provides guidance to determine the variables required to calculate the required length of need, such as runout length and the lateral extent of the area of concern. If the guardrail installation is not sufficient in length, the hazard is not truly shielded and still poses a risk to motorists.

10.3 Terminal Stroke Length

Terminal stroke length is defined as the maximum longitudinal vehicle stopping distance during head-on impacts on the end terminal. Sufficient stroke length is necessary to ensure proper end terminal energy dissipation and that the vehicle comes to a stop before reaching the bridge, where it could roll off the edge of the deck. Terminal stroke length varies for each end terminal system. Roadside engineers should refer to manufacturer specifications to determine the required stroke length for the end terminal desired for installation. It is recommended that the TL-2 stroke length for the end terminal be used when evaluating system lengths in order to be consistent with the test level of the bridge rail system.

Previously, 12.5 ft of standard guardrail has been recommended between a terminal and any MGS special applications, such as the new TL-2 bridge rail, to separate the different systems and ensure they do not negatively affect the performance of the other system. This 12.5 ft of separation guardrail has been recommended for both tangent and flared end terminals, as shown in Figure 110 [6]. However, the additional 12.5 ft of MGS is a conservative approach that may not be applicable in all cases. For example, the additional guardrail may not be cost effective for very low-volume roads where the risk of crashes is minimal and installation funds are limited.




Figure 110. Separation of Manufacturer Specified End Terminal Stroke Length and Bridge Rail

10.4 Anchorage Requirements

For the TL-2 bridge rail and the guardrail to function as intended, sufficient guardrail anchorage is required for the W-beam to develop the tensile forces required to redirect a vehicle. Typical guardrail installations are installed with terminals or trailing end anchorages, which typically consist of two anchorage posts that provide adequate tensile capacity for the rail. However, impacts too close to the guardrail ends will result in anchorage failure and, subsequently, the vehicle won't be contained and redirected. Thus, one needs to consider the beginning and end of the length of need for the anchorages to remain effective.

Under TL-3 conditions, the beginning of the length of need for end terminals is typically at the third post from the upstream end, and end of the length of need for a standard trailing end anchorage has been defined as the sixth post from the downstream end [9-10]. The beginning of length of need for TL-2 terminals is typically defined as the same point for a TL-3 installation, and the end of length of need for a TL-2 installation has not yet been evaluated. The length of need points are potentially closer to their respective ends for a TL-2 installation, but until further research is conducted, these points will remain unknown. As such, design should consider the third post from the end of an end terminal as the beginning of the redirective length of the system when designing the system length needed to shield the hazard unless the selected end terminal was crash tested with the beginning of length of need point upstream of the third post. On the downstream end of the bridge rail, it is recommended that a minimum of six posts, including the two anchorage posts, be used in order to develop adequate system anchorage and ensure that vehicle redirection is achieved throughout the entire length of the bridge rail.

10.5 Compression Terminal Force Resistance

Compression terminals require the guardrail to resist a certain amount of compressive forces as the vehicle is brought to a stop. After the guardrail anchorage is released at the beginning of an end-on impact, only the downstream support posts are left to provide resistance to the guardrail and prevent the entire installation (and vehicle) from translating downstream. Note, tension based end terminals would not require downstream posts to resist impact loads, so this concern only applies to compression terminals.

The resistance applied to the guardrail by a post can be defined as the minimum between the post's longitudinal (weak-axis) bending strength, the post's torsional strength, and the shear capacity of the guardrail attachment bolt. Weak-axis bending capacity was calculated based on a load application height, H , of 25 in. Post sockets and soil were assumed to act as a fixed end supports. The yield strength, F_y , of both posts was 50 ksi, and a strength reduction factor, ϕ , of 0.9 was applied to the yield strength. The capacity of the posts, P , was determined using the equation $P = \frac{\phi F_y Z_y}{H}$, where Z_y is the weak axis section modulus of the post.

S3x5.7 posts utilized $\frac{5}{16}$ -in. diameter A307 Gr. A bolts, while W6x8.5 posts utilized $\frac{3}{8}$ -in. diameter A307 Gr. A bolts. The factored yield strength, ϕF_{nv} , of the bolts obtained from the *AISC Steel Construction Manual* was 20.3 ksi [25]. The force required to achieve bolt shear capacity, P , was calculated using the equation $P = \phi F_{nv} A_b$, where A_b is the nominal cross sectional area of the bolt.

The torsional capacity of the posts was determined by assuming the post sockets and soil would leave the posts unrestrained from warping and the posts would only be loaded in pure torsion. Load applied via the W-beam rail would have an eccentricity, l , equal to the blockout depth plus half of the post depth. Yield stress, F_y , for both posts was 50 ksi, and a strength reduction factor, ϕ , of 0.9 was applied to the yield strength. The force acting at the face of a post required to cause torsional yielding, P , was calculated by determining the applied load acting at the face of the post using the equation $P = \frac{\phi F_y J}{t_f l \theta'}$, where θ' , which describes the rate of change of the angle of rotation about the longitudinal axis of the member, was obtained from *AISC Design Guide 9* [26]. The term t_f is defined as the flange thickness of the post, and J is defined as the polar moment of inertia of the post.

All three failure strengths were calculated for both the S3x5.7 bridge rail and a typical W6x8.5 MGS post and are shown in Table 17. The capacity of an S3x5.7 post was limited to 1.1 kips through the shear capacity of the $\frac{5}{16}$ -in. diameter A307 Gr. A bolt, while the strength of a W6x8.5 was found to be 2.4 kips through torsion failure with a 12-in. blockout. For shorter blockouts, the capacity of a W6x8.5 post would be limited by its weak-axis bending capacity of 2.8 kips. Posts used within the end terminals on the downstream side of an installation would also resist the compressive forces in the W-beam. However, many terminal posts are weakened or breakaway posts, so the capacity of these posts would require further analysis to determine their capacities.

Table 17. TL-2 Bridge Rail and MGS Post Compressive Capacity Loads

| Post | Weak Axis Bending Load kips | Bolt Shear Load kips | Post Torsion Load kips |
|------------------------------------|--------------------------------|-------------------------|---------------------------------------|
| TL-2 Bridge Rail Posts (S3x5.7) | 1.2 | 1.5 | 6.75 |
| MGS Posts (W6x8.5) | 2.8 | 6.2 | 2.4 (12-in. block) 11.9 (no block) |

The magnitude of the compressive forces applied to the guardrail varies by compression terminal due to the differences in energy absorbing mechanisms. Average compressive forces were previously determined through an analysis of full-scale crash testing, and are shown in Table 18 [27]. Peak end terminal compressive forces have the potential to be greater than the average end terminal forces. Should the designer wish to design for the case of peak end terminal forces, a factor of safety may be utilized.

Table 18. End Terminal Average Compressive Forces [27]

| End Terminal System | Average Compressive Force kips |
|---------------------|-----------------------------------|
| BEST-350 | 18.-22.5 |
| ET-2000 | 12-21.3 |
| ET-2000 Plus | 12-21.3 |
| FLEAT-350 | 13.5-16.7 |
| SKT-350 | 10.5-15.2 |
| SKT-MGS | 10.5 |
| ET-Plus (27¾ in.) | 15 |
| ET-Plus (31 in.) | 12.7 |
| SGET | 15.2 |
| MSKT | 12.6 |

The length of MGS adjacent to the bridge required to resist the terminal compression force depends on multiple site-specific factors, such as the type of terminal and the length and number of posts in the bridge rail. However, for the guardrail installation to resist the compression loads of the terminal, the following equation must be satisfied;

$$N_s P_s + N_w P_w > C$$

where N_s is the number of S3x5.7 bridge rail posts, P_s is the strength of an S3x5.7 post, N_w is the number of W6x8.5 MGS posts, P_w is the strength of a W6x8.5 post, and C is the compressive load for a given terminal. Values for the post strengths and terminal compression forces can be found in Tables 17 and 18, while the number of bridge rail posts will be site specific. The only remaining variable is the number of MGS posts, which can be solved for and translated into a required length of MGS by multiplying by a 75-in. spacing per post. Note, the posts within the upstream terminal's stroke length should not be counted as part of N_w or the guardrail resistance, as these posts would be overrun by the impacting vehicle and disengage from the rail. Example calculations are shown in Appendix H.

11 SUMMARY, CONCLUSIONS, AND RECOMMENDATIONS

The objective of this project was to develop a new side-mounted, TL-2 bridge rail for low-volume roads. The bridge railing was to utilize 31-in. W-beam guardrail and S3x5.7 posts, similar to previously developed bridge rails and guardrail systems attached to concrete culverts [3-7]. The bridge railing was to be completely side-mounted (i.e., no hardware on the deck surface) and incorporate a socketed post attachment for ease of installation and repair. Finally, the bridge railing was to be compatible with both 7-in. thick CIP decks and 12-in. thick precast beam-slab decks. Both deck types utilize steel channels along the deck edge that could be used as part of the post-to-deck attachment.

Two different types of socket-to-deck attachments were explored. Welded attachments involved the HSS4x4x $\frac{3}{8}$ steel tube sockets being welded directly to the steel channels along the edge of the deck. Welded attachments required the channels to be strongly anchored to the deck or the channels would be pried off during impact events. Thus, multiple channel anchorage designs were explored, including straight bars butt-welded to the inside surface of the channel, U-bars flare-bevel welded to the upper corner of the channel, and hooked rebar flare-bevel welded to gussets located in the upper corner of the channel. A bolted attachment involved a prefabricated socket assembly being bolted to the side the deck. The bolts were inserted through the steel channels and threaded into coupling nuts embedded into the deck. Threaded rods were threaded into the other end of the coupling nuts and extended into the interior of the deck. When loaded, the tensile loads in the bolts would be directly transferred through the coupling nuts to the threaded anchors. Thus, the channel was not directly loaded and the chance of damage to the edge of the deck was minimal.

Six dynamic component tests were conducted on both welded and bolted attachment designs and on both CIP and precast beam-slab decks. Testing was also conducted in both the lateral and longitudinal directions to evaluate both loading conditions. During the tests, the novel bolt, coupling nut, and threaded rod anchorage design performed as intended. The posts were bent over while the socket assemblies, attachment hardware, and decks remained undamaged. Lateral testing of a welded attachment with the channel anchored by straight bars welded to the channel's web resulted in the channel being pulled slightly off the deck edge. A $\frac{1}{8}$ -in. crack opened between the top of the channel and the concrete deck, and minor concrete spalling was observed adjacent to the channel. Testing of the U-bar channel anchorage proved strong enough to prevent the channel from prying away from the deck and prevented any damage to the socket and deck. Both the welded and bolted designs performed satisfactorily in longitudinal tests as the posts bent over and no damage was found to the deck or attachment hardware.

Following a review of the component testing results, the bolted attachment with coupling nut and threaded rod anchors was selected for further evaluation through full-scale crash testing. Although MASH 2016 specifies two full-scale crash tests to satisfy TL-2 safety criteria, the greater mass of the 2270P pickup truck was expected to produce higher system deflections and anchorage loads than the 1100C small car. Additionally, two similar systems had previously been successfully crash tested with the 1100C vehicle [3-5]. Therefore, test designation no. 2-10 with the small car was not considered critical, and only test designation no. 2-11 was conducted to evaluate the MASH TL-2 bridge rail.

The test article for the full-scale crash test was built on a simulated 7-in. thick CIP, as this represented the weaker of the two deck options and was more susceptible to damage. A 75-ft long bridge rail installation was constructed in the middle of a 182-ft long MGS guardrail installation equipped with guardrail anchors on each end. During test no. N2BR-1 the 4,999-lb pickup truck impacted the TL-2 bridge rail at a speed of 44.2 mph and an angle of 25.5 degrees. The vehicle was successfully contained and smoothly redirected with moderate damage to vehicle. All vehicle decelerations, ORAs, and OIVs fell within the recommended safety limits established in MASH 2016. Therefore, test no. N2BR-1 was successful according to the safety criteria of MASH 2016 test designation no. 2-11. A summary of the test evaluation is shown in Table 19.

Although MASH requires two full-scale crash tests, testing with the 1100C test vehicle was not deemed critical for the evaluation of the new bridge rail. Previous MASH crash testing has been conducted with both the 2270P and the 1100C vehicles on the MGS Bridge Rail and the TxDOT T631 bridge rail [3-5]. Similar to the NDOT TL-2 Bridge Rail developed herein, both of these previous bridge rails consist of 31-in. tall, 12-gauge, W-beam guardrail supported by S3x5.7 posts. Further, all three bridge rails were designed to absorb impact energy through bending of the weak S3x5.7 posts while the attachment of the post to the deck remains rigid and intact. The TxDOT T631 bridge rail was successfully tested to MASH test designation nos. 2-10 and 2-11 with a 75-in. post spacing, which is the same as the new NDOT TL-2 bridge rail. Additionally, the MGS Bridge Rail was successfully tested to MASH test designation nos. 3-10 and 3-11 with a 37.5-in. post spacing utilizing the same post assembly and HSS4x4x $\frac{3}{8}$ steel sockets incorporated into the new NDOT TL-2 bridge rail. Since the socket assembly remained undamaged and intact throughout an impact event, the new TL-2 bridge rail would be expected to perform very similarly to the TL-2 version of the TxDOT T631 during a MASH 2-10 test. Therefore, MASH test designation no. 2-10 was determined to be non-critical, and the new, NDOT side-mounted bridge rail was considered crashworthy to MASH TL-2 criteria.

The simulated bridge deck and all of the socket assemblies remained undamaged during test no. N2BR-1. A few of the socket assemblies rotated downstream during the test, but this was only due to the vertical slots in the mounting plate that were included to allow height adjustments during installation, and they could easily be straightened. None of the attachment bolts or coupling nuts were damaged. As such, repairs to the system would only include the removal and replacement of damaged W-beam and posts.

The TL-2 bridge rail design included 12-in. backup plates to be installed behind the W-beam at every bridge post location, as shown previously on Figures 55 and 75. Due to an oversight, these backup plates were not installed within the full-scale test installation. Although the test was conducted successfully without them, it is still recommended to utilize backup plates in non-blocked, weak-post guardrail systems to prevent the rail tearing as observed in other full-scale crash tests on similar systems [4-5, 13].

Following the full-scale crash test, crash simulations were conducted to evaluate the connection between the TL-2 bridge rail and the standard MGS. BARRIER VII models were constructed and validated against the TL-2 full-scale crash test documented herein as well as TL-3 impacts into the MGS and the MGS with an omitted post. The validated model was then subjected to 25 different crash tests with the vehicle impacting the TL-3 bridge rail and approaching the adjacent MGS. A 75-in. spacing was used between the outermost bridge rail post and the adjacent MGS post. All simulations were conducted with impact conditions in accordance

with MASH test designation no. 2-11. The BARRIER VII analysis showed only minor increases in the guardrail pocketing angles and tensile rail forces due to the transition from TL-2 bridge rail to MGS. Thus, the direct connection of the new TL-2 bridge rail to adjacent MGS while maintaining a consistent 75-in. post spacing was determined to be crashworthy under MASH TL-2 conditions.

The minimum length of MGS installed adjacent to the guardrail was also investigated. Factors to be considered when defining the minimum system length include guardrail length of need to shield the hazard, terminal stroke length, guardrail anchorage requirements, and the installation length necessary to resist the terminal compression forces. Guidance pertaining to these factors was provided in Chapter 10 and example calculations are provided in Appendix H.

The new TL-2 bridge rail was designed to be compatible with both 7-in. thick CIP decks and 12-in. thick precast beam-slabs. The 7-in. CIP deck was selected as the critical deck for full-scale crash testing due to its thinner and weaker structure. As such, details for attaching the bridge rail to a 7-in. CIP deck are shown in Chapter 5.

Three different options were developed for attaching the bridge rail to 12-in. precast beam-slabs. Option 1 includes keeping as many components as possible identical to the as-tested configuration with a 7-in. CIP deck. The socket assemblies, bolts, coupling nuts, threaded rods, and embedded plates would all remain the same. Holes in the C12x20.7 side channel would be centered 3.5 in. from the top to accommodate the unmodified socket assembly. The only different component would be the steel channel assembly, which would increase in size to match the deck thickness. Details for the Option 1 attachment of the bridge rail to a 12-in. precast beam-slab deck are shown in Figures 111 through 115.

Option 2 was modeled after the configuration subjected to dynamic component testing as part of the early attachment development efforts (see attachment location G and channel assembly F). This configuration optimizes the attachment hardware by incorporating slightly smaller $\frac{3}{4}$ -in. diameter bolts, coupling nuts, and threaded rods as compared to the $\frac{7}{8}$ -in. diameter hardware in the as-tested configuration. However, it also requires a longer socket assembly and longer posts. Details for the Option 2 attachment of the bridge rail to a 12-in. precast beam-slab deck are shown in Figures 116 through 120.

Option 3 incorporates the same attachment hardware as the as-tested configuration and keeps the location of the hardware in the middle of the deck thickness. Like Option 2, this configuration requires an elongated socket assembly and post compared to the as-tested system. Details for the Option 3 attachment of the bridge rail to a 12-in precast beam-slab deck are shown in Figures 121 through 125.

Although a continuous steel channels was used along the side of the simulated bridge deck in the full-scale crash test, some bridges are constructed with channels located only at post locations. Since the attachment bolts are directly linked to threaded anchors embedded in the deck, loading to the side-channels is minimal. Thus, implementing the new TL-2 bridge rail system on a deck with short segments of steel channels is not expected to affect the performance of the system. The short channel segments should be at least 20 in. long to match the channel lengths tested during the component testing phase of this project. Details for short channel segments for both 7-in. CIP decks and 12-in. precast beam-slab decks are shown in Figures 126 and 127.

Bridge posts should not be placed too close to the upstream or downstream ends of a bridge deck as the attachment anchors may not be able to develop the required shear and/or tension loads. Thus, a post should be no closer than 10 in. from the ends of a deck, as measured to the center of the post. Note, this corresponds to half of the short channel segment length, so the short segments can be placed at the ends of the deck and the corresponding post would be 10 in. away.

Finally, the bridge railing system developed herein utilizes the same 31-in. tall W-beam and S3x5.7 weak posts as two other MASH crash tested TL-3 bridge railings. Additionally, all three bridge rails perform the same way with post bending absorbing the impact energy while the deck and post-to-deck-attachment remain undamaged. The only difference between NDOT's new TL-2 bridge rail and these other two MASH TL-3 railings is the post spacing for the TL-3 railings was reduced to 37.5 in. on-center. Therefore, if the post spacing of the new bridge railing developed herein were reduced to 37.5 in. on-center, the system would be expected to perform similarly to the other systems and be crashworthy to MASH TL-3 evaluation criteria.

Table 19. Summary of Safety Performance Evaluation

| Evaluation Factors | Evaluation Criteria | Test No. N2BR-1 |
|---------------------------------|---|--------------------|
| Structural Adequacy | A. Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underide, or override the installation although controlled lateral deflection of the test article is acceptable. | S |
| Occupant Risk | D. 1. Detached elements, fragments or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone. 2. Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH 2016. | S |
| | F. The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees. | S |
| | H. Occupant Impact Velocity (OIV) (see Appendix A, Section A5.2.2 of MASH 2016 for calculation procedure) should satisfy the following limits: | S |
| | Occupant Impact Velocity Limits | S |
| | Component Preferred Maximum | |
| | Longitudinal and Lateral 30 ft/s 40 ft/s | |
| | I. The Occupant Ridedown Acceleration (ORA) (see Appendix A, Section A5.2.2 of MASH 2016 for calculation procedure) should satisfy the following limits: | S |
| | Occupant Ridedown Acceleration Limits | S |
| | Component Preferred Maximum | |
| | Longitudinal and Lateral 15.0 g's 20.49 g's | |
| MASH 2016 Test Designation No. | | 2-11 |
| Final Evaluation (Pass or Fail) | | Pass |

S – Satisfactory U – Unsatisfactory NA - Not Applicable




Figure 111. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 1, Cross Section




Figure 112. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 1, Channel Assembly




Figure 113. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 1, Embedded Anchorage




Figure 114. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 1, Post Assembly




Figure 115. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 1, Socket Assembly




Figure 116. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 2, Cross Section




Figure 117. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 2, Channel Assembly




Figure 118. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 2, Embedded Anchorage




Figure 119. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 2, Post Assembly




Figure 120. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 2, Socket Assembly




Figure 121. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 3, Cross Section




Figure 122. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 3, Channel Assembly




Figure 123. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 3, Embedded Anchorage




Figure 124. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 3, Post Assembly




Figure 125. System Details, TL-2 Bridge Rail Attachment to 12-in. Deck, Option 3, Socket Assembly




Figure 126. Details for 20-in. Long C7x9.8 Channel Assembly for Use on 7-in. CIP decks




Figure 127. Details for 20-in. Long C12x20.7 Channel Assembly for Use on 12-in. CIP decks

12 REFERENCES

1. *Manual for Assessing Safety Hardware (MASH), Second Edition*, American Association of State Highway and Transportation Officials (AASHTO), Washington, D.C., 2016.
2. Ray, M.H., and Carrigan, C.E., *Recommended Guidelines for the Selection of Test Levels 2 through 5 Bridge Railings*, National Cooperative Highway Research Program (NCHRP) Report 22-12(03), American Association of State Highway and Transportation Officials (AASHTO), Washington, D.C., February 10, 2014.
3. Thiele, J.C., Sicking, D.L., Faller, R.K., Bielenberg, R.W., Lechtenberg, K.A., Reid, J.D., and Rosenbaugh, S.K., *Development of a Low-Cost, Energy-Absorbing Bridge Rail*, Report No. TRP-03-226-10, Midwest Roadside Safety Facility, University of Nebraska-Lincoln, Lincoln, Nebraska, August 11, 2012.
4. Williams, W. F., Bligh, R.P., Menges, W.L., and Kuhn, D.L., *MASH TL-3 Crash Test and Evaluation of the TxDOT T631 Bridge Rail*, Report No. 9-1002-12-10, Texas A&M Transportation Institute, Texas A&M University, College Station, Texas, January 2014.
5. Williams, W.F., Bligh, R.P., Menges, W.L., and Kuhn, D.L., *Crash Test and Evaluation of the TxDOT T631 Bridge Rail*, Report No. 9-1002-12-12, Texas A&M Transportation Institute, Texas A&M University, College Station, Texas, July 2016.
6. Schneider, A.J., Rosenbaugh, S.K., Faller, R.K., Sicking, D.L., Lechtenberg, K.A., and Reid, J.D., *Safety Performance Evaluation of Weak-Post, W-Beam Guardrail Attached to Culvert*, Report No. TRP-03-277-14, Midwest Roadside Safety Facility, University of Nebraska-Lincoln, Lincoln, Nebraska, February 12, 2014.
7. Rosenbaugh, S.K., Asadollahi Pajouh, M., and Faller, R.K., *Top-Mounted Sockets for Weak-Post MGS on Culverts*, Report No. TRP-03-368-19, Midwest Roadside Safety Facility, University of Nebraska-Lincoln, Lincoln, Nebraska, October 2019.
8. Society of Automotive Engineers (SAE), *Instrumentation for Impact Test – Part 1 – Electronic Instrumentation*, SAE J211/1 MAR95, New York City, NY, July 2007.
9. Mongiardini, M., Faller, R.K., Reid, J.D., Sicking, D.L., Stolle, C.S., and Lechtenberg, K.A., *Downstream Anchoring Requirements for the Midwest Guardrail System*, Report No. TRP-03-279-13, Midwest Roadside Safety Facility, University of Nebraska-Lincoln, Lincoln, Nebraska, October 28, 2013.
10. Mongiardini, M., Faller, R.K., Reid, J.D., and Sicking, D.L., *Dynamic Evaluation and Implementation Guidelines for a Non-Proprietary W-Beam Guardrail Trailing-End Terminal*, Paper No. 13-5277, Transportation Research Record No. 2377, Journal of the Transportation Research Board, TRB AFB20 Committee on Roadside Safety Design, Transportation Research Board, Washington D.C., January 2013, pages 61-73.

11. *Clarifications on Implementing the AASHTO Manual for Assessing Safety Hardware*, 2016, FHWA and AASHTO, <https://design.transportation.org/wp-content/uploads/sites/21/2019/11/Clarifications-on-Implementing-MASH-2016-aka-MASH-QA-Updated-Nov-19-2019.pdf>, November 2019.
12. Stolle, C.S., Reid, J.D., Faller, R.K., and Mongiardini, M., *Dynamic Strength of a Modified W-Beam BCT Trailing-End Termination*, Paper No. IJCR 886R1, Manuscript ID 1009308, International Journal of Crashworthiness, Taylor & Francis, Vol. 20, Issue 3, Published online February 23, 2015, pages 301-315.
13. Rosenbaugh, S.K., Faller, R.K., Lechtenberg, K.A., and Holloway, J.C., *Development and Evaluation of Weak-Post W-beam Guardrail in Mow-Strips*, Report No. TRP-03-322-15, Midwest Roadside Safety Facility, University of Nebraska-Lincoln, Lincoln, Nebraska, October 2015.
14. Hinch, J., Yang, T.L., and Owings, R., *Guidance Systems for Vehicle Testing*, ENSCO, Inc., Springfield, Virginia, 1986.
15. *Center of Gravity Test Code - SAE J874 March 1981*, SAE Handbook Vol. 4, Society of Automotive Engineers, Inc., Warrendale, Pennsylvania, 1986.
16. *Vehicle Damage Scale for Traffic Investigators*, Second Edition, Technical Bulletin No. 1, Traffic Accident Data (TAD) Project, National Safety Council, Chicago, Illinois, 1971.
17. *Collision Deformation Classification – Recommended Practice J224 March 1980*, Handbook Volume 4, Society of Automotive Engineers (SAE), Warrendale, Pennsylvania, 1985.
18. Powell, G.H., *Computer Evaluation of Automobile Barrier Systems*, Report No. FHWA -RD-73-73, Department of Civil Engineering, University of California, Berkley, California, August 1970.
19. Powell, G.H., *Barrier VII: A computer Program for Evaluation of Automobile Barrier Systems*, Report No. FHWA -RD-73-51, Department of Civil Engineering, University of California, Berkley, California, April 1973.
20. Herr, J.E., Rohde, J.R., Sicking, D.L., Reid, J.D., Faller, R.K., Holloway, J.C., Coon, B.A., and Polivka, K.A., *Development of Standards for Placement of Steel Guardrail Posts in Rock*, Final Report to the Midwest States' Regional Pooled Fund Program, Report No. TRP-03-119-03, Project No. SPR-3(017)-Year 9, Midwest Roadside Safety Facility, University of Nebraska-Lincoln, May 30, 2003.
21. Kuipers, B.D., Faller, R.K. and Reid, J.D., *Critical Flare Rates for W-beam Guardrail – Determining Maximum Capacity using Computer Simulation*, Final Report to the National Academy of Sciences, Report No. TRP-03-157-04, NCHRP 17-20(3), Midwest Roadside Safety Facility, University of Nebraska-Lincoln, January 24, 2005.

22. Asadollahi Pajouh, M., Bielenberg, R.W., Schmidt, J.D., Lingenfelter, J., Faller, R.K., and Reid, J.D. *Placement of Breakaway Poles Located Directly Behind Midwest Guardrail System (MGS)*, Report No. TRP-03-361-17, Midwest Roadside Safety Facility, University of Nebraska-Lincoln, Lincoln, Nebraska, June 29, 2017.
23. Lingenfelter, J.L., Rosenbaugh, S.K., Bielenberg, R.W., Lechtenberg, K.A., Faller, R.K. and Reid, J.D., *Midwest Guardrail System (MGS) with an Omitted Post*, Report No. TRP-03-326-16, Midwest Roadside Safety Facility, University of Nebraska-Lincoln, Lincoln, Nebraska, February 22, 2016.
24. *Roadside Design Guide (RDG)*, Fourth Edition, American Association of State Highway and Transportation Officials (AASHTO), Washington, D.C., 2011.
25. *American Institute of Steel Construction Steel Construction Manual*, American Institute of Steel Construction, 2017.
26. *American Institute of Steel Construction Design Guide 9: Torsion*, American Institute of Steel Construction, 2003.
27. Schmidt, J.D., Bielenberg, R.W., Schroder, B.D., Faller, R.K., and Lechtenberg, K.A., *Safety Investigation and Design Guidance for Curbs Near Energy Absorbing End Terminals*, Report No. TRP-03-358-17, Midwest Roadside Safety Facility, University of Nebraska-Lincoln, Lincoln, Nebraska, July 10, 2017.

13 APPENDICES

Appendix A. Bogie Test Material Specifications

Table A-1. Bill of Materials, Test Nos. N2B-1 through N2B-6

| Item No. | Part Description | Material Specification | Reference No. |
|----------|--|--|----------------------------------|
| a1 | Concrete | Min. f'c = 6,000 psi NE Mix 47BD | R#2147369871 |
| b1 | C7x9.8, 36" Long C-Channel | ASTM A36 | H#1047907 |
| b2 | C7x9.8, 36" Long C-Channel | ASTM A36 | H#1047907 |
| b3 | C7x12.25, 36" Long C-Channel | ASTM A36 | H#63142712 |
| b4 | C12x20.7, 20" Long C-Channel | ASTM A36 | H#55049945 |
| b5 | C12x20.7, 20" Long C-Channel | ASTM A36 | H#55049945 |
| b6 | 10"x2 3/4"x1/4" Plate Washer | ASTM A36 | H#B707407 |
| b7 | 2x2x1/4" Gusset | ASTM A36 | H#B707407 |
| c1 | HSS4x4x3/8", 6 5/8" Long Square Tube | ASTM A500 Gr. B | H#W45369 |
| c2 | HSS4x4x3/8", 11 5/8" Long Square Tube | ASTM A500 Gr. B | H#W45369 |
| c3 | 10"x7"x1/2" Steel Plate | ASTM A572 Gr. 50 | H#A7D898 |
| c4 | 12"x10"x1/2" Steel Plate | ASTM A572 Gr. 50 | H#A7D898 |
| c5 | 12"x10"x1/2" Steel Plate | ASTM A572 Gr. 50 | H#A7D898 |
| e1 | S3x5.7, 39" Long Steel Post | ASTM A992 | H#59070748 |
| e2 | S3x5.7, 44" Long Steel Post | ASTM A992 | H#59070748 |
| e3 | 2 3/4"x1"x1/4" Post Standoff | ASTM A36 | H#64055041 |
| f1 | 5/8" Dia. UNC, 5" Long Heavy Hex Head Bolt and Nut | Bolt - ASTM F3125 Gr. A325 Type 1 Nut - ASTM A563DH | BOLT: H#C20373 NUT: H#C114376 |
| f2 | 3/4" Dia. UNC, 1 3/4" Long Heavy Hex Head Bolt | ASTM A449 | H#NF14204233 |
| f3 | 3/4" Dia. Heavy Hex Coupling Nut | ASTM A563DH or A194 Gr. 2H | H#NF16203911 |
| f4 | 3/4" Dia., 30" Long Threaded Rod | ASTM A449 | H#DL1610487601 |

Table A-2. Bill of Materials, Test Nos. N2B-1 through N2B-6, Cont.

| Item No. | Part Description | Material Specification | Reference No. |
|----------|--|----------------------------|----------------|
| f5 | 7/8" Dia. UNC, 2" Long Heavy Hex Head Bolt | ASTM A325 HVY HEX | H#331704677 |
| f6 | 7/8" Dia. Hex Coupling Nut | ASTM A563DH or A194 Gr. 2H | H#NF14103504 |
| f7 | 7/8" Dia., 30" Long Threaded Rod | ASTM A449 | H#DL1610686802 |
| f8 | 1" Dia. UNC, 2" Long Heavy Hex Head Bolt | ASTM A449 | H#NF16103170 |
| f9 | 1" Dia. Heavy Hex Coupling Nut | ASTM A563DH or A194 Gr. 2H | H#NF14103504 |
| f10 | 1" Dia. Heavy Hex Nut | ASTM A563DH or A194 Gr. 2H | H#DL15105591 |
| f11 | 1" Dia., 24" Long Threaded Rod | ASTM A449 | H#A164782 |
| f12 | 1" Dia. Hardened Flat Washer | ASTM F436 | H#276190 |
| f13 | 7/8" Dia. Hardened Flat Washer | ASTM F436 | H#274703 |
| f14 | 3/4" Dia. Hardened Flat Washer | ASTM F436 | H#273699 |
| g1 | #4 Bar, 287 1/2" Long | ASTM A615 Gr. 60 | H#58028860 |
| g2 | #4 Bar, 251 1/2" Long | ASTM A615 Gr. 60 | H#58028860 |
| g3 | #4 Bar, 200 1/2" Long | ASTM A615 Gr. 60 | H#58028860 |
| g4 | #4 Bar, 63" Long | ASTM A615 Gr. 60 | H#58028860 |
| g5 | #4 Bar, 48" Long | ASTM A615 Gr. 60 | H#58028860 |
| g6 | #4 Bar, 32" Long | ASTM A615 Gr. 60 | H#58028860 |
| g7 | #4 Bar, 20" Long | ASTM A615 Gr. 60 | H#58028860 |
| g8 | #3 Bar, 86 7/8" Long Unbent | ASTM A615 Gr. 60 | H#587796 |
| g9 | #4 Bar, 90 3/8" Long | ASTM A615 Gr. 60 | H#58028860 |
| g10 | #8 Bar, 90 3/8" Long | ASTM A615 Gr. 60 | H#KN14104453 |
| g11 | #4 Bar, 18" Long | ASTM A706 Gr. 60 | H#53145629 |
| g12 | #4 Bar, 23 11/16" Long Unbent | ASTM A706 Gr. 60 | H#53145629 |
| g13 | #4 Bar, 40" Long Unbent | ASTM A706 Gr. 60 | H#53145629 |
| g14 | #5 Bar, 52 3/16" Long Unbent | ASTM A706 Gr. 60 | H#53145629 |
| g15 | #4 Bar, 18" Long | ASTM A615 Gr. 60 | H#58028860 |



LINCOLN OFFICE
825 "M" Street Suite 100
Lincoln, NE 68508
Phone: (402) 479-2200
Fax: (402) 479-2276

COMPRESSION TEST OF CYLINDRICAL CONCRETE SPECIMENS - 6x12

ASTM Designation: C 39

Client Name: Midwest Roadside Safety Facility
Project Name: Miscellaneous Concrete Testing
Placement Location: TL-2

Date: 30-Nov-17

Mix Designation:

Required Strength:

Laboratory Test Data

| Laboratory Identification | Field Identification | Date Cast | Date Received | Date Tested | Days Cured in Field | Days Cured in Laboratory | Age of Test, Days | Length of Specimen, in. | Diameter of Specimen, in. | Cross-Sectional Area, sq.in. | Maximum Load, lbf | Compressive Strength, psi. | Required Strength, psi. | Type of Fracture | ASTM Practice for Capping Specimen |
|---------------------------|----------------------|------------|---------------|-------------|---------------------|--------------------------|-------------------|-------------------------|---------------------------|------------------------------|-------------------|----------------------------|-------------------------|------------------|------------------------------------|
| URR- 46 | D | 10/20/2017 | 11/30/2017 | 11/30/2017 | 41 | 0 | 41 | 12 | 5.99 | 28.20 | 155,217 | 5,500 | | 5 | C 1231 |
| URR- 47 | E | 10/20/2017 | 11/30/2017 | 11/30/2017 | 41 | 0 | 41 | 12 | 6.01 | 28.35 | 163,635 | 5,770 | | 5 | C 1231 |
| URR- 48 | F | 10/20/2017 | 11/30/2017 | 11/30/2017 | 41 | 0 | 41 | 12 | 6.00 | 28.24 | 161,598 | 5,720 | | 5 | C 1231 |

1 cc: Ms. Karla Lechtenberg
Midwest Roadside Safety Facility

Remarks:

All concrete test data in this report was produced by Benesch personnel using ASTM Standard Methods and Practices unless otherwise noted.


Test results presented relate only to the concrete sampled by Benesch personnel as referenced above.

This report shall not be reproduced except in full, without the written approval of Alfred Benesch & Company.

Report Number 2147369871

Page 1

Sketches of Types of Fractures



Type 1

Reasonably well-formed cones on both ends, less than 1 in. (25 mm) of cracking through caps



Type 2

Well-formed cone on one end, vertical cracks running through caps, no well-defined cone on other end



Type 3

Columnar vertical cracking through both ends, no well-formed cones



Type 4

Diagonal fracture with no cracking through ends; top with hammer to distinguish from Type 1



Type 5

Side fractures at top or bottom (occur commonly with unbonded caps)



Type 6

Similar to Type 5 but end of cylinder is pointed

ALFRED BENESCH & COMPANY
CONSTRUCTION MATERIALS LABORATORY



By Brant Wells, Field/Lab Operations Manager

Figure A-1. Concrete, Test Nos. N2B-1 through N2B-6



CMC STEEL ALABAMA
101 S 50TH STREET
BIRMINGHAM AL 35212-3525

CERTIFIED MILL TEST REPORT
For additional copies call
800-637-3227

We hereby certify that the test results presented here
are accurate and conform to the reported grade specification

Marcus W. McCluney
Marcus W. McCluney - CMC Steel AL

Quality Assurance Manager

1SERIES-BPS®

| | | | |
|--|--|--|--|
| HEAT NO.: 1047907 SECTION: CHANNEL 7"x9.8# 40'0" A36/572T1 GRADE: ASTM A36-14/A572-15 Gr 50 Tp1 ROLL DATE: 06/09/2017 MELT DATE: 06/06/2017 Cert. No.: 82115015 / 047907B840 | S Steel & Pipe Supply Co Inc O L 555 Poyntz Ave D Manhattan KS US 66502-6085 T 7855875182 O 7855872282 | S Steel & Pipe Supply Co H I 401 New Century Pkwy P New Century KS US 66031-0000 T 9137684333 O 7855875381 | Delivery#: 82115015 BOL#: 72094677 CUST PO#: 4500287306 CUST P/N: 25798040 DLVRY LBS / HEAT: 10976.000 LB DLVRY PCS / HEAT: 28 EA |
|--|--|--|--|

| Characteristic | Value | Characteristic | Value | Characteristic | Value |
|-------------------------|---------|------------------------------|---------|----------------|-------|
| C | 0.13% | Elongation Gage Lgth test 1 | 8IN | | |
| Mn | 0.73% | Yield to tensile ratio test1 | 0.76 | | |
| P | 0.015% | Yield Strength test 2 | 58.7ksi | | |
| S | 0.032% | Tensile Strength test 2 | 76.8ksi | | |
| Si | 0.20% | Elongation test 2 | 25% | | |
| Cu | 0.26% | Elongation Gage Lgth test 2 | 8IN | | |
| Cr | 0.20% | Yield to tensile ratio test2 | 0.76 | | |
| Ni | 0.12% | | | | |
| Mo | 0.063% | | | | |
| V | 0.005% | | | | |
| Cb | 0.010% | | | | |
| Sn | 0.009% | | | | |
| B | 0.0000% | | | | |
| Ti | 0.002% | | | | |
| N | 0.0095% | | | | |
| Carbon Eq A6 | 0.33% | | | | |
| Yield Strength test 1 | 57.6ksi | | | | |
| Tensile Strength test 1 | 75.6ksi | | | | |
| Elongation test 1 | 23% | | | | |

The Following is true of the material represented by this MTR:

- *Material is fully killed
- *100% melted and rolled in the USA
- *EN10204:2004 3.1 compliant
- *Contains no weld repair
- *Contains no Mercury contamination
- *Manufactured in accordance with the latest version of the plant quality manual
- *Meets the "Buy America" requirements of 23 CFR635.410

REMARKS :

ALSO MEETS A709 GR. 36, ASME SA36-08 ADDEND A, M270 GR. 36, A709 GR. 50 TYP 1, A529-50, A992, CAN 44W, CAN 50W

06/22/2017 14:48:49
Page 1 OF 1

Figure A-2. C7x9.8, 36-in. Long C-Channel, Test Nos. N2B-1 through N2B-6



GERDAU

US-ML-CALVERT CITY
1035 SHAR-CAL ROAD
CALVERT CITY, KY 42029
USA

CERTIFIED MATERIAL TEST REPORT

Page 1/1

| | | | | | | |
|--|--|---|--|--------------------|--------------------------------------|-----------------------------|
| CUSTOMER SHIP TO STEEL & PIPE SUPPLY CO INC 401 NEW CENTURY PKWY NEW CENTURY, KS 66031-1127 USA | | CUSTOMER BILL TO STEEL & PIPE SUPPLY CO INC MANHATTAN, KS 66505-1688 USA | | GRADE GGMULTI | SHAPE / SIZE Channel / 7 X 12.25# | DOCUMENT ID: 0000010926 |
| SALES ORDER 3842668/000010 | | CUSTOMER MATERIAL N° 00000000257122540 | | LENGTH 40'00" | WEIGHT 17,640 LB | HEAT / BATCH 63142712/02 |
| SPECIFICATION / DATE or REVISION ASTM A529-14, A572-15 ASTM A6-14, A36-14, ASME SA-36 ASTM A709-15, AASHTO M270-12 CSA G40.20-13/G40.21-13 | | | | | | |
| CUSTOMER PURCHASE ORDER NUMBER 4500268004 | | BILL OF LADING 1322-0000021503 | | DATE 08/10/2016 | | |

| CHEMICAL COMPOSITION | C | Mn | P | S | Si | Cu | Ni | Cr | Mo | V | Nb | Al | N |
|----------------------|------|------|-------|-------|------|------|------|------|-------|-------|-------|-------|--------|
| % | % | % | % | % | % | % | % | % | % | % | % | % | % |
| | 0.11 | 0.74 | 0.012 | 0.033 | 0.23 | 0.24 | 0.08 | 0.11 | 0.028 | 0.018 | 0.001 | 0.001 | 0.0127 |

| CHEMICAL COMPOSITION | Sn |
|----------------------|-------|
| % | % |
| | 0.011 |

| MECHANICAL PROPERTIES | Elong. | G/L | UTS | UTS | YS | YS |
|-----------------------|--------|-------|-------|-----|-------|-----|
| | % | Inch | PSI | MPa | PSI | MPa |
| | 24.00 | 8.000 | 72300 | 499 | 55400 | 382 |
| | 24.00 | 8.000 | 72550 | 500 | 55340 | 382 |

| GEOMETRIC CHARACTERISTICS | CSA |
|---------------------------|-------|
| | Sqin |
| | 0.468 |
| | 0.466 |

COMMENTS / NOTES

This grade meets the requirements for the following grades:
ASTM Grades: A36; A529-50; A572-50; A709-36; A709-50
CSA Grades: 44W; 50W
AASHTO Grades: M270-36; M270-50
ASME Grades: SA36

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

Bhaskar

BHASKAR YALAMANCHILI
QUALITY DIRECTOR

Michael

MICHAEL HERNDON
QUALITY ASSURANCE MGR.

Figure A-3. C7x12.25, 36-in. Long C-Channel, Test Nos. N2B-1 through N2B-6



US-ML-CARTERSVILLE
384 OLD GRASSDALE ROAD NE
CARTERSVILLE, GA 30121
USA

CERTIFIED MATERIAL TEST REPORT

Page 1/1

| | | | | |
|--|---|--------------------|--------------------------------------|-----------------------------|
| CUSTOMER SHIP TO STEEL & PIPE SUPPLY CO INC JONESBURG INDUSTRIAL PARK JONESBURG, MO 63351 USA | CUSTOMER BILL TO STEEL & PIPE SUPPLY CO INC MANHATTAN, KS 66505-1688 USA | GRADE GGMULTI | SHAPE / SIZE Channel / 12 X 20.7# | DOCUMENT ID: 0000091740 |
| SALES ORDER 5121870/000030 | CUSTOMER MATERIAL N° 000000002512207040 | LENGTH 40'00" | WEIGHT 19,872 LB | HEAT / BATCH 55049945/02 |
| SPECIFICATION / DATE or REVISION ASTM A529-14, A572-15 ASTM A6-14, A36-14, ASME SA-36 ASTM A709-15, AASHTO M270-12 CSA G40.20-13/G40.21-13 | | | | |
| CUSTOMER PURCHASE ORDER NUMBER G450023237 | BILL OF LADING 1323-0000090662 | DATE 05/31/2017 | | |

| CHEMICAL COMPOSITION | | | | | | | | | | | | | |
|----------------------|---------|--------|--------|---------|---------|---------|---------|---------|--------|---------|--------|---------|--|
| C % | Mn % | P % | S % | Si % | Cu % | Ni % | Cr % | Mo % | V % | Nb % | N % | Sn % | |
| 0.08 | 1.16 | 0.016 | 0.021 | 0.26 | 0.28 | 0.10 | 0.10 | 0.026 | 0.036 | 0.002 | 0.0100 | 0.009 | |

| MECHANICAL PROPERTIES | | | | | | | |
|-----------------------|-------------|------------|------------|----------------|-----------|--|--|
| Elong. % | G/L Inch | UTS PSI | UTS MPa | YS 0.2% PSI | YS MPa | | |
| 22.50 | 8.000 | 71900 | 496 | 54900 | 379 | | |
| 21.50 | 8.000 | 72700 | 501 | 55800 | 385 | | |

COMMENTS / NOTES

This grade meets the requirements for the following grades:
ASTM Grades: A36; A529-50; A572-50; A709-36; A709-50
CSA Grades: 44W; 50W
AASHTO Grades: M270-36; M270-50
ASME Grades: SA36

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

Bhaskar

BHASKAR YALAMANCHILI
QUALITY DIRECTOR

Phone: (409) 769-1014 Email: Bhaskar.Yalamanchili@gerdau.com

Yan Wang

YAN WANG
QUALITY ASSURANCE MGR.

Phone: (770) 387 5718 Email: yan.wang@gerdau.com

Figure A-4. C7x20.7, 36-in. Long C-Channel, Test Nos. N2B-1 through N2B-6

**STEEL AND
PIPE SUPPLY**
SPS Coil Processing Tulsa
5275 Bird Creek Ave.
Port of Catoosa, OK 74015

METALLURGICAL TEST REPORT

PAGE 1 of 1
DATE 06/27/2017
TIME 22:09:18
USER GIANGRER

S
O
L
D
T
O

S
H
I
P
T
O

13713
Warehouse 0020
1050 Fort Gibson Rd
CATOOSA OK 74015-3033

| Order | Material No. | Description | Quantity | Weight | Customer Part | Customer PO | Ship Date |
|---------------|--------------|--------------------------------------|----------|-----------|---------------|-------------|------------|
| 40287387-0030 | 70872120TM | 1/4 72 X 120 A36 TEMPERPASS STPLMLPL | 12 | 7,351.200 | | | 06/27/2017 |

| Heat No. 8707407 | | Vendor | Chemical Analysis | | | | | | | | | | Melted and Manufactured in the USA | | | |
|--------------------|-----------|-------------------------|---------------------------------------|---------|--------|----------|------------|--------|--------|----------|----------|----------|------------------------------------|----------|--------|--|
| Produced from Coil | | STEEL DYNAMICS COLUMBUS | DOMESTIC MILL STEEL DYNAMICS COLUMBUS | | | | | | | | | | | | | |
| Carbon | Manganese | Phosphorus | Sulphur | Silicon | Nickel | Chromium | Molybdenum | Boron | Copper | Aluminum | Titanium | Vanadium | Columbium | Nitrogen | Tin | |
| 0.0700 | 0.8100 | 0.0130 | 0.0030 | 0.0200 | 0.0400 | 0.0500 | 0.0100 | 0.0001 | 0.1000 | 0.0270 | 0.0030 | 0.0030 | 0.0010 | 0.0070 | 0.0050 | |

| Mechanical / Physical Properties | | | | | | | | | |
|----------------------------------|-----------|-------|-------|-------|--------|-----------|-----------|-------------|-------|
| Mill Coil No. 17B761473 | | | | | | | | | |
| Tensile | Yield | Elong | Rckwl | Grain | Charpy | Charpy Dr | Charpy Sz | Temperature | Olsen |
| 59600.000 | 44600.000 | 39.00 | | | 0 | NA | | | |
| 59600.000 | 44700.000 | 35.10 | | | 0 | NA | | | |
| 61295.000 | 43391.000 | 32.90 | | | 0 | NA | | | |
| 59828.000 | 42127.000 | 40.85 | | | 0 | NA | | | |

Batch 0004826149 12 EA 7,351.200 LB

THE CHEMICAL, PHYSICAL, OR MECHANICAL TESTS REPORTED ABOVE ACCURATELY REFLECT INFORMATION AS CONTAINED IN THE RECORDS OF THE CORPORATION.
The material is in compliance with EN 10204 Section 4.1 Inspection Certificate Type 3.1

Figure A-5. 10-in. x 2¾-in. x ¼-in. Plate Washer, Test Nos. N2B-1 through N2B-6



SPS Coil Processing Tulsa
5275 Bird Creek Ave.
Port of Catoosa, OK 74015

METALLURGICAL TEST REPORT

PAGE 1 of 1
DATE 06/27/2017
TIME 22:09:18
USER GIANGREER

S
O
L
D
T
O

S
H
I
P
T
O

13713
Warehouse 0020
1050 Fort Gibson Rd
CATOOSA OK 74015-3033

| Order | Material No. | Description | Quantity | Weight | Customer Part | Customer PO | Ship Date |
|---------------|--------------|-------------------------------------|----------|-----------|---------------|-------------|------------|
| 40287387-0030 | 70672120TM | 1/4 72 X 120 A36 TEMPERPASS STPMLPL | 12 | 7,351.200 | | | 06/27/2017 |

| Chemical Analysis | | | | | | | | | | | | | | | |
|--------------------|-------------------------|------------|---------|---------|--------|----------|------------|--------|--------|----------|----------|------------------------------------|-----------|----------|--------|
| Heat No. | Vendor | DOMESTIC | | | | | | | | | | Melted and Manufactured in the USA | | | |
| B707407 | STEEL DYNAMICS COLUMBUS | | | | | | | | | | | | | | |
| Produced from Coil | | | | | | | | | | | | | | | |
| Carbon | Manganese | Phosphorus | Sulphur | Silicon | Nickel | Chromium | Molybdenum | Boron | Copper | Aluminum | Titanium | Vanadium | Columbium | Nitrogen | Tin |
| 0.0700 | 0.8100 | 0.0130 | 0.0030 | 0.0200 | 0.0400 | 0.0500 | 0.0100 | 0.0001 | 0.1000 | 0.0270 | 0.0030 | 0.0030 | 0.0010 | 0.0070 | 0.0050 |

| Mechanical / Physical Properties | | | | | | | | | | |
|----------------------------------|-----------|-----------|-------|-------|-------|--------|-----------|-----------|-------------|-------|
| Mill Coil No. | Tensile | Yield | Elong | Rckwl | Grain | Charpy | Charpy Dr | Charpy Sz | Temperature | Olsen |
| 17B761473 | 59600.000 | 44600.000 | 39.00 | | | 0 | NA | | | |
| | 59600.000 | 44700.000 | 35.10 | | | 0 | NA | | | |
| | 61295.000 | 43391.000 | 32.90 | | | 0 | NA | | | |
| | 59828.000 | 42127.000 | 40.85 | | | 0 | NA | | | |

Batch 0004826149 12 EA 7,351.200 LB

THE CHEMICAL, PHYSICAL, OR MECHANICAL TESTS REPORTED ABOVE ACCURATELY REFLECT INFORMATION AS CONTAINED IN THE RECORDS OF THE CORPORATION.
The material is in compliance with EN 10204 Section 4.1 Inspection Certificate Type 3.1

Figure A-6. 2-in. x 2-in. x 1/4-in. Gusset, Test Nos. N2B-1 through N2B-6

Atlas Tube Corp (Chicago)
1855 East 122nd Street
Chicago, Illinois, USA
60633
Tel: 773-646-4500
Fax: 773-646-6128



Ref.B/L: 80773104
Date: 07.24.2017
Customer: 179

MATERIAL TEST REPORT

Sold to

Steel & Pipe Supply Company
PO Box 1688
MANHATTAN KS 66505
USA

Shipped to

Steel & Pipe Supply Company
1020 West Fort Gibson
CATOOSA OK 74015
USA

| | | | | | | | | | | | | | | | |
|----------------------------------|-------|------------|------------|----------------------------|---------|-------|------------------------|-------|-------|-------|----------|-----------------------------|-------|-------|-------|
| Material: 4.0x4.0x375x40"0(5x2). | | | | Material No: 400403754000 | | | | | | | | Made in: USA | | | |
| | | | | | | | | | | | | Melted in: USA | | | |
| Sales order: 1196766 | | | | Purchase Order: 4500290927 | | | | | | | | Cust Material #: 6540037540 | | | |
| Heat No | C | Mn | P | S | Si | Al | Cu | Cb | Mo | Ni | Cr | V | Ti | B | N |
| W45369 | 0.190 | 0.790 | 0.011 | 0.007 | 0.020 | 0.039 | 0.040 | 0.004 | 0.003 | 0.010 | 0.050 | 0.002 | 0.001 | 0.000 | 0.005 |
| Bundle No | PCs | Yield | Tensile | | Eln.2in | | Certification | | | | CE: 0.34 | | | | |
| M800718467 | 10 | 061632 Psi | 073060 Psi | | 30 % | | ASTM A500-13 GRADE B&C | | | | | | | | |
| Material Note: | | | | | | | | | | | | | | | |
| Sales Or.Note: | | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | |
|----------------------------------|-------|------------|------------|----------------------------|---------|-------|------------------------|-------|-------|-------|----------|-----------------------------|-------|-------|-------|
| Material: 4.0x4.0x375x40"0(5x2). | | | | Material No: 400403754000 | | | | | | | | Made in: USA | | | |
| | | | | | | | | | | | | Melted in: USA | | | |
| Sales order: 1196766 | | | | Purchase Order: 4500290927 | | | | | | | | Cust Material #: 6540037540 | | | |
| Heat No | C | Mn | P | S | Si | Al | Cu | Cb | Mo | Ni | Cr | V | Ti | B | N |
| W45369 | 0.190 | 0.790 | 0.011 | 0.007 | 0.020 | 0.039 | 0.040 | 0.004 | 0.003 | 0.010 | 0.050 | 0.002 | 0.001 | 0.000 | 0.005 |
| Bundle No | PCs | Yield | Tensile | | Eln.2in | | Certification | | | | CE: 0.34 | | | | |
| M800718474 | 10 | 061632 Psi | 073060 Psi | | 30 % | | ASTM A500-13 GRADE B&C | | | | | | | | |
| Material Note: | | | | | | | | | | | | | | | |
| Sales Or.Note: | | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | |
|----------------------------------|-------|------------|------------|----------------------------|---------|-------|------------------------|-------|-------|-------|----------|--------------------------------|-------|-------|-------|
| Material: 6.0x4.0x375x40"0(3x2). | | | | Material No: 600403754000 | | | | | | | | Made in: USA | | | |
| | | | | | | | | | | | | Melted in: USA | | | |
| Sales order: 1198462 | | | | Purchase Order: C450006656 | | | | | | | | Cust Material #: 6660040037540 | | | |
| Heat No | C | Mn | P | S | Si | Al | Cu | Cb | Mo | Ni | Cr | V | Ti | B | N |
| V2570 | 0.190 | 0.620 | 0.013 | 0.010 | 0.020 | 0.031 | 0.160 | 0.009 | 0.020 | 0.060 | 0.090 | 0.002 | 0.001 | 0.000 | 0.008 |
| Bundle No | PCs | Yield | Tensile | | Eln.2in | | Certification | | | | CE: 0.33 | | | | |
| M800717340 | 6 | 071646 Psi | 082892 Psi | | 29 % | | ASTM A500-13 GRADE B&C | | | | | | | | |
| Material Note: | | | | | | | | | | | | | | | |
| Sales Or.Note: | | | | | | | | | | | | | | | |

Jason Richard
Jason Richard

Authorized by Quality Assurance:
The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements.
CE calculated using the AWS D1.1 method.



Figure A-7. HSS4x4x3/8 Square Tube, Test Nos. N2B-1 through N2B-6

SSAB

Preliminary Test Certificate

Form TC1: Revision 2: Date 23 Apr 2014

1770 Bill Sharp Boulevard, Muscatine, IA 52761-9412, US **Official copy to follow**

| | | | | | | | |
|--|--|-------------------------------|--|--|--|-------------------------------------|--|
| Customer: STEEL & PIPE SUPPLY P.O. BOX 1688 MANHATTAN KS 66502 | | Customer P.O. No.: 4500287649 | | Mill Order No.: 41-504804-02 | | Shipping Manifest : MT318692 | |
| Product Description: ASTM A572-50/M345(15)/A709-50/M345(16A) | | | | Ship Date: 21 Jun 17 Cert Date: 21 Jun 17 | | Cert No: 061649975 (Page 1 of 1) | |
| Size: 0.500 X 96.00 X 240.0 (IN) | | | | | | | |

| Tested Pieces | | | Tensiles | | | | | | Charpy Impact Tests | | | | | | | | | | | | |
|---------------|----------|------------------|----------|----------|-----------|-----|--------------------|---------|---------------------|--------------------------------|--|--|--|----------------------|--|--|--|---------|---------|--------------|-------------------|
| Heat Id | Piece Id | Tested Thickness | Tst Loc | YS (KSI) | UTS (KSI) | %RA | Elong % 2in 8in | Tst Dir | Hardness | Abs. Energy(FTLB) 1 2 3 Avg | | | | % Shear 1 2 3 Avg | | | | Tst Tmp | Tst Dir | Tst Siz (mm) | BDWTT Tst %Shr |
| A7D898 | D19 | 0.496 (DISCRT) | L 61 | 73 | | | 38 | T | | | | | | | | | | | | | |
| A7F058 | D31 | 0.497 (DISCRT) | L 55 | 68 | | | 37 | T | | | | | | | | | | | | | |
| B7D657 | D18 | 0.507 (DISCRT) | L 57 | 77 | | | 28 | T | | | | | | | | | | | | | |

| Heat Id | Chemical Analysis | | | | | | | | | | | | | | ORGN |
|---------|-------------------|------|------|------|-----|--------|-----|-----|-----|-----|------|------|------|-----|------|
| | C | Mn | P | S | Si | Tot Al | Cu | Ni | Cr | Mo | Cb | V | Ti | | |
| A7D898 | .05 | 1.32 | .014 | .004 | .10 | .034 | .30 | .14 | .15 | .03 | .024 | .027 | .008 | USA | |
| A7F058 | .05 | 1.21 | .012 | .006 | .02 | .028 | .31 | .14 | .10 | .04 | .002 | .053 | .001 | USA | |
| B7D657 | .16 | 1.14 | .013 | .007 | .03 | .029 | .30 | .15 | .17 | .04 | .002 | .033 | .006 | USA | |

KILLED STEEL.
MERCURY IS NOT A METALLURGICAL COMPONENT OF THE STEEL AND NO MERCURY WAS INTENTIONALLY ADDED DURING THE MANUFACTURE OF THIS PRODUCT.
MTR EN 10204:2004 INSPECTION CERTIFICATE 3.1 COMPLIANT
100% MELTED AND MANUFACTURED IN THE USA.
PRODUCTS SHIPPED:

| | | | | | | | | | |
|--------|-----|-------|---------|------|--------|-----|-------|---------|------|
| B7D657 | D18 | PCES: | 2, LBS: | 6534 | A7F058 | D31 | PCES: | 1, LBS: | 3267 |
| A7D898 | D19 | PCES: | 3, LBS: | 9801 | | | | | |

| | | |
|-------------------------------|--|-----------------------------|
| (H) Cust Part # : 721696240A2 | WE HEREBY CERTIFY THAT THIS MATERIAL WAS TESTED IN ACCORDANCE WITH, AND MEETS THE REQUIREMENTS OF, THE APPROPRIATE SPECIFICATION | SENTRY METALLURGY - PRODUCT |
|-------------------------------|--|-----------------------------|

Figure A-8. 1/2-in. Thick Steel Plate, Test Nos. N2B-1 through N2B-6



US-ML-MIDLOTHIAN
300 WARD ROAD
MIDLOTHIAN, TX 76065
USA

CUSTOMER SHIP TO
STEEL & PIPE SUPPLY CO INC
401 NEW CENTURY PKWY
NEW CENTURY,KS 66031-1127
USA

CUSTOMER BILL TO
STEEL & PIPE SUPPLY CO INC
MANHATTAN,KS 66505-1688
USA

GRADE
A36/A572-50

SHAPE / SIZE
Standard I-Beam / 3 X 5.7# / 75 X
8.5

DOCUMENT ID:
0000050470

LENGTH
40'00"

| | |
|--------|----------|
| WEIGHT | 8,208 LB |
|--------|----------|

HEAT / BATCH
59070748/02

SALES ORDER
4082394/000030

CUSTOMER MATERIAL N°
000000000035357040

SPECIFICATION / DATE of REVISION

ASME SA36
ASTM A572-15
ASTM A6-14, A36-14
ASTM A709-13A

CUSTOMER PURCHASE ORDER NUMBER
4500271337

BILL OF LADING
1327-0000209580

| | |
|------|------------|
| DATE | 09/02/2016 |
|------|------------|

CHEMICAL COMPOSITION

| C % | Mn % | P % | S % | Si % | Cu % | Ni % | Cr % | Mo % | Sn % | V % | Nb % | Al % |
|------|------|-------|-------|------|------|------|------|-------|-------|-------|-------|-------|
| 0.14 | 0.91 | 0.020 | 0.035 | 0.21 | 0.32 | 0.17 | 0.16 | 0.036 | 0.009 | 0.003 | 0.013 | 0.002 |

CHEMICAL COMPOSITION

CEgyA6
%
0.36

MECHANICAL PROPERTIES

YS 0.2%
PSI
61464
61487

UTS
PSI
78321
78301

YS
MPa
424
424

UTS
MPa
540
540

| | |
|-------|--|
| G/L | |
| Inch | |
| 8.000 | |
| 8.000 | |

| | |
|-------|--|
| G/L | |
| mm | |
| 200.0 | |
| 200.0 | |

MECHANICAL PROPERTIES

| | |
|--------|--|
| Elong. | |
| 23.40 | |
| 21.30 | |

COMMENTS / NOTES

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

Pharkay

BHASKAR YALAMANCHILI
— QUALITY DIRECTOR

Tom L. Dainton

TOM HARRINGTON
QUALITY ASSURANCE MGR.

Figure A-9. S3x5.7 Steel Post, Test Nos. N2B-1 through N2B-6



GERDAU

US-ML-WILTON
1500-2500 WEST 3RD STREET
WILTON, IA 52778
USA

CERTIFIED MATERIAL TEST REPORT

Page 1/1

| | | | | | | |
|--|--|---|--|-----------------------------------|------------------------------------|-----------------------------|
| CUSTOMER SHIP TO STEEL & PIPE SUPPLY CO INC 401 NEW CENTURY PKWY NEW CENTURY, KS 66031-1127 USA | | CUSTOMER BILL TO STEEL & PIPE SUPPLY CO INC MANHATTAN, KS 66505-1688 USA | | GRADE A36/44W | SHAPE / SIZE Flat Bar / 1/4 X 1 | DOCUMENT ID: 0000011110 |
| SALES ORDER 4190352/000010 | | CUSTOMER MATERIAL N° 00000000010810020 | | LENGTH 20'00" | WEIGHT 19,584 LB | HEAT / BATCH 64055041/02 |
| SPECIFICATION / DATE or REVISION ASME SA36 ASTM A6-14, A36-14 ASTM A709-15, AASHTO M270-12 CSA G40.20-13/G40.21-13 | | CUSTOMER PURCHASE ORDER NUMBER 4500272853 | | BILL OF LADING 1334-0000034941 | | DATE 09/20/2016 |

| CHEMICAL COMPOSITION | | | | | | | | | | | | |
|----------------------|---------|--------|--------|---------|---------|---------|---------|---------|--------|---------|---------|---------|
| C % | Mn % | P % | S % | Si % | Cu % | Ni % | Cr % | Mo % | V % | Nb % | Al % | Pb % |
| 0.15 | 0.57 | 0.007 | 0.021 | 0.21 | 0.26 | 0.09 | 0.07 | 0.020 | 0.001 | 0.014 | 0.002 | 0.0000 |

| CHEMICAL COMPOSITION | | Sn % |
|--------------------------|--|---------|
| CEq _{A529} % | | |
| 0.33 | | 0.018 |

| MECHANICAL PROPERTIES | | | | | |
|-----------------------|-------------|------------|------------|-----------|-----------|
| Elong. % | G/L Inch | UTS PSI | UTS MPa | YS PSI | YS MPa |
| 22.50 | 8.000 | 74300 | 512 | 58000 | 400 |
| 22.50 | 8.000 | 74400 | 513 | 57600 | 397 |

| GEOMETRIC CHARACTERISTICS |
|---------------------------|
| R-R |
| 123.14 |

COMMENTS / NOTES

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

Maskar

BHASKAR YALAMANCHILI
QUALITY DIRECTOR

Brett Krause BRETT KRAUSE
QUALITY ASSURANCE MGR.

Figure A-10. 2¾-in. x 1-in. x ¼-in. Post, Test Nos. N2B-1 through N2B-6



ISO 9001, ISO/TS16949
ISO / IEC 17025
ISO 14001



LOT NO.: 1610-58099
3023G

FASTENER TEST REPORT

(THIS DOCUMENT MAY ONLY BE REPRODUCED IN ITS ENTIRETY, WITH PRIOR WRITTEN APPROVAL BY THE INFASCO LABORATORY)

(THE INFASCO LABORATORY IS ACCREDITED BY THE CCN FOR THE TESTS LISTED AT WWW.CCN.CA)

COMPLIES WITH EN10204 2004 INSPECTION CERTIFICATE 3.1

DATE 2016-10-19

| | | | |
|-------------------------|--|----------|-------|
| DESCRIPTION AND MARKING | A325-1 STRUCTURAL BOLT UNC N HDG HOLLOW TRIANGLE & "A325" | | |
| SIZE | 5/8-11 X 5 | GRADE | 1036M |
| | | QUANTITY | 5,800 |

HEAT CHEMICAL ANALYSIS (provided by steel supplier)

| HEAT NO. | C % | Mn % | P % | S % | Si % | | | | |
|----------|------|------|-------|-------|------|--|--|--|--|
| C20373 | 0.36 | 0.96 | 0.007 | 0.013 | 0.25 | | | | |

| METHOD | ASTM F606 PROOF LOAD (psi) | ASTM F606 WEDGE TENSILE STRENGTH (psi) | SHEAR STRENGTH | SURFACE HARDNESS (HR 30N) | ASTM F606 CORE HARDNESS (ROCKWELL) HRC 25.0 HRC 34.0 | MICRO HARDNESS | ASTM E376 COATING THICKNESS (0.001 in) |
|------------|----------------------------------|---|----------------|------------------------------|--|----------------|---|
| SPEC. MIN. | 85,000 | 120,000 | | | | | 2.00 |
| SPEC. MAX: | | | | | | | |
| S NO. 1 | 87,000 | 147,000 | | | HRC 32.2 | | 3.52 |
| A NO. 2 | 87,000 | 146,000 | | | 32.7 | | 3.63 |
| M NO. 3 | 87,000 | 147,000 | | | 32.0 | | 3.98 |
| P NO. 4 | | | | | 32.4 | | 2.92 |
| L NO. 5 | | | | | | | 3.41 |
| E NO. 6 | | | | | | | 3.41 |
| | | | | | | | 4.09 |
| | | | | | | | 3.28 |
| | | | | | | | 3.95 |
| | | | | | | | 2.66 |
| | | | | | | | 3.07 |
| | | | | | | | 2.65 |
| | | | | | | | 3.30 |
| | | | | | | | 3.50 |
| | | | | | | | 3.42 |

THE ABOVE TESTED SAMPLES HAVE BEEN INSPECTED FOR VISUAL DISCONTINUITIES AND FOUND ACCEPTABLE. THEY COMPLY IN ALL RESPECTS WITH THE LATEST EDITION OF THE FOLLOWING SPECS:
ASTM A325 TYPE 1 ASME B18.2.6, THREADS PER ASME B1.1 CLASS 2A. UNLESS OTHERWISE SPECIFIED.
MEETS THE SURFACE DISCONTINUITIES REQUIREMENTS
ASTM F2329, ASTM-A-153 Class C
THESE FASTENERS WERE OIL QUENCHED AND TEMPERED AT A TEMP. ABOVE 800°F.
NO BISMUTH, SELENIUM, TELLURIUM OR LEAD HAVE BEEN INTENTIONALLY ADDED
COATING THICKNESS VALUES PROVIDED BY COATING SUPPLIER.

MANUFACTURED IN: CANADA
The steel was melted and rolled
in North America and is mercury and asbestos-free.

INFASCO
A division of Ilastgroupe LP 700 Ouellette, Marleville (Quebec) J3M 1P5
A Helco Company Tel.: (450) 658-8741 Fax: (450) 480-6496

Isabelle Parent, Eng., M.A.Sc.
Quality Assurance Foreman

FQ-019-2 Rev. 09

Revision date of test report: 2017-01-09

Page 1 of 1

Figure A-11. 5/8-in. Dia., 5-in. Long Heavy Hex Head Bolt, Test Nos. N2B-1 through N2B-6



ISO 9001, ISO/TS16949
ISO / IEC 17025
ISO 14001

LOT NO: 1604-53117
8441G



FASTENER TEST REPORT

(THIS DOCUMENT MAY ONLY BE REPRODUCED IN ITS ENTIRETY, WITH PRIOR WRITTEN APPROVAL BY THE INFASCO LABORATORY)

(THE INFASCO LABORATORY IS ACCREDITED BY THE CCN FOR THE TESTS LISTED AT WWW.CCN.CA)

COMPLIES WITH EN10204:2004 INSPECTION CERTIFICATE 3.1

DATE 2016-05-25

| | | | |
|-------------------------|--|----------|---------|
| DESCRIPTION AND MARKING | HVY HEX NUT A563-DH FNA OS. UNC OS HDG+L TRIANGLE & "DH" | | |
| SIZE | 5/8-11 .020 O/S | GRADE | 1046 |
| | | QUANTITY | 131,000 |

HEAT CHEMICAL ANALYSIS (provided by steel supplier)

| HEAT NO. | C % | Mn % | P % | S % | Si % | Cu % | Ni % | | |
|----------|------|------|-------|-------|------|------|------|--|--|
| C114376 | 0.44 | 0.84 | 0.010 | 0.009 | 0.22 | 0.12 | 0.06 | | |

| METHOD | ASTM F606 | | | | ASTM F606 | | ASTM E376 |
|------------|------------|------------------------|----------------|---------------------------|--------------------------|----------------|-------------------|
| | PROOF LOAD | WEDGE TENSILE STRENGTH | SHEAR STRENGTH | SURFACE HARDNESS (HR 30N) | CORE HARDNESS (ROCKWELL) | MICRO HARDNESS | COATING THICKNESS |
| | (psi) | | | | | | (0.001 in) |
| SPEC. MIN. | 150,000 | | | | HRC 24.0 | | 2.00 |
| SPEC. MAX. | | | | | HRC 38.0 | | |
| S NO.1 | 157,000 | | | | HRC 30.6 | | 3.38 |
| A NO.2 | 155,000 | | | | 29.8 | | 3.23 |
| M NO.3 | 156,000 | | | | 30.7 | | 3.06 |
| P NO.4 | 156,000 | | | | 29.9 | | 2.59 |
| L NO.5 | 155,000 | | | | 31.9 | | 2.68 |
| E NO.6 | | | | | | | 2.68 |
| | | | | | | | 2.88 |
| | | | | | | | 2.60 |
| | | | | | | | 2.20 |
| | | | | | | | 2.50 |
| | | | | | | | 2.76 |
| | | | | | | | 2.83 |
| | | | | | | | 2.94 |
| | | | | | | | 2.16 |
| | | | | | | | 2.35 |

THE ABOVE TESTED SAMPLES HAVE BEEN INSPECTED FOR VISUAL DISCONTINUITIES AND FOUND ACCEPTABLE. THEY COMPLY IN ALL RESPECTS WITH THE LATEST EDITION OF THE FOLLOWING SPECS:
ASTM A563 DH AND ASME B18.2.2, THREADS PER ASME B1.1 CLASS 2B UNLESS OTHERWISE SPECIFIED.

ASTM F2329, ASTM-A-153 CLASS C + LUBRICANT

COATING THICKNESS VALUES PROVIDED BY COATING SUPPLIER.

MANUFACTURED IN: CANADA
The steel was melted and rolled
in North America and is mercury and asbestos-free.

INFASCO
A division of Iifest groupe LP
A Helco Company
700 Ouellette, Marleville (Quebec) J3M 1P6
Tel.: (450) 658-8741 Fax: (450) 460-5496

Daniel Gullbault
Quality Assurance Foreman

FQ-019-2 Rev. 09

Revision date of test report: 2016-06-17

Page 1 of 1

Figure A-12. 5/8-in. Dia. 5-in. Long Heavy Hex Head Nut, Test Nos. N2B-1 through N2B-6

NUCOR
FASTENER DIVISION

LOT NO.
353485A

Post Office Box 6100
Saint Joe, Indiana 46785
Telephone 260/337-1600

CUSTOMER NO/NAME
143 CORDOVA BOLT INC

NUCOR ORDER # 970775

TEST REPORT SERIAL# F8449739

CUST PART #

TEST REPORT ISSUE DATE 11/26/14

DATE SHIPPED 5/23/16

CUSTOMER P.O. # 055645

NAME OF LAB SAMPLER: RYAN UNGER, LAB TECHNICIAN

*****CERTIFIED MATERIAL TEST REPORT*****

NUCOR PART NO QUANTITY LOT NO. DESCRIPTION

160556 650 353485A 3/4-10 X 1 3/4 A325-T HVY HEX

MANUFACTURE DATE 11/17/14

STRUC SCREW PLAIN LESS NUT

A325T
n

--CHEMISTRY MATERIAL GRADE -1039ML1

MATERIAL HEAT **CHEMISTRY COMPOSITION (MTZ HEAT ANALYSIS) BY MATERIAL SUPPLIER

NUMBER C MN P S SI NUCOR STEEL - NEBRASKA

RM029564 NF14204233 .40 .88 .006 .016 .25

--MECHANICAL PROPERTIES IN ACCORDANCE WITH ASTM A325-14

| SURFACE | CORE | PROOF LOAD | TENSILE STRENGTH | |
|---------------------------|----------|------------|------------------|--------------|
| HARDNESS | HARDNESS | 28400 LBS | 4 DEG-WEDGE | |
| (R30N) | (RC) | | (LBS) | STRESS (PSI) |
| N/A | 30.0 | PASS | 49490 | 148174 |
| N/A | 31.6 | PASS | 48610 | 145539 |
| N/A | 31.0 | PASS | 49240 | 147425 |
| N/A | 31.1 | | | |
| AVERAGE VALUES FROM TESTS | | | 49113 | 147046 |
| 30.9 | | | | |
| PRODUCTION LOT SIZE | | 6800 PCS | | |

--VISUAL INSPECTION IN ACCORDANCE WITH ASTM A325-14

HEAT TREATMENT - AUSTENITIZED, OIL QUENCHED & TEMPERED (MIN 800 DEG F)


4 PCS. SAMPLED LOT PASSED

--DIMENSIONS PER ASME B18.2.6-2010

| CHARACTERISTIC | #SAMPLES TESTED | MINIMUM | MAXIMUM |
|----------------------|-----------------|---------|---------|
| Width Across Corners | 8 | 1.399 | 1.402 |
| Head Height | 8 | 0.468 | 0.475 |
| Threads | 8 | PASS | PASS |

ALL TESTS ARE IN ACCORDANCE WITH THE LATEST REVISIONS OF THE METHODS PRESCRIBED IN THE APPLICABLE SAE AND ASTM SPECIFICATIONS. THE SAMPLES TESTED CONFORM TO THE SPECIFICATIONS AS DESCRIBED/LISTED ABOVE AND WERE MANUFACTURED FREE OF MERCURY CONTAMINATION. NO HEATS TO WHICH BISMUTH, SELENIUM, TELLURIUM, OR LEAD WAS INTENTIONALLY ADDED HAVE BEEN USED TO PRODUCE THE BOLTS.

THE STEEL WAS MELTED AND MANUFACTURED IN THE U.S.A. AND THE PRODUCT WAS MANUFACTURED AND TESTED IN THE U.S.A. PRODUCT COMPLIES WITH DFARS 252.225-7016. WE CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL SUPPLIER AND OUR TESTING LABORATORY. THIS CERTIFIED MATERIAL TEST REPORT RELATES ONLY TO THE ITEMS LISTED ON THIS DOCUMENT AND MAY NOT BE REPRODUCED EXCEPT IN FULL.

 ACCREDITED

MECHANICAL FASTENER
CERTIFICATE NO. A2LA 0159.01
EXPIRATION DATE 12/31/15

NUCOR FASTENER
A DIVISION OF NUCOR CORPORATION

John W. Ferguson
JOHN W. FERGUSON
QUALITY ASSURANCE SUPERVISOR

Figure A-13. 3/4-in. Dia. 1 3/4-in. Long Heavy Hex Head Bolt, Test Nos. N2B-1 through N2B-6

Customer: WECALL INC

Ord #: T803092 Part #: 507373 Cust PO#: 21642

Page 1 of 2

NUCOR
NUCOR GOLD FINISH WISCONSIN, INC.

Mill Certification
1/13/2017

MTR #: E1-135435
7200 S 6th St
OAK CREEK, WI 53154
(414) 764-0220
Fax: (414) 764-2073

Sold To: EARLE M JORGENSEN CO
1900 MITCHELL BLVD
PO BOX 1900
SCHAUMBURG, IL 60194
(847) 301-2346
Fax: (847) 891-2203

Ship To: EARLE M JORGENSEN CO
1900 MITCHELL BLVD
SCHAUMBURG, IL 60194
(847) 301-6116
Fax: (847) 891-2203

R 135982

| | | | |
|---------------|--|-----------------|------------|
| Customer P.O. | P764144-423 | Sales Order | 634243.1 |
| Product Group | Cold Finish Bar | Part Number | 321499 |
| Grade | 4140/4142 ASTM A106 (REPLACES ASTM A331) | Lot # | E1177188 |
| Size | Hex 1.2500 (.0050) | Heat # | NF16203911 |
| Product | HX 1.2500" 4140DH 12-R AN.CD | B.L. Number | E1-235907 |
| Description | CF Grade 4140DH | Load Number | E1-135435 |
| Customer Spec | 4140 | Customer Part # | 507373 |

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.

Part Detail: HX 1.2500" 4140 12-R Cold Drawn Annealed
Process: Annealed, Cold Drawn

Melt Date: 11/3/2016

| | | | | | | | | | | | |
|--------|--------|--------|--------|-------|-------|-------|-------|--------|--------|---------|--------|
| C | Mn | P | S | Si | Cu | Cr | Ni | Mo | Sn | V | Cb |
| 0.42% | 0.98% | 0.008% | 0.027% | 0.27% | 0.13% | 0.98% | 0.10% | 0.180% | 0.007% | 0.0060% | 0.004% |
| Al | Pb | | | | | | | | | | |
| 0.030% | 0.000% | | | | | | | | | | |

DI value: 5.75

Melting Mill: Nucor Bar NE

Country of Melting: USA

Simulated Hardenability Band

| | | | | | | | | | | | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|----|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| J1 | J2 | J3 | J4 | J5 | J6 | J7 | J8 | J9 | J10 | J11 | J12 | J13 | J14 | J15 | J16 | J18 | J20 | J22 | J24 | J26 | J28 | J30 | J32 |
| 57 | 57 | 57 | 57 | 57 | 57 | 57 | 57 | 55 | 54 | 52 | 50 | 50 | 50 | 49 | 48 | 48 | 47 | 46 | 45 | 44 | 43 | 42 | 40 |

Reduction Ratio 29.0 :1

Country of Rolling: USA

Rolling Mill: Nucor Bar NE

Grain Size per ASTM E112 = 0

ASTM E381

Surface: 1 Mid Radius: 1 Center: 3

ASTM E45 Method A (Worst)

Sulfides: T: 2.0 H: 0.5 Alumina: T: 1.0 H: 0.5 Silicates: T: 0.5 H: 0.0 Globular: T: 1.0 H: 0.5

- All products produced are weld free.
- Mercury, in any form, has not been used in the production or testing of this material.

Nick Schultz

Nick Schultz
Sales Manager

NBMG-10 January 1, 2012

Page 5 of 6

Figure A-14. 3/4-in. Dia. Heavy Hex Coupling Nut, Test Nos. N2B-1 through N2B-6

30712

Figure A-15. $\frac{3}{4}$ -in. Dia. 30-in. Long Threaded Rod, Test Nos. N2B-1 through N2B-6



GEM-YEAR TESTING LABORATORY CERTIFICATE OF INSPECTION

MANUFACTURER : GEM-YEAR INDUSTRIAL CO., LTD.
ADDRESS : NO.8 GEM-YEAR
ROAD,E.D.Z.,JIASHAN,ZHEJIANG,P.R.CHINA

Tel: (0573)84185001(48Lines)
Fax: (0573)84184488 84184567
DATE : 2018/03/28

PURCHASER : FASTENAL COMPANY PURCHASING

PACKING NO : GEM180115010

PO. NUMBER : 110254885

INVOICE NO : GEM/FNL-180201WI-1

COMMODITY : FINISHED HEX NUT GR-A

PART NO : 36717

SIZE : 7/8-9 NC Q/T 0.56MM

SAMPLING PLAN :

LOT NO : 1N1810005

ASME B18.18-2011 (Category.2)/ASTM F1470-2012

SHIP QUANTITY : 9,000 PCS

HEAT NO : 331704677

LOT QUANTITY 55,748 PCS

MATERIAL : XGML08

HEADMARKS :

FINISH : HOT DIP GALVANIZED PER ASTM A153-
2009/ASTM F2329-2013

MANUFACTURE DATE : 2018/01/05

COUNTRY OF ORIGIN : CHINA

PERCENTAGE COMPOSITION OF CHEMISTRY:ACCORDING TO ASTM A563-2015

| Chemistry | AL% | C% | MN% | P% | S% | SI% |
|--------------|--------|--------|--------|--------|--------|--------|
| Spec. : MIN. | | | | | | |
| MAX. | | 0.5800 | | 0.1300 | 0.2300 | |
| Test Value | 0.0360 | 0.0600 | 0.4500 | 0.0140 | 0.0030 | 0.0300 |

DIMENSIONAL INSPECTIONS :ACCORDING TO ASME B18.2.2-2015

SAMPLED BY : WDANDAN

| INSPECTIONS ITEM | SAMPLE | SPECIFIED | ACTUAL RESULT | ACC. | REJ. |
|-------------------------|--------|------------------------------------|--------------------|------|------|
| WIDTH ACROSS CORNERS | 5 PCS | 1.4470-1.5160 inch | 1.4850-1.4930 inch | 5 | 0 |
| FIM | 15 PCS | ASME B18.2.2-2015 Max. 0.0250 inch | 0.0110-0.0200 inch | 15 | 0 |
| THICKNESS | 5 PCS | 0.7240-0.7760 inch | 0.7460-0.7570 inch | 5 | 0 |
| WIDTH ACROSS FLATS | 5 PCS | 1.2690-1.3120 inch | 1.2930-1.2980 inch | 5 | 0 |
| SURFACE DISCONTINUITIES | 29 PCS | ASTM F812-2012 | PASSED | 29 | 0 |
| THREAD | 15 PCS | GAGING SYSTEM 21 | PASSED | 15 | 0 |

MECHANICAL PROPERTIES : ACCORDING TO ASTM A563-2015

SAMPLED BY : TANGHAO

| INSPECTIONS ITEM | SAMPLE | TEST METHOD | REF | SPECIFIED | ACTUAL RESULT | ACC. | REJ. |
|------------------------|--------|----------------|-----|-----------------|---------------|------|------|
| CORE HARDNESS | 15 PCS | ASTM F606-2014 | | 68-107 HRB | 86-90 HRB | 15 | 0 |
| PROOF LOAD | 5 PCS | ASTM F606-2014 | | Min. 31,416 LBF | OK | 5 | 0 |
| PLATING THICKNESS(μm) | 29 PCS | ASTM B568-1998 | | ≥53 | 62.38-62.57 | 29 | 0 |

WE CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL SUPPLIER
AND OUR TESTING LABORATORY .WHICH ACCREDITED BY ISO/IEC17025(CERTIFICATE NUMBER:3358.01)
WE CERTIFY THAT THE PRODUCTS SUPPLIED ARE IN COMPLIANCE WITH THE REQUIREMENTS OF THE ORDER

Quality Supervisor:

Figure A-16. 7/8-in. Dia. 2-in. Long Heavy Hex Head Bolt, Test Nos. N2B-1 through N2B-6

NUCOR
NUCOR COLD FINISH WISCONSIN, INC.

Mill Certification
4/16/2016

MTR #: 0000008756
7200 S 6th St
OAK CREEK, WI 53154
(414) 764-0220
Fax: (414) 764-2073

Sold To: ALRO STEEL CORP
PO BOX 927
JACKSON, MI 49204-0927
(517) 787-5500
Fax: (517) 787-6399

Ship To: ALRO - AKRON
4787 STATE RD
CUYAHOGA FALLS, OH 44223-3555
(330) 929-4860
Fax: (517) 787-6399

| | | | |
|---------------|--|-----------------|------------|
| Customer P.O. | AK11262453 | Sales Order | 606726.1 |
| Product Group | Cold Finish Bar | Part Number | 321503 |
| Grade | 4140/4142 ASTM A108 (REPLACES ASTM A331) | Lot # | E1164321 |
| Size | Hex 1.5000 (.0050) | Heat # | NF14103504 |
| Product | HX 1.5000" 4140DH 12-R AN.CD ✓ | S.L. Number | E1-229548 |
| Description | CF Grade 4140DH ✓ | Load Number | E1-129088 |
| Customer Spec | 4140 | Customer Part # | 32563000 |

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and shall conform to those requirements.

Part Detail: HX 1.5000" 4140 12-R Cold Drawn Annealed
Process: Annealed, Cold Drawn

Melt Date: 10/3/2014

| | | | | | | | | | | | |
|--------|--------|--------|--------|-------|-------|-------|-------|--------|--------|---------|--------|
| C | Mn | P | S | Si | Cu | Cr | Ni | Mo | Sn | V | Cb |
| 0.40% | 0.95% | 0.006% | 0.022% | 0.31% | 0.16% | 0.95% | 0.08% | 0.190% | 0.007% | 0.0060% | 0.004% |
| Al | Pb | | | | | | | | | | |
| 0.028% | 0.000% | | | | | | | | | | |

DI value: 5.70

Melting Mill: Nucor Bar NE

Country of Melting: USA

Grain Practice: FINE

Simulated Hardenability Band

| | | | | | | | | | | | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|----|----|-----|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| J1 | J2 | J3 | J4 | J5 | J6 | J7 | J8 | J9 | J10 | J11 | J12 | J13 | J14 | J15 | J16 | J18 | J20 | J22 | J24 | J26 | J28 | J30 | J32 |
| 56 | 56 | 50 | 56 | 56 | 58 | 56 | 58 | 54 | 53 | 51.0 | 49 | 49 | 49 | 46 | 47 | 47 | 46 | 45 | 45 | 43 | 42 | 41 | 39 |

Reduction Ratio 21.0 :1

Country of Rolling: USA

Rolling Mill: Nucor Bar NE

ASTM E381

Surface: 1 Mid Radius: 1 Center: 2

ASTM E45 Method A (Worst)

Sulfides: T: 1.5 H: 0.5 Alumina: T: 1.5 H: 0.0 Silicates: T: 0.5 H: 0.0 Globular: T: 1.5 H: 0.5

1. All products produced are weld free.
2. Mercury, in any form, has not been used in the production or testing of this material.

ALRO STEEL/METAL



RT07900927

RECEIVED

APR 16 2015

ALRO STEEL PV

Nick Schultz


Nick Schultz

Sales Manager

NDMG-10 January 1, 2012

Page 2 of 5

Figure A-17. 7/8-in. Dia. Hex Coupling Nut, Test Nos. N2B-1 through N2B-6

| | | | | | | | | | | | | |
|--|---------|--|---------|---|--------------|------|------|-------|------|-------|-------|--------|
|  | | Vulcan Threaded Products 10 Cross Creek Trail Pelham, AL 35124 Tel (205) 620-5100 Fax (205) 620-5150 | | <h2 style="text-align: center;">JOB MATERIAL CERTIFICATION</h2> | | | | | | | | |
| Job No: 513030 | | Job Information | | Certified Date: 1/27/17 | | | | | | | | |
| Containers: S12022849 | | | | | | | | | | | | |
| Customer: Portland Bolt & Mfg., Inc. | | | | Ship To: 3441 NW Guam Street Portland, OR 97210 | | | | | | | | |
| Vulcan Part No: ATR B7 7/8x12 | | | | | | | | | | | | |
| Customer Part No: ATR B7 7/8x12 | | | | | | | | | | | | |
| Customer PO No: 29600 | | | | Shipped Qty: 142 pcs | | | | | | | | |
| Order No: 311935 | | | | Line No: 1 | | | | | | | | |
| Note: | | | | | | | | | | | | |
| Applicable Specifications | | | | | | | | | | | | |
| Type | | Specification | | Rev | Amend | | | | | | | |
| | | ASTM F1554 Gd 105 S4 | | 2015 | | | | | | | | |
| Heat Treat | | ASME SA-193/SA-193M B7 | | 2013 | | | | | | | | |
| | | ASTM A193 B7 | | 2016 | | | | | | | | |
| Test Results | | | | | | | | | | | | |
| See following pages for tests | | | | | | | | | | | | |
| Certified Chemical Analysis | | | | | | | | | | | | |
| Heat No: DL1610685802 | | | | | | | | | | | | |
| Origin: USA | | | | | | | | | | | | |
| C | Mn | P | S | Si | Cr | Mo | Ni | V | Cu | Al | Cb | N |
| 0.420 | 0.91 | 0.004 | 0.007 | 0.26 | 0.87 | 0.16 | 0.06 | 0.008 | 0.18 | 0.039 | 0.005 | 0.0100 |
| DI | RR | G.S. | Macro S | Macro R | Macro C | J1 | J2 | J3 | J4 | J5 | J6 | J7 |
| 4.89 | 120.6:1 | 7 | 2 | 2 | 2 | 57 | 57 | 57 | 57 | 57 | 56 | 55 |
| J8 | J9 | J10 | J12 | J14 | J16 | J18 | J20 | J24 | J28 | J32 | | |
| 53 | 52 | 50 | 47 | 46 | 43 | 42 | 41 | 40 | 37 | 35 | | |
| Notes | | | | | | | | | | | | |
| Material was manufactured, tested and inspected in accordance with Vulcan Threaded Products Inc. Quality Assurance Program and Manual Rev. A, dated 8/23/11. Processed material is Quenched and Tempered - Stress Free. No weld repair performed on the material. No Mercury used in the production of this material. Melted and Manufactured in the USA. Document is in accordance with EN 10204 - 3.1B of 2004 (3.1). | | | | | | | | | | | | |

Plex 1/27/17 4:10 PM vulc.mgn Page 1 of 2

19571 7/8 B7/6105
ATR

Figure A-18. 7/8-in. Dia. 30-in. Long Threaded Rod, Test Nos. N2B-1 through N2B-6

NUCOR
FASTENER DIVISION

LOT NO. 383920A **32405** Post Office Box 6100
Saint Joe, Indiana 46785
Telephone 260/337-1600

CUSTOMER NO/NAME 143 CORDOVA BOLT INC
TEST REPORT SERIAL# FB511122 NUCOR ORDER # 16888
TEST REPORT ISSUE DATE 11/03/16 CUST PART #
DATE SHIPPED 7/10/17 CUSTOMER P.O. # 061576
NAME OF LAB SAMPLER: RYAN UNGER, LAB TECHNICIAN
*****CERTIFIED MATERIAL TEST REPORT*****
NUCOR PART NO QUANTITY LOT NO. DESCRIPTION
162296 574 383920A 1-8 X 2 A325T HVY HX
MANUFACTURE DATE 10/26/16 PLAIN ASTM F3125 TY1

A325T
n

--CHEMISTRY MATERIAL GRADE -1037HL
MATERIAL HEAT **CHEMISTRY COMPOSITION (WT% HEAT ANALYSIS) BY MATERIAL SUPPLIER
NUMBER NUMBER C MN P S SI CR NUCOR STEEL - NEBRASKA
RMO31035 NF16103170 .38 .78 .008 .016 .23 .34

--MECHANICAL PROPERTIES IN ACCORDANCE WITH ASTM F3125-15a
SURFACE CORE PROOF LOAD TENSILE STRENGTH
HARDNESS HARDNESS 51500 LBS 0 DEG-WEDGE
(R30N) (RC) (LBS) STRESS (PSI)
N/A 28.7 PASS 89860 148284
N/A 29.9 PASS 90730 149719
N/A 31.9
AVERAGE VALUES FROM TESTS
30.2 90295 149002
PRODUCTION LOT SIZE 2700 PCS

--VISUAL INSPECTION IN ACCORDANCE WITH ASTM F3125-15a 3 PCS. SAMPLED LOT PASSED
HEAT TREATMENT - AUSTENITIZED, OIL QUENCHED & TEMPERED (MIN 800 DEG F)

--DIMENSIONS PER ASME B18.2.6-2010
CHARACTERISTIC #SAMPLES TESTED MINIMUM MAXIMUM
Width Across Corners 4 1.840 1.843
Head Height 4 0.605 0.610
Threads 4 PASS PASS

ALL TESTS ARE IN ACCORDANCE WITH THE LATEST REVISIONS OF THE METHODS PRESCRIBED IN THE APPLICABLE SAE AND ASTM SPECIFICATIONS. THE SAMPLES TESTED CONFORM TO THE SPECIFICATIONS AS DESCRIBED/LISTED ABOVE AND WERE MANUFACTURED FREE OF MERCURY CONTAMINATION. NO HEATS TO WHICH BISMUTH, SELENIUM, TELLURIUM, OR LEAD WAS INTENTIONALLY ADDED HAVE BEEN USED TO PRODUCE THE BOLTS.
THE STEEL WAS MELTED AND MANUFACTURED IN THE U.S.A. AND THE PRODUCT WAS MANUFACTURED AND TESTED IN THE U.S.A. PRODUCT COMPLIES WITH DFARS 252.225-7014. WE CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL SUPPLIER AND OUR TESTING LABORATORY. THIS CERTIFIED MATERIAL TEST REPORT RELATES ONLY TO THE ITEMS LISTED ON THIS DOCUMENT AND MAY NOT BE REPRODUCED EXCEPT IN FULL.

ASME
ACCREDITED

MECHANICAL FASTENER
CERTIFICATE NO. A2LA 0139.01
EXPIRATION DATE 12/31/17

NUCOR FASTENER
A DIVISION OF NUCOR CORPORATION
John W. Ferguson
JOHN W. FERGUSON
QUALITY ASSURANCE SUPERVISOR

Page 1 of 1


32405-1

Figure A-19. 1-in. Dia. 2-in. Long Heavy Hex Head Bolt, Test Nos. N2B-1 through N2B-6

Wecall Inc.

P.O. Box 39 • 64 Penniman Rd. • Orwell, OH 44076
(440) 437-8202 • Fax: (440) 437-8208
Fastener Insignia: 01OH

Record of Conformance

| | | | | | | | |
|--|--|------------------------------------|--------------------------------------|---|--------|-------|--------|
| Sold To: Portland Bolt & Mfg. Co., Inc 3441 NW Guam St. Portland OR 97210 | | | | Shipped To: Portland Bolt & Mfg. 3441 NW Guam St. Portland OR 97210 | | | |
| Customer PO Number 32404/2 | Order Date 20-Sep-17 | Order Quantity 2 | Customer Part Number 55555 | | | | |
| Fastener Type Coupling Nut | Description 1-1/2" Hex x 2-5/8" Long | | | Thread Description 7/8" - 9 UNC 2B RH | | | |
| Fastener Specification ASTM A563 Gr DH | Coating Specification | | | Fastener Lot Number 4142 | | | |
| Raw Material Lot Code 20465-2 | Raw Material Grade ASTM A108 Gr 4140 | | | Heat Number NF14103504 | | | |
| Cold Finish Source Nucor Cold Finish USA | Cold Finish Country | Melt Source Nucor Bar NE | Melt Country USA | | | | |
| Heat Analysis per Material Supplier: | | | | | | | |
| %C | %MN | %P | %S | %SI | %CR | %NI | %MO |
| 0.400% | 0.950% | 0.006% | 0.022% | 0.310% | 0.950% | 0.08% | 0.190% |
| Heat Treatment Process: | | | | | | | |
| Harden @ 1550 F for 2.5 Hrs. | | | | | | | |
| Temper @ 1175 F for 2.5 Hrs. | | | | | | | |
| Test #1 Proof Load | | Test #2 Hardness | | Test #3 | | | |
| Results Pass | | Results Pass | | Results | | | |
| <p>We certify that this data is a true representation of information provided by our material supplier and testing laboratory and that these fasteners were manufactured, sampled, tested and inspected in accordance with the specifications listed.</p> <p>These fasteners were manufactured and tested in the USA, from steel which was melted and manufactured in the USA.</p> | | | | | | | |
|  Paul Doherty Wecall Inc. | | | | | | | |

25-Sep-17

Figure A-20. 1-in. Dia. Heavy Hex Coupling Nut, Test Nos. N2B-1 through N2B-6

NUCOR
FASTENER DIVISION

LOT NO.
3711238

Post Office Box 6100
Saint Joe, Indiana 46785
Telephone 260/337-1600

CUSTOMER NO/NAME
8001 FASTENAL COMPANY-KS

NUCOR ORDER # 978943

TEST REPORT SERIAL# FB408556

CUST PART # 38210

TEST REPORT ISSUE DATE 5/04/16


DATE SHIPPED 8/17/16

CUSTOMER P.O. # 210117217

NAME OF LAB SAMPLER: SANDRA NEUMANN-PLUMMER, LAB TECHNICIAN

*****CERTIFIED MATERIAL TEST REPORT*****

NUCOR PART NO QUANTITY LOT NO. DESCRIPTION
175647 3600 3711238 1-8 GR DH HV H.D.G.
MANUFACTURE DATE 1/07/16 HEX NUT H.D.G./GREEN LUBE



--CHEMISTRY MATERIAL GRADE -1045L

| MATERIAL | HEAT | **CHEMISTRY COMPOSITION (WT% HEAT ANALYSIS) BY MATERIAL SUPPLIER | | | | |
|----------|------------|--|-----|------|------|-----|
| NUMBER | NUMBER | C | MN | P | S | SI |
| RM030412 | DL15105591 | .44 | .64 | .005 | .020 | .20 |

NUCOR STEEL - SOUTH CAROL

--MECHANICAL PROPERTIES IN ACCORDANCE WITH ASTM A563-07a

| SURFACE | CORE | PROOF LOAD | TENSILE STRENGTH | |
|----------|----------|------------|------------------|--------------|
| HARDNESS | HARDNESS | 90900 LBS | DEG-WEDGE | STRESS (PSI) |
| (R50N) | (RC) | | (LBS) | |
| N/A | 26.6 | PASS | N/A | N/A |
| N/A | 27.0 | PASS | N/A | N/A |
| N/A | 27.6 | PASS | N/A | N/A |
| N/A | 28.9 | PASS | N/A | N/A |
| N/A | 26.7 | PASS | N/A | N/A |

AVERAGE VALUES FROM TESTS
27.4

PRODUCTION LOT SIZE 90800 PCS

--VISUAL INSPECTION IN ACCORDANCE WITH ASTM A563-07a 80 PCS. SAMPLED LOT PASSED

--COATING - HOT DIP GALVANIZED TO ASTM F2329-13 - GALVANIZING PERFORMED IN THE U.S.A.

| | | | | | | |
|-------------|------------|-------------|-------------|-------------|-------------|-------------|
| 1. 0.00294 | 2. 0.00311 | 3. 0.00346 | 4. 0.00235 | 5. 0.00218 | 6. 0.00270 | 7. 0.00353 |
| 8. 0.00322 | 9. 0.00406 | 10. 0.00269 | 11. 0.00275 | 12. 0.00315 | 13. 0.00487 | 14. 0.00253 |
| 15. 0.00416 | | | | | | |


AVERAGE THICKNESS FROM 15 TESTS .00318

HEAT TREATMENT - AUSTENITIZED, OIL QUENCHED & TEMPERED (MIN 800 DEG F)

--DIMENSIONS PER ASME B18.2.6-2010

| CHARACTERISTIC | #SAMPLES TESTED | MINIMUM | MAXIMUM |
|----------------------|-----------------|---------|---------|
| Width Across Corners | 8 | 1.824 | 1.844 |
| Thickness | 32 | 0.980 | 1.001 |

ALL TESTS ARE IN ACCORDANCE WITH THE LATEST REVISIONS OF THE METHODS PRESCRIBED IN THE APPLICABLE SAE AND ASTM SPECIFICATIONS. THE SAMPLES TESTED CONFORM TO THE SPECIFICATIONS AS DESCRIBED/LISTED ABOVE AND WERE MANUFACTURED FREE OF MERCURY CONTAMINATION. NO INTENTIONAL ADDITIONS OF BISMUTH, SELENIUM, TELLURIUM, OR LEAD WERE USED IN THE STEEL USED TO PRODUCE THIS PRODUCT. THE STEEL WAS MELTED AND MANUFACTURED IN THE U.S.A. AND THE PRODUCT WAS MANUFACTURED AND TESTED IN THE U.S.A. PRODUCT COMPLIES WITH DFARS 252.225-7014. WE CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL SUPPLIER AND OUR TESTING LABORATORY. THIS CERTIFIED MATERIAL TEST REPORT RELATES ONLY TO THE ITEMS LISTED ON THIS DOCUMENT AND MAY NOT BE REPRODUCED EXCEPT IN FULL.



MECHANICAL FASTENER
CERTIFICATE NO. A2LA 0139.01
EXPIRATION DATE 12/31/17

NUCOR FASTENER
A DIVISION OF NUCOR CORPORATION




JOHN W. FERGUSON
QUALITY ASSURANCE SUPERVISOR

Figure A-21. 1-in. Dia. Heavy Hex Nut, Test Nos. N2B-1 through N2B-6

| | | | | | | | | | | |
|--|------------------------|--|---------|---|--------|-------|-------|--------|------|---------|
|  | | Vulcan Threaded Products 10 Cross Creek Trail Pelham, AL 35124 Tel (205) 620-5100 Fax (205) 620-5150 | | JOB MATERIAL CERTIFICATION | | | | | | |
| Job No: 522717 | | Job Information | | Certified Date: 3/29/17 | | | | | | |
| Containers: S12299838 S12299871 S12299878 | | | | | | | | | | |
| Customer: Conklin and Conklin | | | | Ship To: 34201 Seventh Street Union City, CA 94587 | | | | | | |
| Vulcan Part No: BAR B7 .9144x144 | | | | | | | | | | |
| Customer Part No: RAWSTEEL-910-B | | | | | | | | | | |
| Customer PO No: 018032 | | | | Shipped Qty: 7486 lbs | | | | | | |
| Order No: 312995 | | | | Line No: 1 | | | | | | |
| Note: | | | | | | | | | | |
| Applicable Specifications | | | | | | | | | | |
| Type | Specification | Rev | Amend | Option | | | | | | |
| - | ASTM F1554 Gd 105 S4 | 2015 | | | | | | | | |
| Heat Treat | ASME SA-193/SA-193M B7 | 2013 | | | | | | | | |
| | ASTM A193 B7 | 2016 | | | | | | | | |
| Test Results | | | | | | | | | | |
| See following pages for tests | | | | | | | | | | |
| Certified Chemical Analysis | | | | | | | | | | |
| Heat No: A164782 Lot: 5688 | | | | | | | | | | |
| Origin: USA | | | | | | | | | | |
| C | Mn | P | S | Si | Cr | Mo | Ni | V | Cu | Al |
| 0.420 | 0.87 | 0.010 | 0.012 | 0.25 | 1.01 | 0.21 | 0.13 | 0.004 | 0.21 | 0.038 |
| Cb | Sn | Ti | N | B | Ca | As | Sb | H, ppm | DI | RR |
| 0.001 | 0.009 | 0.001 | 0.0089 | 0.0003 | 0.0005 | 0.005 | 0.004 | 1.2 | 5.90 | 196.9.1 |
| G.S. | Macro S | Macro R | Macro C | J1 | J2 | J3 | J4 | J5 | J6 | J7 |
| 7 | 1 | 1 | 2 | 57 | 57 | 57 | 57 | 57 | 57 | 57 |
| J8 | J9 | J10 | J12 | J14 | J16 | J18 | J20 | J24 | J28 | J32 |
| 57 | 57 | 55 | 51 | 51 | 49 | 48 | 47 | 46 | 44 | 41 |
| Notes | | | | | | | | | | |
| Material was manufactured, tested and inspected in accordance with Vulcan Threaded Products Inc. Quality Assurance Program and Manual Rev. A, dated 8/23/11. Processed material is Quenched and Tempered - Stress Free. No weld repair performed on the material. No Mercury used in the production of this material. Melted and Manufactured in the USA. Document is in accordance with EN 10204 - 3.1B of 2004 (3.1). | | | | | | | | | | |

19572 1" B7 / G105 ATR

Plex 3/29/17 1:26 PM vulc.mgr Page 1 of 2

PORTLAND BOLT
PO 31961
INV 73947
100 1" X 144" B7 ATR, BLK 10F2
AUGUST 21, 2017

APR 25 2017

Figure A-22. 1-in. Dia. 24-in. Long Threaded Rod, Test Nos. N2B-1 through N2B-6

STAMPING THE FUTURE
WROUGHT WASHER MFG., INC.



September 6, 2017

Certification of Compliance

003280
FASTENAL COMPANY PURCHASING
P.O. BOX 978
WINONA, MN 55987

Wrought Washer
Ord/Lot Number
304915

HT ORDER 303714

| Heat Number | Chemical Analysis | | | | | Date Shipped | Quantity Shipped |
|-----------------------|-------------------------------|-------|-------|-------|-------|--------------|------------------|
| | C | Mn | P | S | Si | | |
| 276190 | 0.330 | 0.840 | 0.008 | 0.005 | 0.243 | | |
| Purchase Order Number | Part Description | | | | | Date Shipped | |
| 110246277 | 1" F436 S MARK HDG 0156034 | | | | | 09/06/2017 | |

We hereby certify that the subject parts conform to the requirements of the applicable specification indicated for the subject parts and are in complete conformance to F436-11. We hereby certify that the subject parts were hardened to RC 26-45. We hereby certify that the subject parts were hot dip galvanized in accordance with specification ASTM A153 CLASS D and ASTM F2329.

We hereby certify that all statutory requirements as to American Production and Labor Standards and all conditions of purchase applicable to the transaction have been complied with and that the subject parts were melted and manufactured in the U.S.A. No weld repairs were made to the material.

Truly yours,
Wrought Washer Mfg., Inc.

Paul Schaefer
Q.C. Manager

Sworn and subscribed before me on September 6, 2017
My commission expires April 24, 2021



(032) S MARK, HT, HDG, F436
WW INTERNAL USE : 64814602/008/017315/59500

1901 CHICORY RD. • MOUNT PLEASANT, WI 53403 • PHONE (262) 554-9550 • FAX (262) 554-9584
VISIT OUR WEBSITE: www.wroughtwasher.com

Figure A-23. 1-in. Dia. Hardened Flat Washer, Test Nos. N2B-1 through N2B-6

STAMPING THE FUTURE
WROUGHT WASHER MFG., INC.



August 30, 2017

Certification of Compliance

003280
FASTENAL COMPANY PURCHASING
P.O. BOX 978
WINONA, MN 55987

Wrought Washer
Ordr/Lot Number
304151

HT ORDER 302984

| Heat Number | Chemical Analysis | | | | | Si |
|-------------|-------------------|-------|-------|-------|-------|----|
| | C | Mn | P | S | | |
| 274703 | 0.340 | 0.830 | 0.008 | 0.002 | 0.227 | |

| Purchase Order Number | Part Description | Date Shipped | Quantity Shipped |
|-----------------------|--------------------------------|--------------|------------------|
| 110246277 | 7/8 F436 S MARK HDG 0156031 | 08/30/2017 | 11,000 |

We hereby certify that the subject parts conform to the requirements of the applicable specification indicated for the subject parts and are in complete conformance to F436-11. We hereby certify that the subject parts were hardened to RC 26-45. We hereby certify that the subject parts were hot dip galvanized in accordance with specification ASTM A153 CLASS D and ASTM F2329.

We hereby certify that all statutory requirements as to American Production and Labor Standards and all conditions of purchase applicable to the transaction have been complied with and that the subject parts were melted and manufactured in the U.S.A. No weld repairs were made to the material.

Truly yours,
Wrought Washer Mfg., Inc.

Paul Schaefer
Q.C. Manager

Sworn and subscribed before me on August 30, 2017
My commission expires April 24, 2021



(032) S MARK, HT, HDG, F436
WW INTERNAL USE : 64814601/007/017305/59091

1901 CHICORY RD. • MOUNT PLEASANT, WI 53403 • PHONE (262) 554-9550 • FAX (262) 554-9584
VISIT OUR WEBSITE: www.wroughtwasher.com

Figure A-24. 7/8-in. Dia. Hardened Flat Washer, Test Nos. N2B-1 through N2B-6

STAMPING THE FUTURE
WROUGHT WASHER MFG., INC.



July 12, 2017

Certification of Compliance

003280
FASTENAL COMPANY PURCHASING
P.O. BOX 978
WINONA, MN 55987

Wrought Washer
Ord/Lot Number
303708

HT ORDER 302794

Heat Number
273699

| Chemical Analysis | | | | |
|-------------------|-------|-------|-------|-------|
| C | Mn | P | S | Si |
| 0.520 | 0.650 | 0.009 | 0.002 | 0.026 |

Purchase
Order Number
110242728

Part Description
3/4 F436 S MARK HDG
0156028 PO 110242728

Date
Shipped
07/11/2017

Quantity
Shipped
10,200

We hereby certify that the subject parts conform to the requirements of the applicable specification indicated for the subject parts and are in complete conformance to F436-11. We hereby certify that the subject parts were hardened to RC 26-45. We hereby certify that the subject parts were hot dip galvanized in accordance with specification ASTM A153 CLASS D and ASTM F2329.

We hereby certify that all statutory requirements as to American Production and Labor Standards and all conditions of purchase applicable to the transaction have been complied with and that the subject parts were melted and manufactured in the U.S.A. No weld repairs were made to the material.

Truly yours,
Wrought Washer Mfg., Inc.

Paul Schaefer
Q.C. Manager


Sworn and subscribed before me on July 12, 2017
My commission expires April 24, 2021



(032) S MARK, HT, HDG, F436
WW INTERNAL USE : 64693002/004/017295/59089

1901 CHICORY RD. • MOUNT PLEASANT, WI 53403 • PHONE (262) 554-9550 • FAX (262) 554-9584
VISIT OUR WEBSITE: www.wroughtwasher.com

Figure A-25. 3/4-in. Dia. Hardened Flat Washer, Test Nos. N2B-1 through N2B-6



US-ML-MIDLOTHIAN
300 WARD ROAD
MIDLOTHIAN, TX 76065
USA

CERTIFIED MATERIAL TEST REPORT

Page 1/1

| | | | | | | |
|--|--|--|--|-------------------|-----------------------------------|-----------------------------|
| CUSTOMER SHIP TO NEBCO INC STEEL DIVISION HAVELOCK, NE 68529 USA | | CUSTOMER BILL TO CONCRETE INDUSTRIES INC LINCOLN, NE 68529-0529 USA | | GRADE 60 (420) | SHAPE / SIZE Rebar / #4 (13MM) | DOCUMENT ID: 0000000000 |
| SALES ORDER 4767685/000010 | | CUSTOMER MATERIAL N° | | LENGTH 60'00" | WEIGHT 60,120 LB | HEAT / BATCH 58028860/02 |
| SPECIFICATION / DATE or REVISION ASTM A615/A615M-15 E1 | | | | | | |

| | | |
|--|-----------------------------------|--------------------|
| CUSTOMER PURCHASE ORDER NUMBER 123815 | BILL OF LADING 1327-0000228798 | DATE 03/16/2017 |
|--|-----------------------------------|--------------------|

| | | | | | | | | | | | | |
|----------------------|---------|--------|--------|---------|---------|---------|---------|---------|---------|--------|---------|---------|
| CHEMICAL COMPOSITION | | | | | | | | | | | | |
| C % | Mn % | P % | S % | Si % | Cu % | Ni % | Cr % | Mo % | Sn % | V % | Nb % | Al % |
| 0.43 | 0.89 | 0.013 | 0.040 | 0.21 | 0.27 | 0.10 | 0.13 | 0.018 | 0.006 | 0.019 | 0.011 | 0.003 |


| | | | | | | | | | | | | |
|----------------------|--|--|--|--|--|--|--|--|--|--|--|--|
| CHEMICAL COMPOSITION | | | | | | | | | | | | |
| CEq _{A706} | | | | | | | | | | | | |
| 0.60 | | | | | | | | | | | | |

| | | | | | |
|-----------------------|-----------|------------|------------|-------------|-----------|
| MECHANICAL PROPERTIES | | | | | |
| YS PSI | YS MPa | UTS PSI | UTS MPa | G/L Inch | G/L mm |
| 68350 | 471 | 108860 | 751 | 8.000 | 200.0 |

| | |
|-----------------------|----------|
| MECHANICAL PROPERTIES | |
| Elong. | BendTest |
| 14.20 | OK |


COMMENTS / NOTES

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.



BHASKAR YALAMANCHILI
QUALITY DIRECTOR

Phone: (409) 769-1014 Email: Bhaskar.Yalamanchili@gerdau.com



TOM HARRINGTON
QUALITY ASSURANCE MGR.

Phone: 972-779-1872 Email: Tommy.Harrington@gerdau.com

Figure A-26. No. 4 Rebar Mill Certification, Test Nos. N2B-1 through N2B-6

EVRAZ

ROCKY MOUNTAIN STEEL
A DIVISION OF EVRAZ INC. NA

2100 S. Freeway
Pueblo, CO 81004 USA

MATERIAL TEST REPORT

Date Printed: 09-SEP-16

| | | |
|-------------------------|-----------------------------------|-------------------------------------|
| Date Shipped: 09-SEP-16 | Product: BAR #3 (3/8") | Specification: ASTM A706/A615 Gr 60 |
| FWIP: 52815366 | Customer: CONCRETE INDUSTRIES INC | Cust. PO: 121420 |
| | P O BOX 29529 | |
| | LINCOLN, NE 68529 | |

| Heat Number | CHEMICAL ANALYSIS (In Weight %, uncertainty of measurement 0.005%) | | | | | | | | | | | | | | | (Heat cast 07/25/16) | |
|-------------|--|------|-------|-------|------|------|------|------|-------|-------|-------|--------|-------|-------|--------|----------------------|--|
| | C | Mn | P | S | Si | Cu | Ni | Cr | Mo | Al | V | B | Cb | Sn | N | Ti | |
| 587796 | 0.28 | 1.22 | 0.014 | 0.023 | 0.21 | 0.25 | 0.09 | 0.21 | 0.019 | 0.003 | 0.037 | 0.0003 | 0.000 | 0.010 | 0.0089 | 0.001 | |
| | Carbon Equivalent = 0.511 | | | | | | | | | | | | | | | | |

| Heat Number | MECHANICAL PROPERTIES | | | | | (Tensiles test date 08/26/16) | | Bend | Wt/ft |
|-------------|-----------------------|-------------|----------------|----------------|---------------|-------------------------------|----|-------|-------|
| | Sample No. | Yield (Psi) | Ultimate (Psi) | Elongation (%) | Reduction (%) | | | | |
| 587796 | 01 | 68469 | 103770 | 15.2 | | | OK | 0.363 | |
| | | (MPa) 472.1 | 715.5 | | | | | | |
| 587796 | 02 | 68592 | 101150 | 14.2 | | | OK | 0.365 | |
| | | (MPa) 472.9 | 697.4 | | | | | | |

All melting and manufacturing processes of the material subject to this test certificate occurred in the United States of America.

ERMS also certifies this material to be free from Mercury contamination.

This material has been produced, tested and conforms to the requirements of the applicable specifications. We hereby certify that the above test results represent those contained in the records of the Company.

Valoree Varick

Valoree Varick
General Supervisor of Quality

Figure A-27. No. 3 Rebar Mill Certification, Test Nos. N2B-1 through N2B-6

SOLD ADELPHIA METALS I LLC
TO: 411 MAIN ST E
NEW PRAGUE, MN 56071-

NUCOR
NUCOR STEEL KANKAKEE, INC.

CERTIFIED MILL TEST REPORT

Page: 2

SHIP ADELPHIA METALS - TRK
TO: 411 MAIN STREET EAST
NEW PRAGUE, MN 56071-

Ship from:
MTR #: 0000024491
Nucor Steel Kankakee, Inc.
One Nucor Way
Bourbonnais, IL 60914
815-937-3131

Date: 25-Jul-2014
B.L. Number: 484645
Load Number: 251220

Material Safety Data Sheets are available at www.nucorbar.com or by contacting your inside sales representative.

NBMG-06 January 1, 2012


| LOT # HEAT # | DESCRIPTION | PHYSICAL TESTS | | | | | CHEMICAL TESTS | | | | | | | | | |
|--------------------------------------|---|------------------|-------------------|------------------|------|---------------|----------------|-------------|--------------|--------------|-------------|----------|------|--|--|--|
| | | YIELD P.S.I. | TENSILE P.S.I. | ELONG % IN 8" | BEND | WT% DEF | C Ni | Mn Cr | P Mo | S V | Si Cb | Cu Sn | C.E. | | | |
| PO# => KN1410445301 KN14104453 | 811627 Nucor Steel - Kankakee Inc 16/#5 Rebar 40' A706M(A706) WELDABLE ASTM A706/A706M-09b GR60 [420] A ASHTO M322 TEN/YD = 1.44 Melted 07/22/14 Rolled 07/24/14 | 67,451 465MPa | 97,059 669MPa | 14.6% | OK | -3.9% .044 | .26 .20 | 1.20 .27 | .020 .069 | .036 .044 | .22 .001 | .36 | .50 | | | |

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.
1.) Weld repair was not performed on this material.
2.) Melted and Manufactured in the United States.
3.) Mercury, Radium, or Alpha source materials in any form have not been used in the production of this material.

QUALITY
ASSURANCE: Matt Luymes

Matt Luymes

Figure A-28. No. 8 Rebar Mill Certification, Test Nos. N2B-1 through N2B-6



GERDAU
 US-ML-BEAUMONT
 100 OLD HIGHWAY 90 WEST
 VIDOR, TX 77662
 USA

CERTIFIED MATERIAL TEST REPORT

| | | | | |
|---|--|---|-----------------------------------|-----------------------------|
| CUSTOMER SHIP TO CONCRETE INDUSTRIES INC 6300 CORNHUSKER HWY LINCOLN, NE 68507-3112 USA | CUSTOMER BILL TO CONCRETE INDUSTRIES INC LINCOLN, NE 68529-0529 USA | GRADE 60/A706-60 | SHAPE / SIZE Rebar / #4 (13MM) | DOCUMENT ID: 0000000000 |
| SALES ORDER 5290798/000010 | | LENGTH 0 | WEIGHT 47,498 LB | HEAT / BATCH 53145629/02 |
| CUSTOMER MATERIAL N° | | SPECIFICATION / DATE or REVISION ASTM A615/A615M-15 E1 ASTM A706/A706M-15 | | |
| CUSTOMER PURCHASE ORDER NUMBER 126067 | BILL OF LADING 4785-00000000192 | DATE 06/30/2017 | | |

| | | | | | | | | | | | | |
|----------------------|---------|--------|--------|---------|---------|---------|---------|---------|---------|--------|---------------------|--|
| CHEMICAL COMPOSITION | | | | | | | | | | | | |
| C % | Mn % | P % | S % | Si % | Cu % | Ni % | Cr % | Mo % | Sn % | V % | CEq _{A706} | |
| 0.27 | 1.11 | 0.022 | 0.010 | 0.21 | 0.31 | 0.12 | 0.22 | 0.043 | 0.012 | 0.047 | 0.49 | |


| | | | | | |
|-----------------------|-----------|------------|------------|-------------|-------------|
| MECHANICAL PROPERTIES | | | | | |
| YS PSI | YS MPa | UTS PSI | UTS MPa | G/L Inch | Elong. % |
| 67685 | 467 | 101935 | 703 | 8.000 | 14.20 |

| | |
|-----------------------|------|
| MECHANICAL PROPERTIES | |
| Bend Test | T/Y |
| OK | 1.51 |


| | | | |
|---------------------------|-----------------|-----------------|-------------------|
| GEOMETRIC CHARACTERISTICS | | | |
| %Light | Def Hgt Inch | Def Gap Inch | Def Space Inch |
| -1.30 | 0.023 | 0.100 | 0.323 |

COMMENTS / NOTES

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.



BHASKAR YALAMANCHILI
 QUALITY DIRECTOR
 Phone: (409) 769-1014 Email: Bhaskar.Yalamanchili@gerdau.com



LEONARDO RADICCHI
 QUALITY ASSURANCE MGR.
 Phone: 409-769-1086 Email: Leonardo.Cunha@gerdau.com

Figure A-29. No. 4 Rebar Mill Certification, Test Nos. N2B-1 through N2B-6

Appendix B. Bogie Test Results




Figure B-1. Test No. N2B-1 Results (SLICE-1)




Figure B-2. Test No. N2B-1 Results (SLICE-2)




Figure B-3. Test no. N2B-2 Results (SLICE-1)




Figure B-4. Test No. N2B-2 Results (SLICE-2)




Figure B-5. Test No. N2B-3 Results (SLICE-1)




Figure B-6. Test No. N2B-3 Results (SLICE-2)




Figure B-7. Test No. N2B-4 Results (SLICE-1)




Figure B-8. Test No. N2B-4 Results (SLICE-2)




Figure B-9. Test No. N2B-5 Results (SLICE-1)




Figure B-10. Test No. N2B-5 Results (SLICE-2)




Figure B-11. Test No. N2B-6 Results (SLICE-1)




Figure B-12. Test No. N2B-6 Results (SLICE-2)

Appendix C. Full-Scale Test Material Specifications

Table C-1. Bill of Materials, Test No. N2BR-1

| Item No. | Description | Material Specification | Reference No. |
|----------|---|---|---|
| a1 | 6'-3" 12-gauge W-Beam MGS Section | AASHTO M180 | HTCode#9760 H#31631800 |
| a2 | 12'-6" 12-gauge W-Beam MGS Section | AASHTO M180 | H#9411949 |
| a3 | 12'-6" 12-gauge W-Beam MGS End Section | AASHTO M180 | HTCode#1207 H#C84187 |
| b1 | 72" Long Foundation Tube | ASTM A500 Gr. B | HTCode#811T08220 |
| b2 | BCT Timber Post - MGS Height | SYP Grade No. 1 or better (No knots within 18" of ground on tension face) | Charge#24096 |
| b3 | W6x8.5 or W6x9, 72" Long Steel Post | ASTM A992 Gr. 50 | H#55048942 |
| b4 | 6"x12"x14 1/4" Timber Blockout for Steel Posts | SYP Grade No.1 or better | Ch#23888 LIGHT BLUE, White Paint Post#27, Post#25 |
| b5 | 2 3/4"x1"x1/4" Post Standoff | ASTM A36 | H#64055041/02 |
| b6 | S3x5.7, 39" Long Steel Post | ASTM A992 Gr. 50 | H#59076269/02 |
| c1 | 10"x7"x1/2" Steel Plate | ASTM A572 Gr. 50 | H#A7D898 |
| c2 | 10"x2 3/4"x1/4" Plate Washer | ASTM A36 | H#17126641 |
| c3 | HSS4"x4"x3/8", 6 5/8" Long Square Tube | ASTM A500 Gr. B | H#W46930 |
| c4 | 3 1/2"x1"x1/8" | ASTM A36 | H#62213 |
| c5 | C7x9.8, 225" Long C-Channel | ASTM A36 | H#52080955/02 |
| c6 | 6 5/8"x2"x1/8" Shim Plate | ASTM A36 | H#1164312 |
| d1 | #4 Bar, 896 1/2" Long | ASTM A615 Gr. 60 | H#5716646 |
| d2 | #4 Bar, 32" Long | ASTM A615 Gr. 60 | H#57166635 |
| d3 | #4 Bar, 16" Long | ASTM A615 Gr. 60 | H#17-00688 |
| d4 | #4 Bar, 18" Long | ASTM A706 Gr. 60 | H#594643 |
| e1 | 5/8"-11 UNC, 14"] Long Guardrail Bolt and Nut | Bolt - ASTM A307 Gr. A Nut - ASTM A563A | H#100886654 |
| e2 | 5/8"-11 UNC, 10" Long Guardrail Bolt and Nut | Bolt - ASTM A307 Gr. A Nut - ASTM A563A | H#DL16102715 |
| e3 | 5/8"-11 UNC, 1 1/4" Long Guardrail Bolt and Nut | Bolt - ASTM A307 Gr. A Nut - ASTM A563A | Bolts: H#20455760 Nuts: 20479830 |

Table C-2. Bill of Materials, Test No. N2BR-1, Cont.

| Item No. | Description | Material Specification | Reference No. |
|----------|--|--|--|
| e4 | 5/8"-11 UNC, 5" Long Heavy Hex Head Bolt and Nut | Bolt - ASTM F3125 Gr. A325 Type 1 Nut - ASTM A563DH | Bolt: H#CR10456700-41 Nut: H#75068952 L#27160 |
| e5 | 7/8"-9 UNC, 24" Long Threaded Rod | ASTM A449 or Equivalent COC says A449 | Job#542344 |
| e6 | 7/8"-9 UNC, 2" Long Heavy Hex Head Bolt | ASTM A449 or Equivalent ASTM A325 | P#0129028BO C#180083637 H#331313371 |
| e7 | 7/8" Dia. Heavy Hex Coupling Nut | ASTM A563DH | H#NF100884291 |
| e8 | 7/8" Dia. Heavy Hex Nut | ASTM A563DH or Equivalent | H#6214369204 |
| e9 | 1" Dia. Hex Nut | ASTM A563A | P#36119 C#110207371 H#15306714-3 |
| e10 | 5/8"-11 UNC, 10" Long Hex Head Bolt and Nut | Bolt - ASTM A307 Gr. A or Equivalent, Nut - ASTM A563A or Equivalent | Bolts: H#DL16102715 Nuts: P#36713 C#210101523 |
| e11 | 7/8"-9 UNC, 8" Long Hex Head Bolt and Nut | Bolt - ASTM A307 Gr. A or Equivalent, Nut - ASTM A563A or Equivalent | FASTENAL COC |
| e12 | 5/8"-11 UNC, 1 1/2" Long Hex Head Bolt and Nut | Bolt - ASTM A307 Gr. A or Equivalent, Nut - ASTM A563A or Equivalent | Bolts: H#816070039 Nuts: P#36713 C#210101523 |
| e13 | 5/16"-18 UNC, 1 1/4" Long Hex Head Bolt and Nut | Bolt - ASTM A307 Gr. A or Equivalent, Nut - ASTM A563A or Equivalent | Bolts: P#91830 C#120263056 H#G4604921 Nut: P#1136703 C#120200536 H#183425 |
| e14 | 16D Double Head Nail | - | McMaster-Carr PO E000357170 |
| f1 | 1 3/4"x1 3/4"x1/8" Square Washer | 11GA A1011 -CS-TYB TEMP HS | H#B707141 |
| f2 | 7/8" Dia. Plain Round Washer | ASTM F844 | FASTENAL COC |

Table C-3. Bill of Materials, Test No. N2BR-1, Cont.

| Item No. | Description | Material Specification | Reference No. |
|----------|--|--|---|
| f3 | 5/8" Dia. Plain Round Washer | ASTM F844 | N/A |
| f4 | 7/8" Dia. Hardened Flat Washer | ASTM F436 | H#173583 |
| f5 | 1" Dia. Plain Round Washer | ASTM F844 | N/A |
| g1 | BCT Anchor Cable End Swaged Fitting | Fitting - ASTM A576 Gr. 1035 Stud - ASTM F568 Class C | CGLP Order# 256284 |
| g2 | 3/4" Dia. 6x19, 24 1/2" Long IWRC IPS Wire Rope | IPS | CGLP Order# 256284 |
| g3 | 115-HT Mechanical Splice - 3/4" Dia. | As Supplied | N/A |
| g4 | Crosby Heavy Duty HT - 3/4" Dia. Cable Thimble | Stock No. 1037773 | N/A |
| g5 | Crosby G2130 or S2130 Bolt Type Shackle - 1 1/4" Dia. w/ thin head bolt, nut, and cotter pin, Grade A, Class 3 | Stock Nos. 1019597 and 1019604 - As Supplied | N/A |
| g6 | Chicago Hardware Drop Forged Heavy Duty Eye Nut - Drilled and Tapped 1 1/2" Dia. - UNC 6 | Stock No. 107 - As Supplied | N/A |
| g7 | TLL-50K-PTB Load Cell | As Supplied | N/A |
| g8 | 8"x8"x5/8" Anchor Bearing Plate | ASTM A36 | H#4181496 |
| g9 | 2 3/8" O.D. x 6" Long BCT Post Sleeve | ASTM A53 Gr. B Schedule 40 | H#A79999 |
| h1 | Anchor Bracket Assembly | ASTM A36 | South: H#4153095 North: R#17-282 |
| h2 | Ground Strut Assembly | ASTM A36 | H#195070 |
| | Deck Concrete | Min. f'c = 6,000 psi NE Mix 47BD | Ticket#1222277, 1222285 PC#485030000 |
| il | Grade Beam Concrete | Min f'c = 4,000 psi | Ticket#4202504 PC#470031PF |

GREGORY HIGHWAY PRODUCTS, INC.
4100 13th St. SW
Canton, Ohio 44710

Customer: GUARDRAIL SYSTEMS
8000 SERUM AVE.
RALSTON, NE, 68127-4213

Test Report
Ship Date: 10/12/2016
Customer P O: EMAIL 8-21-2016
Shipped to: GUARDRAIL SYSTEMS
Project: STOCK
GHP Order No.: 9386AJ


| HT # code | Heat # | C. | MN. | P. | S. | SI. | Tensile | Yield | Elong. | Quantity | Class | Type | Description |
|-----------|----------|------|------|-------|-------|------|---------|-------|--------|----------|-------|------|--|
| 9760 | 31631800 | 0.2 | 0.85 | 0.01 | 0.001 | 0.04 | 79600 | 62100 | 25 | 6 | A | 1 | 12GA 15FT 7.5IN WB T13F T1 3IN |
| 9761 | 4152233 | 0.22 | 0.74 | 0.011 | 0.006 | 0.01 | 79057 | 59958 | 25.33 | 6 | A | 1 | 12 GA 12FT 8IN WB T1 FLEAT-SKT COMBO PAN |
| 9760 | 31631800 | 0.2 | 0.85 | 0.01 | 0.001 | 0.04 | 79600 | 62100 | 25 | 5 | A | 1 | 12GA 25FT 0IN 3FT 1 1/2IN WB T1 |
| 9692 | 31629790 | 0.2 | 0.82 | 0.012 | 0.002 | 0.04 | 81442 | 58556 | 17.56 | 1 | A | 1 | 12GA 25FT 0IN 3FT 1 1/2IN WB T1 |
| 9760 | 31631800 | 0.2 | 0.85 | 0.01 | 0.001 | 0.04 | 79600 | 62100 | 25 | 40 | A | 1 | 12GA 6FT 3IN WB T1 HS@ 3FT 1.5IN |

R#17-402 QTY 2

For Georgia MGS though only one will be used there.

February 2017 SMT

Bolts comply with ASTM A-307 specifications and are galvanized in accordance with ASTM A-153, unless otherwise stated
Nuts comply with ASTM A-563 specifications and are galvanized in accordance with ASTM A-153, unless otherwise stated
All other galvanized material conforms with ASTM-123 & ASTM-653
All Galvanizing has occurred in the United States
All steel used in the manufacture is of Domestic Origin, "Made and Melted in the United States"
All Steel used meets Title 23CFR 635.410 - Buy America
All Guardrail and Terminal Sections meets AASHTO M-180, All structural steel meets AASHTO M-183 & M270
All Bolts and Nuts are of Domestic Origin
All material fabricated in accordance with Nebraska & Iowa Department of Transportation
All controlled oxidized/corrosion resistant Guardrail and terminal sections meet ASTM A606, Type 4

By: 
Andrew Artar, VP of Sales & Marketing
Gregory Highway Products, Inc.


STATE OF OHIO: COUNTY OF STARK
Sworn to and subscribed before me, a Notary Public, by
Andrew Artar this 13 day of October, 2016

Notary Public, State of Ohio

Figure C-1. 6-ft 3-in. 12-Gauge W-Beam MGS Section Material Certification, Test No. N2BR-1


GREGORY HIGHWAY PRODUCTS, INC.
4100 13th St. SW
Canton, Ohio 44710

| | | | |
|-----------|--------------------------------|----------------|--------------------------------|
| Customer: | UNIVERSITY OF NEBRASKA-LINCOLN | Test Report | |
| | 401 CANFIELD ADMIN BLDG | Ship Date: | 7/9/2015 |
| | P O BOX 880439 | Customer P.O.: | 4500274709/ 07/07/2015 |
| | LINCOLN, NE 68588-0439 | Shipped to: | UNIVERSITY OF NEBRASKA-LINCOLN |
| | | Project: | TESTING COIL |
| | | GHP Order No.: | 183305 |

| HT # code | Heat # | C. | Mn. | P. | S. | Si. | Tensile | Yield | Elong. | Quantity | Class | Type | Description |
|-----------|---------|------|------|------|-------|------|---------|-------|--------|----------|-------|------|----------------------------------|
| 8534 | 9411949 | 0.21 | 0.75 | 0.01 | 0.006 | 0.01 | 75774 | 56527 | 27.15 | 10 | A | 2 | 12GA 25FT WB T2 MGS ANCHOR PANEL |
| 8534 | 9411949 | 0.21 | 0.75 | 0.01 | 0.006 | 0.01 | 75774 | 56527 | 27.15 | 100 | A | 2 | 12GA 12FT6IN/3FT1 1/2IN WB T2 |
| 8534 | 9411949 | 0.21 | 0.75 | 0.01 | 0.006 | 0.01 | 75774 | 56527 | 27.15 | 20 | A | 2 | 12GA 25FT0IN 3FT1 1/2IN WB T2 |

Bolts comply with ASTM A-307 specifications and are galvanized in accordance with ASTM A-153, unless otherwise stated.
Nuts comply with ASTM A-563 specifications and are galvanized in accordance with ASTM A-153, unless otherwise stated.
All other galvanized material conforms with ASTM-123 & ASTM-653
All Galvanizing has occurred in the United States
All steel used in the manufacture is of Domestic Origin, "Made and Melted in the United States"
All Steel used meets Title 23CFR 635.410 - Buy America
All Guardrail and Terminal Sections meets AASHTO M-180, All structural steel meets AASHTO M-183 & M270
All Bolts and Nuts are of Domestic Origin
All material fabricated in accordance with Nebraska Department of Transportation
All controlled oxidized/corrosion resistant Guardrail and terminal sections meet ASTM A606, Type 4.

By: 
Andrew Artar, VP of Sales & Marketing
Gregory Highway Products, Inc.

STATE OF OHIO: COUNTY OF STARK
Sworn to and subscribed before me a Notary Public, by
Andrew Artar this 17 day of July, 2015.

Notary Public, State of Ohio

DAWN R. BATTON
NOTARY PUBLIC
STATE OF OHIO
Comm. Expires
March 03, 2018
Recorded in
Portage County


Figure C-2. 12-ft 6-in. 12-Gauge W-Beam MGS Section Material Certification, Test No. N2BR-1

GREGORY HIGHWAY PRODUCTS, INC.
4100 13th St. SW
Canton, Ohio 44710


| | | |
|--|---|--|
| Customer: UNIVERSITY OF NEBRASKA-LINCOLN 401 CANFIELD ADMIN BLDG P O BOX 880439 LINCOLN, NE 68588-0439 | Test Report Ship Date: 1/26/2018 Customer P O: 36263 Shipped to: UNIVERSITY OF NEBRASKA-LINCOLN Project: GHP Order No.: 319AA | |
|--|---|--|

| HT # code | Heat # | C. | MN. | P. | S. | SI. | Tensile | Yield | Elong. | Quantity | Class | Type | Description |
|-----------|--------|-----|------|-------|-------|------|---------|-------|--------|----------|-------|------|------------------------------|
| 1207 | C85187 | 0.2 | 0.48 | 0.008 | 0.003 | 0.03 | 80433 | 59371 | 16.35 | 150 | A | 2 | 12GA 12FT6IN3FT1 1/2IN WB T2 |

Bolts comply with ASTM A-307 specifications and are galvanized in accordance with ASTM A-153, unless otherwise stated.
 Nuts comply with ASTM A-563 specifications and are galvanized in accordance with ASTM A-153, unless otherwise stated.
 All other galvanized material conforms with ASTM-123 & ASTM-653.
 All Galvanizing has occurred in the United States
 All steel used in the manufacture is of Domestic Origin, "Made and Melted in the United States"
 All Steel used meets Title 23CFR 635.410 - Buy America
 All Guardrail and Terminal Sections meets AASHTO M-180, All structural steel meets AASHTO M-183 & M270
 All Bolts and Nuts are of Domestic Origin
 All material fabricated in accordance with Nebraska Department of Transportation
 All controlled oxidized/corrosion resistant Guardrail and terminal sections meet ASTM A606, Type 4.

By: 


Jeffery Grover, VP of Highway Products Sales & Marketing
Gregory Highway Products, Inc.



James P Dehnke
Notary Public - State of Ohio
My Commission Expires
October 19, 2019

STATE OF OHIO: COUNTY OF STARK

Sworn to and subscribed before me, a Notary Public, by
Jeffery Grover this 29 day of January, 2018



Notary Public, State of Ohio

Figure C-3. 12-ft 6-in. 12-Gauge W-Beam MGS End Section Material Certification, Test No. N2BR-1

GREGORY HIGHWAY PRODUCTS, INC.
4100 13th St. SW
Canton, Ohio 44710

MIDWEST MACHINERY & SUPPLY CO.
P. O. BOX 703

MILFORD, NE 68405

Test Report
Ship Date: 10/26/2017
Customer P.O.: 3501
Shipped to: MIDWEST MACHINERY & SUPPLY CO.
Project: STOCK
GHP Order No: 7044AA

| HT # code | LOT# | C. | Mn. | P. | S. | SL | Tensile | Yield | Elong. | Quantity | Class | Type | Description |
|-----------|------|------|------|-------|-------|-------|---------|-------|--------|----------|-------|------|---|
| 616137 | | 0.21 | 0.93 | 0.011 | 0.003 | 0.02 | 73148 | 56210 | 32 | 15 | | 2 | 3/16IN X 6IN X 8IN X 5FT IN TUBE SLEEVE |
| 811708220 | | 0.22 | 0.81 | 0.013 | 0.006 | 0.005 | 71412 | 56323 | 35 | 10 | | 2 | 3/16IN X 6IN X 8IN X 5FT IN TUBE SLEEVE |
| 214482 | | 0.04 | 0.83 | 0.014 | 0.005 | 0.02 | 75275 | 68023 | 28.6 | 25 | | | 10GA MGS TB TRAN APPROACH END-RIGHT |
| 214143 | | 0.04 | 0.81 | 0.015 | 0.006 | 0.02 | 75565 | 69618 | 29.7 | 18 | | | 10GA MGS TB TRAN DEPARTURE END-LEFT |

All Galvanizing has occurred in the United States
All steel used in the manufacture is of Domestic Origin, "Made and Melted in the United States"
All Steel used meets Title 29CFR 635.410 - Buy America
All Guardrail and Terminal Sections meets AASHTO M-180, All structural steel meets AASHTO M-183 & M270
All Bolts and Nuts are of Domestic Origin
All material fabricated in accordance with Nebraska Department of Transportation
All controlled oxidized/corrosion resistant Guardrail and terminal sections meet ASTM A606, Type 4.

By: _____

STATE OF OHIO: COUNTY OF STARK
Sworn to and subscribed before me, a Notary Public, by
Andrew Artar this 31 day of October 2017

Notary Public, State of Ohio

James P. Dehnke
Notary Public, State of Ohio
My Commission Expires 10-19-2019

Figure C-4. 72-in. Long Foundation Tube Material Certification, Test No. N2BR-1



CNWP

CENTRAL NEBRASKA WOOD PRESERVERS

1098 East Maple St
Sutton, NE 68979
Phone: 402.773.4319
Email: nick@nebraskawood.com

CERTIFICATE OF COMPLIANCE

Shipped To: Midwest Machinery and Supply
BOL# 10057336
Customer PO# 3460
Preservative: CCA - C 0.60D pcf AWP A UC4B

| Part # | Physical Description | # of Pieces | Charge # | Tested Retention |
|-------------|-----------------------|-------------|----------|------------------|
| GR6806.5CRT | 6x8-6.5' CRT | 105 | 24080 | .603 |
| GR61222BLK | 6x12-22" Block | 56 | 24003 | .700 |
| GR6822CH | 6x8-22" Block | 84 | 24108 | .666 |
| GS6846PST | 5.5x7.5-46" BCT | 42 | 24096 | .661 |
| GS6806.5PST | 5.5x7.5-6.5' Rub Post | 126 | 24080 | .603 |
| GS6823BLK | 5.5x7.5-23" Rub Block | 84 | 24075 | .654 |
| GR61219BLK | 6x12-19" Routered Blk | 168 | 24074 | .676 |

I certify the above referenced material has been produced, treated and tested in accordance with and conforms to AASHTO M133 & M168 standards.

VA: Iowa Wood Preservers certifies that the treated wood products listed above have been treated in accordance with AWP standards, Section 236 of the VDOT Road & Bridge Specifications and meets the applicable minimum penetration and retention requirements.

Nicholas Sowl, General Counsel

7/24/2017
Date

Figure C-5. BCT Timber Post – MGS Height, Test No. N2BR-1



HIGHWAY SAFETY CORP

P.O. BOX 358
GLASTONBURY, CT 06033

CERTIFICATE OF COMPLIANCE/ANALYSIS REPORT

SOLD TO:

MIDWEST MACHINERY & SUPPLY
974-238th Road

Milford, NE, USA

SHIP TO:

MIDWEST MACHINERY & SUPPLY
974 238TH ROAD
MILFORD,

INVOICE / S.O.: 0201778 / 0148102
CUSTOMER P.O.: 3508

REFERENCE: STOCK
DATE SHIPPED: 10/23/2017

| QTY: | HEAT/LOT NO: | ITEM NUMBER: | YIELD: | CC: | TENSILE: | %ELONG: | DESCRIPTION: | C: | Mn: | P: | S: | Si: | Cl: | Type | ACW |
|-----------------------|--------------|-----------------|--------|----------------|----------|---------|---|----|-----|----|----|-----|-----|------|-----|
| 550 (200) (350) | 1702411 | T-POG060080600 | | IB-B0600800 | | | THRIE POST W06 x 008.5W x 06'00 GALV | | | | | | | | |
| 400 | 1703040 | PSG030050503-20 | | IBSB03005000 | | | POST S03@05.7 x 05'03.0 3 HL 2 SD W/PLT 3.5-3-3 SPGLV | | | | | | | | |
| | B76745 | | | PL-B025-080240 | | | | | | | | | | | |

ALL STEEL USED IN MANUFACTURING IS MADE AND MELTED IN THE USA, INCLUDING HARDWARE FASTENERS, AND COMPLIES WITH THE BUY AMERICA ACT. ALL COATINGS PROCESSES ARE PERFORMED IN THE USA AND COMPLY WITH THE BUY AMERICA ACT. BOLTS COMPLY WITH ASTM-A307 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM-A153, UNLESS OTHERWISE STATED. NUTS COMPLY WITH ASTM-A563 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM-A153, UNLESS OTHERWISE STATED. WASHERS COMPLY WITH ASTM F-436 AND/OR F-444 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM-A153, UNLESS OTHERWISE STATED. ALL GUARDRAIL MEETS AASHTO M-180 AND ALL STRUCTURAL STEEL MEETS AASHTO M-270. ALL OTHER GALVANIZED MATERIAL CONFORMS WITH ASTM-A123. ALL OTHER ITEMS COMPLY WITH AASHTO M-111, M-185, M-133, M-265, ASTM A36, ASTM-A709, ASTM-A123, ASTM A506, AND ASTM-A588 SPECIFICATIONS IF APPLICABLE. COMPLIANCE WITH ALL SPECIFICATIONS OF DEPARTMENT OF PUBLIC WORKS, DEPARTMENT OF HIGHWAYS AND TRANSPORTATION, DIVISION OF ROADS AND BRIDGES AND STATE HIGHWAY ADMINISTRATION IS MET IN ALL RESPECTS.

HIGHWAY SAFETY CORPORATION

QUALITY ASSURANCE MANAGER

NOTARIZED UPON REQUEST:

STATE OF CONNECTICUT COUNTY OF HARTFORD
SWORN AND SUBSCRIBED BEFORE ME THIS

3rd

DAY OF

Nov

2017

Margaret J. Satalino

Notary Public

MARGARET J. SATALINO
NOTARY PUBLIC
MY COMMISSION EXPIRES OCT. 31, 2021



CNWP

CENTRAL NEBRASKA WOOD PRESERVERS

1098 East Maple St
Sutton, NE 68979
Phone: 402.773.4319
Email: nick@nebraskawood.com

CERTIFICATE OF COMPLIANCE

Shipped To: Midwest Machinery and Supply

BOL# 100588715

Customer PO# 3528

Preservative: CCA - C 0.60D pcf AWPAC UC4B

| Part # | Physical Description | # of Pieces | Charge # | Tested Retention |
|-----------------|-----------------------|-------------|----------|------------------|
| 4075b | 6x8-14" Block | 126 | 24683 | .665 |
| 6120b | 6x12-14" Block | 84 | 23888 | .678 |
| GS6806.5 PST | 5.5x7.5-6.5' Rub Post | 84 | 24604 | .652 |
| GS6806.5 PST | 5.5x7.5-6.5' Rub Post | 42 | 24603 | .643 |
| GS6814 BLK | 5.5x7.5-14' Block | 126 | 24194 | .633 |
| | | | | |
| | | | | |
| | | | | |

I certify the above referenced material has been produced, treated and tested in accordance with and conforms to AASHTO M133 & M168 standards.

VA: Iowa Wood Preservers certifies that the treated wood products listed above have been treated in accordance with AWPAC standards, Section 236 of the VDOT Road & Bridge Specifications and meets the applicable minimum penetration and retention requirements.


Nick Sowl, General Counsel

1/11/2018
Date

Figure C-7. 6-in. x 12-in. x 14¼-in. Timber Blockouts for Steel Posts Certificates of Compliance, Test No. N2BR-1



GERDAU

US-ML-WILTON
1500-2500 WEST 3RD STREET
WILTON, LA 52778
USA

CERTIFIED MATERIAL TEST REPORT

Page 1/1

| | | | | | | |
|--|--|---|---------------|--------------------|------------------------------------|-----------------------------|
| CUSTOMER SHIP TO STEEL & PIPE SUPPLY CO INC 401 NEW CENTURY PKWY NEW CENTURY, KS 66031-1127 USA | | CUSTOMER BILL TO STEEL & PIPE SUPPLY CO INC MANHATTAN, KS 66505-1688 USA | | GRADE A36/44W | SHAPE / SIZE Flat Bar / 3/4 X 1 | DOCUMENT ID: 0000011110 |
| SALES ORDER 4190352/000010 | | CUSTOMER MATERIAL N° 000000000010810020 | | LENGTH 20'00" | WEIGHT 19,584 LB | HEAT / BATCH 64055041/02 |
| SPECIFICATION / DATE or REVISION ASME SA36 ASTM A5-14, A36-14 ASTM A709-15, AASHTO M270-12 CSA G40.20-13/G40.21-13 | | | H#64055041/02 | | | |
| CUSTOMER PURCHASE ORDER NUMBER 4500272853 | | BILL OF LADING 1334-0000034941 | | DATE 09/20/2016 | | |

| CHEMICAL COMPOSITION | | | | | | | | | | | | | |
|----------------------|---------|--------|--------|---------|---------|---------|---------|---------|--------|---------|---------|---------|--|
| C % | Mn % | P % | S % | Si % | Cu % | Ni % | Cr % | Mo % | V % | Nb % | Al % | Pb % | |
| 0.15 | 0.57 | 0.007 | 0.021 | 0.21 | 0.26 | 0.09 | 0.07 | 0.020 | 0.001 | 0.014 | 0.002 | 0.0000 | |

| CHEMICAL COMPOSITION | | |
|----------------------|---------|--|
| Ceq % | Sn % | |
| 0.33 | 0.018 | |

| MECHANICAL PROPERTIES | | | | | |
|-----------------------|-------------|------------|------------|-----------|-----------|
| Elong % | G/L Inch | UTS PSI | UTS MPa | YS PSI | YS MPa |
| 22.50 | 8.000 | 74300 | 512 | 58000 | 400 |
| 22.50 | 8.000 | 74400 | 513 | 57600 | 397 |

| GEOMETRIC CHARACTERISTICS | |
|---------------------------|--|
| R.R. | |
| 123.14 | |

COMMENTS / NOTES

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

Maskar

BHASKAR YALAMANCHILI
QUALITY DIRECTOR

Brett Krause BRETT KRAUSE

QUALITY ASSURANCE MGR.

Figure C-8. 2¾-in. x 1-in. x ¼-in. Post Standoff Mill Certification, Test No. N2BR-1




|  GERDAU US-ML-MIDLOTHIAN 300 WARD ROAD MIDLOTHIAN, TX 76065 USA | CUSTOMER SHIP TO STEEL & PIPE SUPPLY CO INC 4750 W MARSHALL AVE LONG VIEW, TX 75604-4817 USA | | CUSTOMER BILL TO STEEL & PIPE SUPPLY CO INC MANHATTAN, KS 66505-1688 USA | | GRADE A36/A572-50 | SHAPE / SIZE Standard I-Beam / 3 X 5.74 / 75 X 8.5 | DOCUMENT ID: 0000184326 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|--|-----------|---|-------------|----------------------|---|---|-----------------------------|----------------|------------|-----------|------------|-------------|-----------|-------|-------|------|------|-------|-------|-------|-------|------|-------|-------|-------|------|------|------|-------|-------|-------|-------|-------|
| | SALES ORDER 5937305/000050 | | CUSTOMER MATERIAL N° 000000000035357040 | | LENGTH 40'00" | PCS 36 | WEIGHT 8,208 LB | HEAT / BATCH 59076269/02 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | CUSTOMER PURCHASE ORDER NUMBER 4500299528 | | BILL OF LADING 1327-0000263916 | | DATE 01/15/2018 | | SPECIFICATION / DATE or REVISION ASME SA36 H#59076269/02 ASTM A572-15 ASTM A6-14, A36-14 ASTM A709-15 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| CHEMICAL COMPOSITION <table border="1"> <thead> <tr> <th>C %</th> <th>Mn %</th> <th>P %</th> <th>S %</th> <th>Si %</th> <th>Co %</th> <th>Ni %</th> <th>Cr %</th> <th>Mo %</th> <th>Sb %</th> <th>V %</th> <th>Nb %</th> <th>Al %</th> </tr> </thead> <tbody> <tr> <td>0.10</td> <td>0.84</td> <td>0.014</td> <td>0.024</td> <td>0.18</td> <td>0.33</td> <td>0.11</td> <td>0.18</td> <td>0.013</td> <td>0.007</td> <td>0.001</td> <td>0.012</td> <td>0.003</td> </tr> </tbody> </table> | | | | | | | | | C % | Mn % | P % | S % | Si % | Co % | Ni % | Cr % | Mo % | Sb % | V % | Nb % | Al % | 0.10 | 0.84 | 0.014 | 0.024 | 0.18 | 0.33 | 0.11 | 0.18 | 0.013 | 0.007 | 0.001 | 0.012 | 0.003 |
| C % | Mn % | P % | S % | Si % | Co % | Ni % | Cr % | Mo % | Sb % | V % | Nb % | Al % | | | | | | | | | | | | | | | | | | | | | | |
| 0.10 | 0.84 | 0.014 | 0.024 | 0.18 | 0.33 | 0.11 | 0.18 | 0.013 | 0.007 | 0.001 | 0.012 | 0.003 | | | | | | | | | | | | | | | | | | | | | | |
| CHEMICAL COMPOSITION CEgyA6 0.31 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MECHANICAL PROPERTIES <table border="1"> <thead> <tr> <th>YS 0.2% PSI</th> <th>UTS PSI</th> <th>YS MPa</th> <th>UTS MPa</th> <th>G/L Inch</th> <th>G/L mm</th> </tr> </thead> <tbody> <tr> <td>56532</td> <td>68686</td> <td>390</td> <td>474</td> <td>8.000</td> <td>200.0</td> </tr> <tr> <td>56815</td> <td>69000</td> <td>392</td> <td>476</td> <td>8.000</td> <td>200.0</td> </tr> </tbody> </table> | | | | | | | | | YS 0.2% PSI | UTS PSI | YS MPa | UTS MPa | G/L Inch | G/L mm | 56532 | 68686 | 390 | 474 | 8.000 | 200.0 | 56815 | 69000 | 392 | 476 | 8.000 | 200.0 | | | | | | | | |
| YS 0.2% PSI | UTS PSI | YS MPa | UTS MPa | G/L Inch | G/L mm | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 56532 | 68686 | 390 | 474 | 8.000 | 200.0 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 56815 | 69000 | 392 | 476 | 8.000 | 200.0 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MECHANICAL PROPERTIES Elong. % 22.70 21.80 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| COMMENTS / NOTES | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <p>The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.</p> <div style="display: flex; justify-content: space-between;"> <div>  BHASKAR YALAMANCHILI QUALITY DIRECTOR Phone: (409) 769-014 Email: Bhaskar.Yalamanchili@gerdau.com </div> <div>  WADE LUMPKINS QUALITY ASSURANCE MGR. Phone: 972-779-3118 Email: Wade.Lumpkins@gerdau.com </div> </div> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

Figure C-9. S3x5.7 Post Mill Certification, Test No. N2BR-1 Mill Certification, Test No. N2BR-1

SSAB

Preliminary Test Certificate

Form TC1: Revision 2: Date 23 Apr 2014

1770 Bill Sharp Boulevard, Muscatine, IA 52761-9412, US **Official copy to follow**

| | | | | | | | |
|--|--|--|--|------------------------------|--|--|--|
| Customer: STEEL & PIPE SUPPLY P.O. BOX 1688 MANHATTAN KS 66502 | | Customer P.O. No.: 4500287649 | | Mill Order No.: 41-504804-02 | | Shipping Manifest : MT318692 | |
| | | Product Description: ASTM A572-50/M345(15)/A709-50/M345(16A) | | | | Ship Date: 21 Jun 17 Cert Date: 21 Jun 17 | |
| | | Size: 0.500 X 96.00 X 240.0 (IN) | | | | Cert No: 061649975 (Page 1 of 1) | |

| Tested Pieces | | | Tensiles | | | | | Charpy Impact Tests | | | | | | | | | | | | | | | |
|---------------|----------|------------------|----------|----------|-----------|-----|-------------|---------------------|---------|----------|-------------------|--|--|--|---------|--|--|---------|---------|---------|--------------|-----------|------|
| Heat Id | Piece Id | Tested Thickness | Tst Loc | YS (KSI) | UTS (KSI) | %RA | Elong % 2in | % 8in | Tst Dir | Hardness | Abs. Energy(FTLB) | | | | % Shear | | | Tst Avg | Tst Tmp | Tst Dir | Tst Siz (mm) | BDWTT Tmp | %Shr |
| A7D898 | D19 | 0.496 (DISCRT) | L 61 | 73 | | | 38 | | T | | | | | | | | | | | | | | |
| A7F058 | D31 | 0.497 (DISCRT) | L 55 | 68 | | | 37 | | T | | | | | | | | | | | | | | |
| B7D657 | D18 | 0.507 (DISCRT) | L 57 | 77 | | | 28 | | T | | | | | | | | | | | | | | |

| Heat Id | Chemical Analysis | | | | | | | | | | | | | | ORGN |
|---------|-------------------|------|------|------|-----|--------|-----|-----|-----|-----|------|------|------|-----|------|
| | C | Mn | P | S | Si | Tot Al | Cu | Ni | Cr | Mo | Cb | V | Ti | | |
| A7D898 | .05 | 1.32 | .014 | .004 | .10 | .034 | .30 | .14 | .15 | .03 | .024 | .027 | .008 | USA | |
| A7F058 | .05 | 1.21 | .012 | .006 | .02 | .028 | .31 | .14 | .10 | .04 | .002 | .053 | .001 | USA | |
| B7D657 | .16 | 1.14 | .013 | .007 | .03 | .029 | .30 | .15 | .17 | .04 | .002 | .033 | .006 | USA | |

KILLED STEEL
MERCURY IS NOT A METALLURGICAL COMPONENT OF THE STEEL AND NO MERCURY WAS INTENTIONALLY ADDED DURING THE MANUFACTURE OF THIS PRODUCT.
MTR EN 10204:2004 INSPECTION CERTIFICATE 3.1 COMPLIANT
100% MELTED AND MANUFACTURED IN THE USA.
PRODUCTS SHIPPED:
B7D657 D18 PCES: 2, LBS: 6534 A7F058 D31 PCES: 1, LBS: 3267
A7D898 D19 PCES: 3, LBS: 9801

| | | |
|--------------------------------|--|-------------------------------|
| (11) Cust Part # : 721696240A2 | WE HEREBY CERTIFY THAT THIS MATERIAL WAS TESTED IN ACCORDANCE WITH, AND MEETS THE REQUIREMENTS OF, THE APPROPRIATE SPECIFICATION | SENIOR METALLURGIST - PRODUCT |
|--------------------------------|--|-------------------------------|

Figure C-10. 10-in. x 7-in. x 1/2-in. Steel Plate Mill Certification, Test No. N2BR-1

STEEL AND PIPE SUPPLY

SPS Coil Processing Tulsa
5275 Bird Creek Ave.
Port of Catoosa, OK 74015

METALLURGICAL TEST REPORT

PAGE 1 of 1
DATE 12/19/2017
TIME 12:50:41
USER WILLIAMR

S
O
L
D
T
O

66031-1127

S
H
I
P
T
O

18271
SPS Warehouse 0045
401 New Century Parkway
NEW CENTURY KS

| Order | Material No. | Description | Quantity | Weight | Customer Part | Customer PO | Ship Date |
|---------------|--------------|------------------------------|----------|-----------|---------------|-------------|------------|
| 40289425-0020 | 70872178 | 1/4 72 X 178 A36 STP MIL PLT | 6 | 5,452.140 | | | 12/19/2017 |

H#17126641

| Heat No. | | Vendor | | Chemical Analysis | | | | | Mill | | | Melted and Manufactured in the USA | | | |
|--------------------|-----------|---------------------|---------|-------------------|--------|----------|------------|--------|---------------------|----------|----------|------------------------------------|-----------|----------|--------|
| 17126641 | | BIG RIVER STEEL LLC | | DOMESTIC | | | | | BIG RIVER STEEL LLC | | | | | | |
| Produced from Coil | | | | | | | | | | | | | | | |
| Carbon | Manganese | Phosphorus | Sulphur | Silicon | Nickel | Chromium | Molybdenum | Boron | Copper | Aluminum | Titanium | Vanadium | Columbium | Nitrogen | Tin |
| 0.1900 | 0.8200 | 0.0070 | 0.0020 | 0.0300 | 0.0400 | 0.0500 | 0.0120 | 0.0001 | 0.1100 | 0.0260 | 0.0010 | 0.0040 | 0.0020 | 0.0077 | 0.0055 |

Mechanical / Physical Properties

| Mill Coil No. | | Yield | | Elong | | Rockwell | | Grain | | Charpy | | Charpy Dr | | Charpy Sz | | Temperature | | Olsen | |
|---------------|--|-----------|--|-------|--|----------|--|-------|--|--------|--|-----------|--|-----------|--|-------------|--|-------|--|
| 17126641-05 | | | | | | | | | | | | | | | | | | | |
| 75700.000 | | 54100.000 | | 28.10 | | | | | | 0 | | NA | | | | | | | |
| 71300.000 | | 52000.000 | | 30.60 | | | | | | 0 | | NA | | | | | | | |
| 71800.000 | | 52000.000 | | 33.20 | | | | | | 0 | | NA | | | | | | | |
| 74800.000 | | 55400.000 | | 28.70 | | | | | | 0 | | NA | | | | | | | |

Batch 0005075120 6 EA 5,452.140 LB

Batch 0005075119 7 EA 8,360.830 LB

THE CHEMICAL, PHYSICAL, OR MECHANICAL TESTS REPORTED ABOVE ACCURATELY REFLECT INFORMATION AS CONTAINED IN THE RECORDS OF THE CORPORATION.
The material is in compliance with EN 10204 Section 4.1 Inspection Certificate Type 3.1

Figure C-11. 10-in. x 2³/₄-in. x 1/4-in. Plate Washer Mill Certification, Test No. N2BR-1

Atlas Tube Corporation
1855 East 122nd Street
Chicago, Illinois, USA
60633
Tel: 773-646-4500
Fax: 773-646-6128



Ref./L: 80796107
Date: 12.07.2017
Customer: 179

MATERIAL TEST REPORT

Sold to

Steel & Pipe Supply Company
PO Box 1688
MANHATTAN KS 66505
USA

H#W46930

Shipped to

Steel & Pipe Supply Company
401 New Century Parkway
NEW CENTURY KS 66031
USA

Material: 4.0x4.0x375x40"0"0(5x2)
Material No: 400403754000
Made in: USA
Melted in: USA
Sales order: 1238969
Purchase Order: C450006892
Cust Material #: 6540037540

| Heat No | C | Mn | P | S | Si | Al | Cu | Co | Mo | Ni | Cr | V | Ti | B | N |
|---------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| W46930 | 0.190 | 0.790 | 0.010 | 0.008 | 0.014 | 0.050 | 0.040 | 0.004 | 0.005 | 0.010 | 0.050 | 0.002 | 0.001 | 0.000 | 0.004 |

Bundle No PCs Yield Tensile Eln.2in Certification CE: 0.34
M800748374 10 067480 Psi 078686 Psi 29 % ASTM A500-13 GRADE B&C

Material Note:
Sales Or.Note:

Material: 8.0x8.0x250x40"0"0(3x3)
Material No: 800802504000
Made in: USA
Melted in: USA
Sales order: 1238966
Purchase Order: C450006892
Cust Material #: 6580025040

| Heat No | C | Mn | P | S | Si | Al | Cu | Co | Mo | Ni | Cr | V | Ti | B | N |
|---------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| M47546 | 0.200 | 0.850 | 0.012 | 0.009 | 0.012 | 0.040 | 0.030 | 0.005 | 0.005 | 0.010 | 0.040 | 0.002 | 0.001 | 0.000 | 0.007 |

Bundle No PCs Yield Tensile Eln.2in Certification CE: 0.36
M900959981 9 064500 Psi 077500 Psi 32 % ASTM A500-13 GRADE B&C

Material Note:
Sales Or.Note:

Material: 8.0x8.0x313x40"0"0(3x2)
Material No: 800803134000
Made in: USA
Melted in: USA
Sales order: 1238971
Purchase Order: C450006892
Cust Material #: 6580031340

| Heat No | C | Mn | P | S | Si | Al | Cu | Co | Mo | Ni | Cr | V | Ti | B | N |
|----------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| 17118861 | 0.210 | 0.750 | 0.007 | 0.003 | 0.020 | 0.027 | 0.120 | 0.001 | 0.013 | 0.040 | 0.040 | 0.003 | 0.000 | 0.000 | 0.006 |

Bundle No PCs Yield Tensile Eln.2in Certification CE: 0.36
M900959865 6 064000 Psi 077500 Psi 32 % ASTM A500-13 GRADE B&C

Material Note:
Sales Or.Note:

Jason Richard
Jason Richard

Authorized by Quality Assurance:
The results reported on this report represent the actual attributes of the material furnished and indicate full compliance with all applicable specification and contract requirements.
CE calculated using the AWS D1.1 method.



Page : 1 Of 3



Figure C-12. HSS4x4x3/8, 65/8-in. Long Square Tube Mill Certification, Test No. N2BR-1

CERTIFICATE OF ANALYSIS

1020 Niedringhaus Ave
PO BOX 366
Granite City, IL 62040
Phone: (618) 452-2833 Fax: (618) 452-8780



Date: 03/01/2016
Time: 13:34:43
Page: 5 of 5

Release #: 6599 Customer: STEEL & PIPE SUPPLY CO. INC.

Customer PO:

Chemistry Heat Number 62213

nValue:

rValue:

| | | | | | | | | | |
|--|-----|-----|-----|-----|--------|-----|------|-----|-----|
| C: | .14 | Mn: | .68 | P: | .021 | S: | .016 | Si: | .19 |
| Cu: | .04 | Al: | | CB: | | V: | | Ni: | |
| Cr: | | Ti: | | N: | | Mo: | | Ca: | |
| Zr: | | Sb: | | B: | | Sn: | | Nb: | |
| Melted and Manufactured Outside of the USA | | | | | TURKEY | | | | |

| Tag No | Product | Gage | Width | Length | Weight | Storage Tag No | Part Number | Rb | Tensile | Yield | Elong |
|--------|---------|--------|--------|----------|-----------|----------------|---------------------|----|---------|-------|-------|
| 748003 | HR FL | 0.1250 | 1.0000 | 240.0000 | 4,352 | | SPSC 1/8 X 1.0 X 2 | | 67000 | 42900 | 36.0 |
| | | | | | Grade A36 | | Cust PO: 4500260308 | | | | |

Authorized Signatory

Mary Macko


Mary Macko

The above stated information is an exact copy of test reports provided by our supplier or independent laboratory and contained in our permanent records, or that the absence of same, the steel listed above was purchased by us to comply with the above stated.


psdata.co-4943

Figure C-13. 3½-in. x 1-in. x ⅛-in. Plate Mill Certification, Test No. N2BR-1

Steel & Pipe Supply Co.
Midwest Steel Works, Inc.
Customer PO: 50247
Heat: 52080955
Shipment: 0018004574

| CERTIFIED MATERIAL TEST REPORT | | | | | | | | | | Page 1/1 | |
|---|------|---|-------|---|------|--------------------|------|---------------------|-------|-----------------------------|--|
|  GERDAU CA-ML-WHITBY 1 GERDAU CT WHITBY, ON L1N 5T1 Canada | | CUSTOMER SHIP TO | | CUSTOMER BILL TO | | GRADE | | SHAPE / SIZE | | DOCUMENT ID: | |
| | | STEEL & PIPE SUPPLY CO INC 401 NEW CENTURY PKWY NEW CENTURY, KS 66031-1127 USA | | STEEL & PIPE SUPPLY CO INC MANHATTAN, KS 66505-1688 USA | | GOMULTI | | Channel / 7 X 9.8# | | 0000060224 | |
| | | SALES ORDER 5780975/000920 | | CUSTOMER MATERIAL N° 00000000025798040 | | LENGTH 40'00" | | WEIGHT 18.816 LB | | HEAT / BATCH 52080955/02 | |
| | | SPECIFICATION / DATE or REVISION | | H#52080955/02 | | | | | | | |
| | | ASTM A572-14, A572-15 ASTM A614, A36-14, ASME SA-36 ASTM A399-15, AASHTO M270-12 CSA G40.30-13/G40.21-13 | | | | | | | | | |
| CUSTOMER PURCHASE ORDER NUMBER 4500297143 | | | | BILL OF LADING 1302-0000068002 | | DATE 12/04/2017 | | | | | |
| CHEMICAL COMPOSITION | | | | | | | | | | | |
| C % | Mn % | P % | S % | Si % | Cr % | Ni % | Cr % | V % | Nb % | | |
| 0.14 | 0.75 | 0.017 | 0.032 | 0.17 | 0.32 | 0.12 | 0.12 | 0.013 | 0.001 | | |
| MECHANICAL PROPERTIES | | | | | | | | | | | |
| Elong. % | | G/L Inch | | UTS PSI | | UTS MPa | | YS 0.2% PSI | | YS MPa | |
| 25.00 | | 8.000 | | 69800 | | 481 | | 51200 | | 353 | |
| 25.00 | | 8.000 | | 71400 | | 492 | | 51100 | | 352 | |
| COMMENTS / NOTES | | | | | | | | | | | |
| This grade meets the requirements for the following grades: ASTM Grades: A36; A572-50; A572-30; A709-36; A709-50 CSA Grades: 44W; 50W AASHTO Grades: M270-36; M270-50 ASME Grades: SA36 | | | | | | | | | | | |

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in Canada. CMTR complies with EN 10204 3.1.


 BHASKAR YALAMANCHILI
 QUALITY DIRECTOR
 Phone: (409) 769-1014 Email: Bhaskar.Yalamanchili@gerdau.com





 LEONARDO NUNES
 QUALITY ASSURANCE MGR.
 Phone: (905) 668-8811 EXT 4055 Email: Leonardo.Nunes@gerdau.com

Figure C-14. C7x9.8, 225-in. Long C-Channel Mill Certification, Test No. N2BR-1


| CERTIFICATE OF ANALYSIS | | | | | | | | | | | | | |
|---|------------------------|---------------------|--------|--|--------|--|--------|----------------------|-------|--|-------|-------|--|
| 1020 Niedringhaus Ave PO BOX 368 Granite City, IL 62040 Phone: (618) 452-2833 Fax: (618) 452-8780 | | | | | |  | | | | Date: 08/26/2016 Time: 12:47:57 Page: 7 of 8 | | | |
| Release #: | | 7226 | | Customer: STEEL & PIPE SUPPLY CO. INC. | | | | Customer PO: | | | | | |
| Chemistry: | | Heat Number 1164312 | | | | | | | | | | | |
| nValue: | | | | | | rValue: | | | | | | | |
| C: | .22 | Mn: | .47 | P: | .008 | S: | .0015 | Si: | .02 | | | | |
| Cu: | .11 | Al: | .03 | CB: | | V: | .002 | Ni: | .04 | | | | |
| Cr: | .05 | Ti: | .003 | N: | .007 | Mo: | .01 | Ca: | .003 | | | | |
| Zr: | | Sb: | | B: | | Sn: | .005 | Nb: | .002 | | | | |
| Melted and Manufactured in the USA | | | | | | | | | | | | | |
| Tag No | Product | Gage | Width | Length | Weight | Storage | Tag No | Part Number | Rb | Tensile | Yield | Elong | |
| 754064 | HR PL | 0.1250 | 2.0000 | 240.0000 | 2,651 | | | SPSC 1/8 X 2.0 X 240 | 74200 | 50800 | 28.0 | | |
| | Mill Tag No: 1165949.0 | | | | | | | | | | | | |
| 754071 | HR PL | 0.1250 | 1.5000 | 240.0000 | 2,549 | | | SPSC 1/8 X 1.5 X 240 | 74200 | 50800 | 28.0 | | |
| | Mill Tag No: 1165949.0 | | | | | | | | | | | | |
| 754072 | HR PL | 0.1250 | 1.5000 | 240.0000 | 2,027 | | | SPSC 1/8 X 1.5 X 240 | 74200 | 50800 | 28.0 | | |
| | Mill Tag No: 1165949.0 | | | | | | | | | | | | |
| 754061 | HR PL | 0.1250 | 2.0000 | 240.0000 | 2,651 | | | SPSC 1/8 X 2.0 X 240 | 74200 | 50800 | 28.0 | | |
| | Mill Tag No: 1165949.0 | | | | | | | | | | | | |
| 754062 | HR PL | 0.1250 | 2.0000 | 240.0000 | 2,651 | | | SPSC 1/8 X 2.0 X 240 | 74200 | 50800 | 28.0 | | |
| | Mill Tag No: 1165949.0 | | | | | | | | | | | | |
| 754063 | HR PL | 0.1250 | 2.0000 | 240.0000 | 2,651 | | | SPSC 1/8 X 2.0 X 240 | 74200 | 50800 | 28.0 | | |
| | Mill Tag No: 1165949.0 | | | | | | | | | | | | |
| The above stated information is an exact copy of test reports provided by our supplier or independent laboratory and contained in our permanent records, or that the absence of same, the steel listed above was purchased by us to comply with the above stated. | | | | | | | | | | | | | |

p3992a-co-894.3

Figure C-15. 6½-in. x 2-in. x ⅛-in. Shim Plate Mill Certification, Test No. N2BR-1

| CERTIFIED MATERIAL TEST REPORT | | | | | | | | | | | | Page 1/1 | | | | | | | | | | | | | | | | | | | | | | | | | |
|--|-----------------|---|-------------------|-----------------------------------|----------|--|---------|--------------------|---------|-----------------------|---------------|-----------------------------------|--|------------------------------|-----------------|-----------------|-------------------|------------|----------|---------|---------|---------|---------|--------|---------------|------|------|-------|-------|------|------|------|------|-------|-------|-------|------|
|  GERDAU US-ML-KNOXVILLE 1919 TENNESSEE AVENUE N. W. KNOXVILLE, TN 37921 USA | | CUSTOMER SHIP TO METAL PARTNERS REBAR LLC 13535 S TORRENCE AVE CHICAGO, IL 60633-2164 USA | | | | CUSTOMER BILL TO METAL PARTNERS INTERNATIONAL 55 S MAIN STREET NAPERVILLE, IL 60540-8500 USA | | | | GRADE 60 (420) TMX | | SHAPE / SIZE Rebar / #4 (13MM) | | DOCUMENT ID: 0060000000 | | | | | | | | | | | | | | | | | | | | | | | |
| | | SALES ORDER 5354816/000010 | | | | CUSTOMER MATERIAL N° X-13-42-2000 | | | | LENGTH 20'00" | | WEIGHT 2,004 LB | | HEAT / BATCH 571666-46/02 | | | | | | | | | | | | | | | | | | | | | | | |
| | | SPECIFICATION / DATE or REVISION ASTM A615/A615M-15 E1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| CUSTOMER PURCHASE ORDER NUMBER 11046 | | | | BILL OF LADING 4751-0000020326 | | | | DATE 07/17/2017 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| CHEMICAL COMPOSITION | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <table border="1"> <thead> <tr> <th>C %</th> <th>Mn %</th> <th>P %</th> <th>S %</th> <th>Si %</th> <th>Cr %</th> <th>Ni %</th> <th>Al %</th> <th>Mo %</th> <th>Sn %</th> <th>V %</th> <th>CEq A706 %</th> </tr> </thead> <tbody> <tr> <td>0.28</td> <td>0.55</td> <td>0.007</td> <td>0.065</td> <td>0.17</td> <td>0.31</td> <td>0.12</td> <td>0.11</td> <td>0.020</td> <td>0.007</td> <td>0.003</td> <td>0.39</td> </tr> </tbody> </table> | | | | | | | | | | | | | | C % | Mn % | P % | S % | Si % | Cr % | Ni % | Al % | Mo % | Sn % | V % | CEq A706 % | 0.28 | 0.55 | 0.007 | 0.065 | 0.17 | 0.31 | 0.12 | 0.11 | 0.020 | 0.007 | 0.003 | 0.39 |
| C % | Mn % | P % | S % | Si % | Cr % | Ni % | Al % | Mo % | Sn % | V % | CEq A706 % | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 0.28 | 0.55 | 0.007 | 0.065 | 0.17 | 0.31 | 0.12 | 0.11 | 0.020 | 0.007 | 0.003 | 0.39 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MECHANICAL PROPERTIES | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <table border="1"> <thead> <tr> <th>YS PSI</th> <th>YS MPa</th> <th>UTS PSI</th> <th>UTS MPa</th> <th>EL inch</th> <th>EL mm</th> </tr> </thead> <tbody> <tr> <td>77120</td> <td>532</td> <td>92280</td> <td>636</td> <td>8.000</td> <td>200.0</td> </tr> </tbody> </table> | | | | | | | | | | | | | | YS PSI | YS MPa | UTS PSI | UTS MPa | EL inch | EL mm | 77120 | 532 | 92280 | 636 | 8.000 | 200.0 | | | | | | | | | | | | |
| YS PSI | YS MPa | UTS PSI | UTS MPa | EL inch | EL mm | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 77120 | 532 | 92280 | 636 | 8.000 | 200.0 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MECHANICAL PROPERTIES Elong. % 11.90 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bend Test OK | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| GEOMETRIC CHARACTERISTICS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <table border="1"> <thead> <tr> <th>%Light</th> <th>Def/Hgt inch</th> <th>Def/Gap inch</th> <th>Def/Space inch</th> </tr> </thead> <tbody> <tr> <td>4.49</td> <td>0.029</td> <td>0.104</td> <td>0.323</td> </tr> </tbody> </table> | | | | | | | | | | | | | | %Light | Def/Hgt inch | Def/Gap inch | Def/Space inch | 4.49 | 0.029 | 0.104 | 0.323 | | | | | | | | | | | | | | | | |
| %Light | Def/Hgt inch | Def/Gap inch | Def/Space inch | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4.49 | 0.029 | 0.104 | 0.323 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| COMMENTS / NOTES | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.


 BHASKAR YALAMANCHILI
 QUALITY DIRECTOR
 Phone: (409) 769-1014 Email: Bhaskar.Yalamanchili@gerdau.com




 JIM HALL
 QUALITY ASSURANCE MGR.
 Phone: 865-202-5972 Email: Jim.hall@gerdau.com

Figure C-16. No. 4 Rebar Mill Certification, Test No. N2BR-1

Page 1/1

| | | | | | | | | | |
|---|---|--|---|--|--|--------------------|---|-----------------------------------|---------------------------|
|  GERDAU US-ML-KNOXVILLE 1919 TENNESSEE AVENUE N. W. KNOXVILLE, TN 37921 USA | CERTIFIED MATERIAL TEST REPORT | | CUSTOMER SHIP TO MIDWEST PIPE COATING 925 KENNEDY AVE SCHERERVILLE, IN 46375-1325 USA | | CUSTOMER BILL TO METAL PARTNERS INTERNATIONAL 47 E CHICAGO AVE NAPERVILLE, IL 60540-5360 USA | | GRADE 60 (420) TMX | SHAPE / SIZE Rebar / #4 (13MM) | DOCUMENT ID: 000000000 |
| | SALES ORDER 5571122000240 | | CUSTOMER MATERIAL N° X-13-42-4000 | | LENGTH 40'00" | WEIGHT 6.012 LB | HEAT / BATCH 57166635/02 | | |
| | CUSTOMER PURCHASE ORDER NUMBER 11095 | | BILL OF LADING 4751-0000021408 | | DATE 09/07/2017 | | SPECIFICATION / DATE OF REVISION ASTM A615/A615M-15 E1 | | |

| | | | | | | | | | | | |
|----------------------|---------|--------|--------|---------|---------|---------|---------|---------|---------|--------|---------|
| CHEMICAL COMPOSITION | | | | | | | | | | | |
| C % | Mn % | P % | S % | Si % | Cu % | Ni % | Cr % | Mo % | Al % | V % | CEqA706 |
| 0.29 | 0.54 | 0.010 | 0.072 | 0.20 | 0.32 | 0.11 | 0.09 | 0.010 | 0.010 | 0.002 | 0.41 |


| | | | | | | | | | |
|-----------------------|--|-----|--|-------|--|-------|--|-------|--|
| MECHANICAL PROPERTIES | | YS | | UTS | | G/L | | G/L | |
| PSI | | MPa | | PSI | | Inch | | mm | |
| 79010 | | 543 | | 95020 | | 8.000 | | 200.0 | |

| | | | |
|-----------------------|--|-----------|--|
| MECHANICAL PROPERTIES | | Bend Test | |
| Elong. | | OK | |
| 11.30 | | | |

| | | | |
|---------------------------|------------------|-----------------|-------------------|
| GEOMETRIC CHARACTERISTICS | | | |
| Weight g | Def 11gr Inch | Def Gap Inch | Def Space Inch |
| 4.19 | 0.030 | 0.105 | 0.321 |


COMMENTS / NOTES

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.



BHASKAR YALAMANCHILI
QUALITY DIRECTOR

Phone: (+991) 769-1814 Email: Bhaskar.Yalamanchili@gerdau.com



JIM HALL
QUALITY ASSURANCE MGR.

Phone: 865-202-5972 Email: Jim.hall@gerdau.com

Figure C-17. No. 4 Rebar Mill Certification, Test No. N2BR-1

Customer Name
Carroll Distributing & Construction S
Customer PO#
L1104261
Shipper No
219957
Heat Number
17-00688



KAPTAN DEMIR CELIK ENDUSTRISI ve TICARET A.S.
FAHRETTIN KERIM GOKAY CAD. BESTEKAR SAADETTIN KAYNAK
SOKAK NO:2 34662 ALTUNIZADE/USKUDAR /ISTANBUL/TURKEY
Tel : +90.216. 547 49 00 , Fax :+90.216. 428 74 74

ORIGINAL

TO WHOM IT MAY CONCERN

DESCRIPTION OF GOODS:

ACE-USA-322/R08
REINFORCING DEFORMED STEEL BARS
QUALITY :ASTM A 615-GR 40/ASTM A 615-GR 60/HR COOLED

12.02.2017
PAGE 1/1

MILL TEST CERTIFICATE

KAPTAN DEMIR CELIK
ENDUSTRISI ve TICARET A.S.
MERSİS NO: 49000000000015

LOT 1

| Size (Inch) | Length (Feet) | GRADE | Heat Number | NUMBER OF BUNDLES | PHYSICAL PROPERTIES | | | | | CHEMICAL ANALYSIS | | | | | | | | | | | | | | | | |
|-------------|---------------|-------|-------------|-------------------|---------------------|------------------|----------|--------|------|-------------------|------|------|-------|-------|------|------|-------|------|-------|--------|------|--|--|--|--|--|
| | | | | | Yield Point | Tensile Strength | Rm / ReH | Elong. | Bond | % | | | | | | | | | | | | | | | | |
| | | | | | Mpa | Mpa | % | % | Test | C | Mn | Si | P | S | Ni | Cr | Mo | Cu | V | N | Co | | | | | |
| (#3) 3/8" | 20 | 60 | 17-00528 | 26 | 466 | 672 | 1.44 | 13.0 | OK | 0.41 | 0.52 | 0.14 | 0.019 | 0.039 | 0.09 | 0.08 | 0.023 | 0.33 | 0.017 | 0.0099 | 0.57 | | | | | |
| (#3) 3/8" | 20 | 60 | 17-00524 | 78 | 466 | 678 | 1.45 | 13.9 | OK | 0.42 | 0.56 | 0.16 | 0.030 | 0.030 | 0.13 | 0.15 | 0.027 | 0.40 | 0.018 | 0.0087 | 0.60 | | | | | |
| (#4) 1/2" | 20 | 40 | 17-00687 | 56 | 335 | 510 | 1.52 | 19.3 | OK | 0.29 | 0.56 | 0.14 | 0.030 | 0.034 | 0.12 | 0.14 | 0.030 | 0.32 | 0.003 | 0.0060 | 0.48 | | | | | |
| (#4) 1/2" | 20 | 40 | 17-00688 | 114 | 342 | 505 | 1.48 | 17.9 | OK | 0.28 | 0.53 | 0.14 | 0.034 | 0.036 | 0.10 | 0.18 | 0.024 | 0.29 | 0.005 | 0.0079 | 0.45 | | | | | |
| (#4) 1/2" | 20 | 40 | 17-00689 | 39 | 343 | 505 | 1.47 | 19.4 | OK | 0.30 | 0.55 | 0.13 | 0.023 | 0.038 | 0.11 | 0.10 | 0.022 | 0.27 | 0.003 | 0.0083 | 0.44 | | | | | |
| (#4) 1/2" | 20 | 60 | 17-00599 | 37 | 487 | 707 | 1.42 | 13.5 | OK | 0.45 | 0.61 | 0.15 | 0.032 | 0.034 | 0.12 | 0.12 | 0.019 | 0.44 | 0.024 | 0.0080 | 0.62 | | | | | |
| (#4) 1/2" | 20 | 60 | 17-00597 | 92 | 465 | 656 | 1.41 | 13.0 | OK | 0.45 | 0.63 | 0.18 | 0.030 | 0.032 | 0.13 | 0.12 | 0.021 | 0.41 | 0.025 | 0.0071 | 0.62 | | | | | |
| (#4) 1/2" | 20 | 60 | 17-00598 | 130 | 466 | 677 | 1.45 | 13.0 | OK | 0.44 | 0.65 | 0.18 | 0.034 | 0.023 | 0.13 | 0.13 | 0.025 | 0.41 | 0.024 | 0.0082 | 0.62 | | | | | |
| (#4) 1/2" | 20 | 60 | 17-00599 | 47 | 467 | 677 | 1.45 | 13.4 | OK | 0.47 | 0.63 | 0.15 | 0.027 | 0.044 | 0.12 | 0.10 | 0.023 | 0.40 | 0.023 | 0.0080 | 0.64 | | | | | |
| (#4) 1/2" | 20 | 60 | 17-00510 | 118 | 487 | 678 | 1.39 | 12.8 | OK | 0.45 | 0.64 | 0.15 | 0.030 | 0.045 | 0.12 | 0.11 | 0.028 | 0.36 | 0.023 | 0.0084 | 0.62 | | | | | |
| (#4) 1/2" | 20 | 60 | 17-00511 | 83 | 508 | 708 | 1.39 | 11.4 | OK | 0.44 | 0.62 | 0.17 | 0.048 | 0.012 | 0.14 | 0.19 | 0.030 | 0.43 | 0.024 | 0.0082 | 0.63 | | | | | |
| (#4) 1/2" | 20 | 60 | 17-00512 | 106 | 489 | 699 | 1.43 | 11.2 | OK | 0.45 | 0.61 | 0.17 | 0.031 | 0.040 | 0.12 | 0.14 | 0.031 | 0.40 | 0.024 | 0.0073 | 0.62 | | | | | |
| (#4) 1/2" | 20 | 60 | 17-00513 | 111 | 479 | 685 | 1.43 | 12.6 | OK | 0.44 | 0.61 | 0.17 | 0.038 | 0.035 | 0.11 | 0.12 | 0.023 | 0.42 | 0.023 | 0.0077 | 0.61 | | | | | |
| (#4) 1/2" | 20 | 60 | 17-00514 | 50 | 492 | 699 | 1.40 | 12.4 | OK | 0.44 | 0.62 | 0.16 | 0.032 | 0.027 | 0.12 | 0.16 | 0.023 | 0.45 | 0.024 | 0.0081 | 0.62 | | | | | |
| (#4) 1/2" | 20 | 60 | 17-00515 | 91 | 488 | 683 | 1.40 | 11.9 | OK | 0.44 | 0.62 | 0.16 | 0.032 | 0.027 | 0.12 | 0.16 | 0.023 | 0.45 | 0.024 | 0.0081 | 0.62 | | | | | |
| (#4) 1/2" | 20 | 60 | 17-00516 | 21 | 480 | 681 | 1.42 | 12.5 | OK | 0.44 | 0.61 | 0.15 | 0.031 | 0.028 | 0.13 | 0.13 | 0.023 | 0.44 | 0.023 | 0.0091 | 0.62 | | | | | |
| (#5) 5/8" | 20 | 60 | 17-00834 | 54 | 477 | 679 | 1.40 | 13.9 | OK | 0.45 | 0.61 | 0.16 | 0.028 | 0.031 | 0.11 | 0.15 | 0.026 | 0.29 | 0.022 | 0.0097 | 0.61 | | | | | |
| (#5) 5/8" | 20 | 60 | 17-00842 | 70 | 476 | 676 | 1.42 | 13.7 | OK | 0.45 | 0.60 | 0.13 | 0.016 | 0.028 | 0.10 | 0.09 | 0.025 | 0.27 | 0.024 | 0.0096 | 0.60 | | | | | |
| (#5) 5/8" | 20 | 60 | 17-00843 | 50 | 452 | 659 | 1.45 | 13.3 | OK | 0.44 | 0.62 | 0.13 | 0.017 | 0.040 | 0.10 | 0.10 | 0.028 | 0.28 | 0.023 | 0.0090 | 0.60 | | | | | |
| (#5) 5/8" | 20 | 60 | 17-00844 | 34 | 474 | 661 | 1.39 | 14.1 | OK | 0.44 | 0.59 | 0.13 | 0.021 | 0.031 | 0.10 | 0.10 | 0.032 | 0.29 | 0.023 | 0.0091 | 0.60 | | | | | |
| (#6) 3/4" | 20 | 60 | 17-00885 | 23 | 470 | 670 | 1.43 | 13.1 | OK | 0.46 | 0.62 | 0.16 | 0.017 | 0.038 | 0.12 | 0.10 | 0.029 | 0.31 | 0.023 | 0.0098 | 0.62 | | | | | |
| (#6) 3/4" | 20 | 60 | 17-00886 | 27 | 468 | 679 | 1.45 | 13.2 | OK | 0.45 | 0.61 | 0.13 | 0.016 | 0.029 | 0.13 | 0.09 | 0.023 | 0.30 | 0.023 | 0.0096 | 0.61 | | | | | |
| TOTAL | | | | 1,455 | | | | | | | | | | | | | | | | | | | | | | |

Figure C-18. No. 4 Rebar Mill Certification, Test No. N2BR-1



2100 S. Foothill
Pueblo, CO 81004 USA

ROCKY MOUNTAIN STEEL
A DIVISION OF EVRAZ INC. NA

MATERIAL TEST REPORT

Date Printed: 28-AUG-17

Date Shipped: 28-AUG-17

Product: DEF #4 (1/2")

Specification: ASTM A706/A615 GR 60

FWIP: 52815348

Customer: HARRIS SUPPLY SOLUTIONS INC

Cust. PO: P147717

318 ARVIN AVE
STONE CREEK, L8E 2M2

| Heat Number | CHEMICAL ANALYSIS (In Weight %, uncertainty of measurement 0.005%) | | | | | | | | | | | | | | (Heat cast 08/14/17) | |
|---------------------------|--|------|-------|-------|------|------|------|------|-------|-------|-------|--------|-------|-------|----------------------|-------|
| | C | Mn | P | S | Si | Ca | Ni | Cr | Mo | Al | V | B | Cb | Sn | N | Ti |
| 594643 | 0.27 | 1.24 | 0.014 | 0.015 | 0.24 | 0.27 | 0.08 | 0.18 | 0.015 | 0.002 | 0.039 | 0.0003 | 0.000 | 0.011 | 0.0087 | 0.001 |
| Carbon Equivalent = 0.501 | | | | | | | | | | | | | | | | |

| Heat Number | Sample No. | MECHANICAL PROPERTIES | | | | | (Tensiles test date 08/16/17) | | Bend | WUT |
|----------------|---------------|-----------------------|-------------------|-------------------|------------------|--|-------------------------------|--|------|-------|
| | | Yield (Psi) | Ultimate (Psi) | Elongation (%) | Reduction (%) | | | | | |
| 594643 | 01 | 67804 | 96380 | 15.0 | | | | | OK | 0.663 |
| | | (MPa) 467.5 | 664.5 | | | | | | | |
| 594643 | 02 | 61540 | 96040 | 14.5 | | | | | OK | 0.662 |
| | | (MPa) 424.3 | 662.2 | | | | | | | |

All melting and manufacturing processes of the material subject to this test certificate occurred in the United States of America.
ERMS also certifies this material to be free from Mercury contamination.

This material has been produced, tested and conforms to the requirements of the applicable specifications. We hereby certify that the above test results represent those contained in the records of the Company.

Methods used: ASTM A370, A510, A615, A706.

Material test report shall not be reproduced except in full, without approval of the company.

Bryce Lakamp
Process Control Engineer

Figure C-19. No. 4 Rebar Mill Certification, Test No. N2BR-1

NUCOR
Nucor Steel Nebraska

Mill Certification
05/09/2017

MTR#: 16101
Lot #: 10088665421
2911 E NUCOR ROAD
PO BOX 308
NORFOLK, NE 68701 US
402-644-0200
Fax: 402-644-0329

Sold To: KING STEEL CORPORATION
5225 E COOK RD
GRAND BLANC, MI 48439 US

Ship To: KING STEEL WAREHOUSE
4608 S 25TH ST
NORFOLK, NE 68701 US

| | | | |
|---------------------------|-------------------------------------|----------------------|----------------|
| Customer P.O. | 022420-MS-T | Sales Order # | 10003125 - 1,2 |
| Product Group | Wire Rod - Industrial Quality | Product # | 1005146 |
| Grade | 1010M1 | Lot # | 10088665421 |
| Size | 0.594" | Heat # | 100886654 |
| BOL # | BOL-113346 | Load # | 16101 |
| Description | WR:Q RD 0.594" 1010M1 COIL 4300 lbs | Customer Part # | |
| Production Date | 05/04/2017 | Qty Shipped LBS | 156830 |
| Product Country Of Origin | United States | Qty Shipped EA | 38 |
| Original Item Description | | Original Item Number | |

I hereby certify that the material described herein has been manufactured in conformance with the specifications and standards listed above and that it satisfies these requirements.

Melt Country of Origin : United States

Melting Date: 04/30/2017

| | | | | | | | | | | | |
|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|-------|-------|
| C (%) | Mn (%) | P (%) | S (%) | Si (%) | Ni (%) | Cr (%) | Mo (%) | Cu (%) | Ti (%) | V (%) | B (%) |
| 0.12 | 0.51 | 0.008 | 0.026 | 0.15 | 0.08 | 0.10 | 0.03 | 0.23 | 0.000 | 0.002 | 0.000 |
| As (%) | Sn (%) | Al (%) | Pb (%) | Ca (%) | | | | | | | |
| 0.002 | 0.008 | 0.00 | 0.000 | 0.000 | | | | | | | |

Reduction Ratio: 158.38 : 1

Other Test Results

Yield (PSI) : 49200

Tensile (PSI) : 83800

Elongation in 8" (%) : 27.0

Comments:

All manufacturing processes of the steel materials in this product, including melting, have been performed in the United States.
All products produced are weld free.
Mercury, in any form, has not been used in the production or testing of this material.
Test conform to ASTM A29-15, ASTM E416 and ASTM E1019-reheated grades or applicable customer requirements.
All material melted at Nucor Steel Nebraska is produced in an Electric Arc Furnace.
Semi-Cast
ISO-17025 LAB accreditation cert available upon request.
Exporting Country: USA
Sales@nucor.com

NBMG-10 January 1, 2012

Jim Hill, Division Metallurgist

Page 1 of 1

Figure C-20. 5/8-in. Dia. 14-in. Long Bolt Mill Certification, Test No. N2BR-1

CERTIFICATE OF COMPLIANCE

ROCKFORD BOLT & STEEL CO.
126 MILL STREET
ROCKFORD, IL 61101
815-968-0514 FAX# 815-968-3111

CUSTOMER NAME: TRINITY INDUSTRIES

CUSTOMER PO: 183621

SHIPPER #: 060458
DATE SHIPPED: 05/11/2017

LOT#: 29783-B

SPECIFICATION: ASTM A307, GRADE A MILD CARBON STEEL BOLTS

| | | | |
|------------------|-----------------------------|-----------------|--------|
| TENSILE: | SPEC: 60,000 psi*min | RESULTS: | 72,977 |
| | | | 72,530 |
| HARDNESS: | 100 max | | 84.70 |
| | | | 85.00 |

*Pounds Per Square Inch.

COATING: ASTM SPECIFICATION F-2329 HOT DIP GALVANIZE
ROGERS GALVANIZE: 29783-B

CHEMICAL COMPOSITION

| MILL | GRADE | HEAT# | C | Mn | P | S | Si |
|-------|-------|------------|-----|-----|------|------|-----|
| NUCOR | 1010 | DL16102715 | .11 | .45 | .004 | .018 | .13 |

7,875 PCS 5/8" X 10" GUARD RAIL BOLT
P/N 3500G

WE HEREBY CERTIFY THE ABOVE BOLTS HAVE BEEN MANUFACTURED BY ROCKFORD BOLT AND STEEL AT OUR FACILITY IN ROCKFORD, ILLINOIS, USA. THE MATERIAL USED WAS MELTED AND MANUFACTURED IN THE USA. WE FURTHER CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIALS SUPPLIER, AND THAT OUR PROCEDURES FOR THE CONTROL OF PRODUCT QUALITY ASSURE THAT ALL ITEMS FURNISHED ON THIS ORDER MEET OR EXCEED ALL APPLICABLE TESTS, PROCESS, AND INSPECTION REQUIREMENT PER ABOVE SPECIFICATION.

STATE OF ILLINOIS
COUNTY OF WINNEBAGO
SIGNED BEFORE ME ON THIS

11th DAY OF May 20 17

Merry F. Shane

Linda Melomas
APPROVED SIGNATORY

5/11/17
DATE




Figure C-21. 5/8-in. Dia. 10-in. Long Bolt Certificate of Compliance, Test No. N2BR-1

10016
Bennett Bolt
38196

Conformance Certificate

Issued to:



AUTO BOLT
QUALITY BOLT MAKING
SINCE 1948

Bennett Bolt Works, Inc.

Report Number: PS31836AH
Date of Testing: 09/01/17
Lot Number: 31836AH-1
Lot Quantity: 192,761
Page: 1 of 5

| | | |
|--|-----------------------|-----------------------------|
| Cust part # 62C125BSP3H | Cust po # 6014494 | Auto Bolt part # GARD7125 |
| Description: GARD 5/8-11x1-1/4, ASTM 307A, Hot dip galvanized, Head - ABN/307A/USA/Lot Id, Oval Shoulder Splice Bolt | | |
| Mechanical and Material Requirements: ASTM A307A | | |
| Finish Specification: HOT DIP GALVANIZED PER ASTM A 153/F2329 OR ASTM A 123 | | |
| Material Grade: 1015-US | Heat Number: 20455760 | CERT ATTACHED |
| Hardness: 69-100 HRB | Case Depth: NA | |
| Surface Hardness: NA | | |
| Tensile Test per: SAE J 429 | ASTM F606 | ASTM F 606M ISO-898-1 OTHER |
| Tensile Test Requirements: 60,000 PSI Min | N/A | Method: Axial |


| Test results using sampling plan ASME / ASTM B18.18.2M | | | | | | | | |
|--|--------|--------|--------|--------|--------|---|---|---|
| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| Hardness HRB | 83.0 | 82.0 | 83.0 | 81.0 | 82.0 | | | |
| | | | | | | | | |
| Ultimate Tensile in PSI | 80,163 | 74,309 | 79,787 | 80,066 | 80,243 | | | |
| | | | | | | | | |

Visual Inspection: 100 Samples were inspected for surface discontinuities per the above mentioned specification.

* Denotes tests sub-contracted to an outside accredited laboratory or results provided by vendor.

Amendments: n-a

www.autobolt.net
4740 Manufacturing Ave
Cleveland, OH 44135

APPROVAL: 

QUALITY MANAGER:
ASSIGNED SIGNATORY: X

THE AUTO BOLT COMPANY IS AN ISO-9001-2008 CERTIFIED COMPANY. CERTIFICATE # US04/3795
THIS TEST REPORT RELATES ONLY TO SAMPLES TESTED AND IS THE CONFIDENTIAL PROPERTY OF OUR CUSTOMER. ANY REPRODUCTION OR DISTRIBUTION, IN WHOLE OR IN PART, WITHOUT OUR WRITTEN PERMISSION, IS STRICTLY PROHIBITED.
THIS PRODUCT MANUFACTURED IN THE UNITED STATES OF AMERICA.

FORM # 8.2.4-1
ISSUE DATE JAN 31, 2005 REV. E
Removed SGS logo 4-10-2007

Figure C-22. 5/8-in. Dia. 1 1/4-in. Long Heavy Hex Head Bolt Certificate of Conformance, Test No. N2BR-1

CERTIFICATION

DATE: 4/3/2017

CUSTOMER

Bennett Bolt Works, Inc.
12 Elbridge Street
Jordan, NY 13080

DESCRIPTION

Nut Guardrail 5/8-11 + .031
A563 GrA HDG
EFG PART NUMBER: T3400

CUSTOMER P.O.

6015438 BLANKET

LOT NUMBER

0068078-124590

MATERIAL

1018

CUSTOMER PART NUMBER

62CNDROH



INVOICE

58432

SHIP DATE

4/3/2017

HEAT NUMBER

20479830

QUANTITY

36000

HARDNESS: B 85.4

PROOF LOAD: 5 samples passed at 75,000 psi min.

PLATING: Hot Dip Galvanized - Pass

All parts processed Mercury free and without Welds.

We hereby certify that to our actual knowledge the information contained herein is correct. We also certify that all parts substantially conform to SAE, ASTM, or customer specifications as agreed upon. The product has been manufactured and tested in accordance with our Quality Assurance manual. The above data accurately represents values provided by our suppliers or values generated in the EFG – Berea Plant laboratory. All manufacturing processes for these parts occurred in the United States of America.

This document may only be reproduced without alteration and only for the purpose of certifying the same or lesser quantity of the product specified here.

The recording of false, fictitious or fraudulent statements or entries on this document may be punishable as a felony under Federal Statutes.

A handwritten signature in cursive script that reads 'Joe Kilpatrick'.

Joe Kilpatrick

Quality Assurance Technician

ENGINEERED FASTENING SOLUTIONS

Figure C-23. 5/8-in. Dia. 1 1/4-in. Long Heavy Hex Head Nut Certificate of Conformance, Test No. N2BR-1



FONTANA FASTENERS
P L A N T F R A N K F O R T L E

TEST REPORT

Operations Center
3281 West County Road 0 NS
Frankfort, IN 46041-8966
T. 765.654.0477
F. 765.654.0857

| | |
|---------------|-------------|
| Ship Date | |
| Certification | 542314*15*1 |
| Report Date | 12-28-16 |

| | |
|----------|----------|
| Cust PO | U39876 |
| Lot Nbr | 776663 |
| Quantity | 1000 |
| Mfg Date | 11-04-16 |

BRIGHTON-BEST INTL SUWANEE GA
250 HORIZON DRIVE
SUWANEE, GA 30024

| PART INFORMATION | | | |
|------------------|---|--------------|------------------------------------|
| Part Number | 480144 | Finish | HOT DIP ZINC PER ASTM A153 CLASS C |
| Description | 5/8-11 X 5 F3125 A325-1 HEAVY HEX STRUCTURAL DOUBLE MADE IN USA | Head Marking | A325 LE USA |

| RAW MATERIAL ANALYSIS | | | | | | | |
|-----------------------|----------------|-------------|------|------------|-------------|-------------|---------|
| Steel Heat Nbr | Steel Supplier | Steel Grade | Code | Element | Rqd Min Pct | Rqd Max Pct | Percent |
| CR10456700-41 | Charter Steel | 30MnB3 | C | Carbon | 0.30 | 0.33 | 0.33 |
| | | | Mn | Manganese | 0.80 | 0.95 | 0.93 |
| | | | P | Phosphorus | 0.000 | 0.020 | 0.007 |
| | | | S | Sulfur | 0.000 | 0.015 | 0.007 |
| | | | Si | Silicon | 0.150 | 0.250 | 0.230 |
| | | | Ni | Nickel | 0.00 | 0.10 | 0.04 |
| | | | Cr | Chromium | 0.10 | 0.20 | 0.15 |
| | | | Mo | Molybdenum | 0.00 | 0.04 | 0.02 |
| | | | Cu | Copper | 0.00 | 0.15 | 0.08 |
| | | | Al | Aluminum | 0.020 | 0.050 | 0.024 |
| | | | B | Boron | 0.0010 | 0.0030 | 0.0028 |
| | | | Ti | Titanium | 0.010 | 0.050 | 0.020 |

| |
|--|
| Certification test results include those reported by the following laboratories: |
| Charter Steel, A2LA, 01-31-17 |
| Fontana Fasteners, Inc., ISO17025-A2LA Cert#0122.02, 05-31-18 |

| MECHANICAL PROPERTIES | | | | | | |
|-----------------------|-----------------------|--------|--------|---------|---------|--|
| Wedge Angle | 10 | | | | | |
| Proof Load | 19200/85000 (lbs/Psi) | | | | | |
| Test Performed | Required | High | Low | Average | Samples | |
| Tensile, PSI | 120000 / 160000 | 143000 | 143000 | 143000 | 4 | |
| Proof Load Elongation | 0.0000 / 0.0005 | 0.0002 | 0 | 0.0001 | 3 | |
| Superficial R30N | 45 / 54 | 46 | 45 | 46 | 4 | |
| Core Hardness, HRC | 25 / 34 | 30 | 27 | 29 | 4 | |

Figure C-24. 5/8-in. Dia. 5-in. Long Heavy Hex Head Bolt Material Certification, Test No. N2BR-1



FONTANA FASTENERS
PLANT FRANKFORT LE

TEST REPORT

Operations Center
3281 West County Road 0 NS
Frankfort, IN 46041-8966
T. 765.654.0477
F. 765.654.0857

| | |
|---------------|-------------|
| Ship Date | |
| Certification | 542314*15*1 |
| Report Date | 12-28-16 |

| | |
|----------|----------|
| Cust PO | U39876 |
| Lot Nbr | 776663 |
| Quantity | 1000 |
| Mfg Date | 11-04-16 |

BRIGHTON-BEST INTL SUWANEE GA
250 HORIZON DRIVE
SUWANEE, GA 30024

| PART INFORMATION | | | |
|------------------|---|--------------|------------------------------------|
| Part Number | 480144 | Finish | HOT DIP ZINC PER ASTM A153 CLASS C |
| Description | 5/8-11 X 5 F3125 A325-1 HEAVY HEX STRUCTURAL DOUBLE MADE IN USA | Head Marking | A325 LE USA |


| RAW MATERIAL ANALYSIS | | | | | | | |
|-----------------------|----------------|-------------|------|------------|-------------|-------------|---------|
| Steel Heat Nbr | Steel Supplier | Steel Grade | Code | Element | Rqd Min Pct | Rqd Max Pct | Percent |
| CR10456700-41 | Charter Steel | 30MnB3 | C | Carbon | 0.30 | 0.33 | 0.33 |
| | | | Mn | Manganese | 0.80 | 0.95 | 0.93 |
| | | | P | Phosphorus | 0.000 | 0.020 | 0.007 |
| | | | S | Sulfur | 0.000 | 0.015 | 0.007 |
| | | | Si | Silicon | 0.150 | 0.250 | 0.230 |
| | | | Ni | Nickel | 0.00 | 0.10 | 0.04 |
| | | | Cr | Chromium | 0.10 | 0.20 | 0.15 |
| | | | Mo | Molybdenum | 0.00 | 0.04 | 0.02 |
| | | | Cu | Copper | 0.00 | 0.15 | 0.08 |
| | | | Al | Aluminum | 0.020 | 0.050 | 0.024 |
| | | | B | Boron | 0.0010 | 0.0030 | 0.0028 |
| | | | Ti | Titanium | 0.010 | 0.050 | 0.020 |

| |
|--|
| Certification test results include those reported by the following laboratories: |
| Charter Steel, A2LA, 01-31-17 |
| Fontana Fasteners, Inc., ISO17025-A2LA Cert#0122.02, 05-31-18 |

| MECHANICAL PROPERTIES | | | | | | |
|-----------------------|-----------------------|--------|--------|---------|---------|--|
| Wedge Angle | 10 | | | | | |
| Proof Load | 19200/85000 (lbs/Psi) | | | | | |
| Test Performed | Required | High | Low | Average | Samples | |
| Tensile, PSI | 120000 / 160000 | 143000 | 143000 | 143000 | 4 | |
| Proof Load Elongation | 0.0000 / 0.0005 | 0.0002 | 0 | 0.0001 | 3 | |
| Superficial R30N | 45 / 54 | 46 | 45 | 46 | 4 | |
| Core Hardness, HRC | 25 / 34 | 30 | 27 | 29 | 4 | |

Figure C-25. 5/8-in. Dia. 5-in. Long Heavy Hex Head Nut Material Certification, Test No. N2BR-1

Job Material Certification Page 3 of 4



Vulcan
THREADED PRODUCTS, INC.

Vulcan Threaded Products
10 Cross Creek Trail
Pelham, AL 35124
Tel (205) 620-5100
Fax (205) 620-5150

JOB MATERIAL CERTIFICATION

Job No: **542344** Job Information Certified Date: 8/18/17

Containers: S12833344 S12833366 S12833557 S12833725 S12833952 S12833953 S12847504

Customer: Conklin and Conklin Ship To: 34201 Seventh Street
Union City, CA 94587

Vulcan Part No: BAR B7 .7987x144 SC
Customer Part No: RAWSTEEL-798-B
Customer PO No: 018290 Shipped Qty: 16341 lbs
Order No: 326755 Line No: 1

Note:

Applicable Specifications

| Type | Specification | Rev | Amend | Option |
|------------|------------------------|------|-------|--------|
| | ASTM F1554 Gd 105 S4 | 2015 | | |
| | ASTM F1554 Gr 105 | 2015 | | |
| Heat Treat | ASME SA-193/SA-193M B7 | 2013 | | |
| | ASTM A193 B7 | 2016 | | |
| Quality | EN 10204 3.1 | 2004 | | |

Test Results

See following pages for tests

Certified Chemical Analysis

Heat No: 10406110 Origin: USA

| C | Mn | P | S | Si | Cr | Mo | Ni | V | Cu |
|---------|---------|-------|-------|--------|--------|------|------|-------|---------|
| 0.410 | 0.87 | 0.007 | 0.025 | 0.28 | 0.31 | 0.21 | 0.06 | 0.003 | 0.13 |
| Al | Nb | Sn | Ti | N | B | DI | RR | G.S. | Macro S |
| 0.028 | 0.001 | 0.008 | 0.002 | 0.0070 | 0.0001 | 5.23 | 54.1 | Fine | 2 |
| Macro R | Macro C | J1 | J2 | J3 | J4 | J5 | J6 | J7 | J8 |
| 2 | 2 | 57 | 57 | 57 | 57 | 57 | 57 | 56 | 55 |
| J9 | J10 | J12 | J14 | J16 | J18 | J20 | J24 | J28 | J32 |
| 54 | 52 | 50 | 48 | 46 | 45 | 44 | 42 | 40 | 38 |

Notes

Material was manufactured, tested and inspected in accordance with Vulcan Threaded Products Inc. Quality Assurance Program and Manual Rev. A, dated 8/23/11. Processed material is Quenched and Tempered - Stress Free. No weld repair performed on the material. No Mercury used in the production of this material. Melted and Manufactured in the USA.
Depth of decarburization meets ASTM A962/A962M-16b spec requirements
Document is in accordance with EN 10204 - 3.1B of 2004 (3.1).

PORTLAND BOLT
PO 34081
INV 75014
50 7/8" X 144" B7 ATR, BLK 1OF2
JANUARY 26, 2018


19571 7/8 B7 5105 ATR

Pls 8/18/17 7:58 AM vulc.mgr Page 1 of 2

SEP 27 2017

https://www.plexonline.com/2c198e84-2955-405d-9c9d-45872c8b79e3/Sales/Report_Job_Cert.asp?Mode... 9/21/2017

Figure C-26. 7/8-in. 24-in. Long Threaded Material Certification, Test No. N2BR-1

| | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|--|---------------------------|---------------|--------------------------|----------------|---|----------------|------------------------|----------------|----------------|----------------|----------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----|----|--|----------|--|--|--|
|  | | | | Product Inspection Report | | | | Shanghai autocraft Co., Ltd. 168 Nanlu Highway, Nanhui Industrial Zone, Shanghai 201300, China Tel: +86 21 3818 1100 | | | | | | | | | | | | | | | | | | | |
| Confirm Item | | ■ Appearance | | ■ Size | | ■ Material | | ■ (ES) | | | | Confirmation | | | | | | | | | | | | | | | |
| Part Name | | Heavy Hex Structural Bolt | | Part Number | | 0129028B0 | | Customer | | AF-FAST | | | | Custo mer | | Inspection | | | | Check | | | | Approval | | | |
| Part Size | | 7/8-9UNC*2" | | Quantity | | 3375PCS | | Lot/Order No. | | 180083637 B14017826 | | | | | | | | | | | | | | | | | |
| REFE. STD | | ASME B 18.2.6 ASTM A325 | | Sampling plan | | B18.18 | | Heat Number | | 331313371 | | | | Suppli er | | 李沙沙 | | | | 雷武 | | | | 左加林 | | | |
| Product Description | | Dimensions according to ANSI/ASME B18.2.6 Mechanical properties according to ASTM A325 | | | | Manufacturing date | | 2014.4.28 | | | | ■ Accept | | | | ___ Reject | | | | | | | | | | | |
| 序号 No. | Item | | Standard | | Sample Qty | Testing Value | | | | | | | | | | | | | | | | | | Result | | | |
| | | | | | | X ₁ | X ₂ | X ₃ | X ₄ | X ₅ | X ₆ | X ₇ | X ₈ | X ₉ | X ₁₀ | X ₁₁ | X ₁₂ | X ₁₃ | X ₁₄ | X ₁₅ | | | | | | | |
| 1 | Head Mark | | ATC A325 | | 29pcs | ATC A325 | | | | | | | | | | | | | | | | | | OK | | | |
| 2 | Width across flats | | 1.394"-1.438" (35.41~36.52) | | 5pcs | 1.406 | 1.408 | 1.407 | 1.406 | 1.407 | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 3 | Width across corners | | 1.589"-1.660" (40.37~42.16) | | 5pcs | 1.603 | 1.604 | 1.610 | 1.603 | 1.609 | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 4 | true position of head with shank | | 0.086" MAX (2.18 MAX) | | 5pcs | 0.010 | 0.008 | 0.010 | 0.012 | 0.010 | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 5 | Head height | | 0.531"-0.563 (13.49~14.30) | | 5pcs | 0.555 | 0.545 | 0.553 | 0.548 | 0.546 | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 6 | total runout of bearing surface with shank | | 0.025" MAX (0.63 MAX) | | 5pcs | 0.011 | 0.010 | 0.007 | 0.009 | 0.006 | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 7 | Overall length | | 1.81"-2.00" (45.98~50.80) | | 15pcs | 1.974 | 1.957 | 1.973 | 1.963 | 1.962 | 1.966 | 1.972 | 1.957 | 1.969 | 1.972 | 1.975 | 1.960 | 1.966 | 1.976 | 1.958 | --- | OK | | | | | |
| 8 | Grip length | | 0.277" MAX (7.05 MAX) | | 15pcs | 0.261 | 0.254 | 0.249 | 0.259 | 0.261 | 0.251 | 0.253 | 0.256 | 0.252 | 0.247 | 0.251 | 0.256 | 0.247 | 0.246 | 0.263 | --- | OK | | | | | |
| 9 | Incomplete threads length | | 0.22" MAX (5.64 MAX) | | 5pcs | 0.173 | 0.165 | 0.163 | 0.171 | 0.176 | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 10 | Bearing thickness | | 0.015"-0.035" (0.39~0.88) | | 5pcs | 0.022 | 0.020 | 0.017 | 0.017 | 0.019 | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 11 | Bearing dia. | | Φ1.297" MIN (Φ32.87 MIN) | | 5pcs | 1.300 | 1.300 | 1.300 | 1.300 | 1.302 | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 12 | Under head Radius | | R0.031"-0.062" (R0.79~1.57) | | 5pcs | 0.050 | 0.044 | 0.048 | 0.048 | 0.040 | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 13 | major dia. | | Φ0.8592"-0.8951" (Φ21.83~22.73) | | 15pcs | 0.883 | 0.881 | 0.882 | 0.884 | 0.882 | 0.883 | 0.882 | 0.884 | 0.883 | 0.882 | 0.882 | 0.883 | 0.883 | 0.881 | 0.884 | --- | OK | | | | | |
| 14 | Hardness (Per standard ASTM F606-13) | | 25-34 HRC | | 15pcs | 29.0 | 29.5 | 29.5 | 29.0 | 28.5 | 29.5 | 30.0 | 29.0 | 29.5 | 29.5 | 29.0 | 30.0 | 28.5 | 29.5 | 29.0 | --- | OK | | | | | |
| 15 | Wedge Tensile Strength (Per standard ASTM F606-13) | | 120,000 psi MIN (825MPa) MIN | | 5pcs | 134725 | 135353 | 135128 | 135395 | 134398 | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 16 | Stress under proof load (Per standard ASTM F606-13) | | 85,000 psi (585MPa) | | 5pcs | 4.0um | 5.0um | 4.0um | 4.5um | 3.0um | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 17 | Decarburization and microstructure (ASTM F2328-11) | | high temper M Complete decarburized depth: 0.015mm Non-decarburized height: 0.86mm min | | 5pcs | OK | OK | OK | OK | OK | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 18 | surface discontinuities | | ASTM F788-13 | | 5pcs | OK | OK | OK | OK | OK | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | --- | OK | | | | | |
| 19 | Coating thickness (ASTM A153-05) | | 53um MIN | | 15pcs | 65.2 | 73.2 | 64.1 | 66.3 | 64.3 | 63.8 | 70.4 | 72.5 | 65.5 | 73.1 | 73.3 | 71.8 | 71.0 | 70.4 | 68.7 | --- | OK | | | | | |
| 20 | Appearance | | Gray, Hot dip galvanized | | 29pcs | Gray, Hot dip galvanized | | | | | | | | | | | | | | | | | | OK | | | |
| 备注 Note | | | | | | | | | | | | | | | | | | | | | | | | | | | |


ATC-QR-QAD824-1-013(A1)

Figure C-27. 7/8-in. Dia. 2-in. Long Heavy Hex Head Bolt Material Certification, Test No. N2BR-1

Wecall Inc.



P.O. Box 39 • 64 Penniman Rd. • Orwell, OH 44076
(440) 437-8202 • Fax: (440) 437-8208
Fastener Insignia: 01OH

Record of Conformance

| | | | | | | | |
|--|--|--|--------------------------------------|--------|--------|-------|--------|
| Sold To: Portland Bolt & Mfg. Co., Inc 3441 NW Guam St. Portland OR 97210 | | Shipped To: Portland Bolt & Mfg. Co., Inc 3441 NW Guam St. Portland OR 97210 | | | | | |
| Customer PO Number 31472 | Order Date 18-Jul-17 | Order Quantity 100 | Customer Part Number 19502 | | | | |
| Fastener Type Coupling Nut | Description 1-1/2" Hex x 3" Long | Thread Description 7/8" - 9 UNC O/S RH | | | | | |
| Fastener Specification ASTM A563 Gr DH | Coating Specification ASTM F2329 | Fastener Lot Number 4878 | | | | | |
| Raw Material Lot Code 21787-1 | Raw Material Grade ASTM A108 Gr 4140 | Heat Number NF100884291 | | | | | |
| Cold Finish Source Nucor | Cold Finish Country USA | Melt Source Nucor Bar NE | Melt Country USA | | | | |
| Heat Analysis per Material Supplier: | | | | | | | |
| %C | %MN | %P | %S | %SI | %CR | %NI | %MO |
| 0.430% | 0.910% | 0.011% | 0.023% | 0.250% | 0.990% | 0.06% | 0.170% |
| Heat Treatment Process: | | | | | | | |
| Harden @ 1550 F for 2 Hrs. Oil Quench | | | | | | | |
| Temper @ 1175 F for 2.5 Hrs. Air Cool | | | | | | | |
| Test #1 Proof Load | Test #2 Hardness | | Test #3 | | | | |
| Results Pass | Results Pass | | Results | | | | |
| <p>We certify that this data is a true representation of information provided by our material supplier and testing laboratory and that these fasteners were manufactured, sampled, tested and inspected in accordance with the specifications listed.</p> <p>These fasteners were manufactured and tested in the USA, from steel which was melted and manufactured in the USA.</p> <p> Paul Doherty Wecall Inc.</p> | | | | | | | |

24-Jul-17

Figure C-28. 7/8-in. Diameter Heavy Hex Coupling Nut Certificate of Conformance, Test No. N2BR-1

| | | | | | |
|--|----------------|--|--|--------------------------------|-------------------------------|
|  UNYTITE INC. INNOVATIVE FASTENING SYSTEMS | | Unytite, Inc. One Unytite Drive Peru, IL 61354 Tel 815-224-2221 Fax 815-224-3434 | | INSPECTION CERTIFICATE | |
| Job No: 26357 | | Job Information | | Certified Date: 8/31/17 | |
| Customer: Customer PO No: Lot Number: 26357-6214369204 | | | Ship To: Shipped Qty: | | |
| Part Information | | | | | |
| Part No: A563 7/8-9 +0.022 DH HHN HDG BLUE DYE-0 | | | | | |
| Description: ASTM A563 HHN, Grade DH, Hot Dipped Galv, Blue Dye Manufactured Quantity: 33,763 | | | | | |
| Applicable Specifications | | | | | |
| Specification | | Amend | | Specification | |
| ASME B1.1 | | 2003 | | ASME B18.2.2 | |
| ASME B18.2.6 | | 2010 | | ASTM A563 | |
| ASTM F2329 | | 2013 | | ASTM F606/606M | |
| ASTM F812/F812M | | 2012 | | 2014 | |
| Test Results Test No: 15662 Test: A563 DH Mechanical Properties | | | | | |
| Description | Hardness (HRC) | Tempering Temp (800 degree F Min) | Proof Load (Pass/Fail) (ASTM Min) | Shape & Dimension ASME B18.2.2 | Thread Precision ASME B18.1.1 |
| Sample Inspection | 27.95 | 1,175 | 69,200 | Pass | Pass |
| Certified Chemical Analysis | | | | | |
| Heat No | Grade | Manufacturer | Origin | C | Mn |
| 6214369204 | 1045 | Gerdau Ameristeel | USA | 0.4400 | 0.7200 |
| | | | | P | S |
| | | | | 0.007 | 0.0270 |
| | | | | Si | Cr |
| | | | | 0.2100 | 0.1800 |
| | | | | Ni | Cu |
| | | | | 0.0700 | 0.1300 |
| Notes | | | | | |
| All tests are in accordance with the latest revisions of the methods prescribed in the applicable SAE and ASTM Specifications. The samples tested conform the specifications as described/listed above and were manufactured free of mercury contamination and there is no welding performed in the production of the products. No heats to which Bismuth, Selenium, Tellurium, or Lead was intentionally added have been used to produce products. The steel was melted and manufactured in the U.S.A. and the product was manufactured and tested in the U.S.A. We certify that this data is true representation of information provided by the material supplier and our testing laboratory. This certified material test report relates only to the items listed on this document and may not be reproduced except in full. | | | | | |
| OFFICIAL SEAL JEAN MARGHERIO NOTARY PUBLIC - STATE OF ILLINOIS MY COMMISSION EXPIRES:10/18/17 | | |  Savage, Dan - Supervisor, Quality Date: 8/31/17 | | |

Plex 8/31/17 2:53 PM dsavage Page 1

Figure C-29. 7/8-in. Diameter Heavy Hex Nut Material Certification, Test No. N2BR-1



GEM-YEAR TESTING LABORATORY CERTIFICATE OF INSPECTION

MANUFACTURER : GEM-YEAR INDUSTRIAL CO., LTD.
ADDRESS : NO.8 GEM-YEAR
ROAD,E.D.Z.,JIASHAN,ZHEJIANG,P.R.CHINA

Tel: (0573)84185001(48Lines)
Fax: (0573)84184488 84184567
DATE : 2017/12/04

PURCHASER : FASTENAL COMPANY PURCHASING
PO. NUMBER : 110207371

PACKING NO : GEM160426014
INVOICE NO : GEM/PNL-160512WI-1

COMMODITY : FINISHED HEX NUT GR-A
SIZE : 1-8 NC

PART NO : 36119
SAMPLING PLAN :
ASME B18.18-2011(Category.2)/ASTM F1470-2012

LOT NO : 1N1640157
SHIP QUANTITY : 10,800 PCS

HEAT NO : 15306714-3

LOT QUANTITY 27,604 PCS

MATERIAL : X1008A

HEADMARKS :

FINISH : PLAIN

MANUFACTURE DATE : 2016/04/26

COUNTRY OF ORIGIN : CHINA

PERCENTAGE COMPOSITION OF CHEMISTRY:ACCORDING TO ASTM A563-2015

| Chemistry | AL% | C% | MN% | P% | S% | SI% |
|--------------|--------|--------|--------|--------|--------|--------|
| Spec. : MIN. | | | | | | |
| MAX. | | 0.5800 | | 0.1300 | 0.2300 | |
| Test Value | 0.0340 | 0.0700 | 0.2700 | 0.0100 | 0.0090 | 0.0400 |

DIMENSIONAL INSPECTIONS ACCORDING TO ASME B18.2.2-2015

SAMPLED BY : ZHANG XIA

| INSPECTIONS ITEM | SAMPLE | SPECIFIED | ACTUAL RESULT | ACC. | REJ. |
|-------------------------|--------|------------------------------------|--------------------|------|------|
| WIDTH ACROSS CORNERS | 4PCS | 1.6530-1.7320 inch | 1.6740-1.6770 inch | 4 | 0 |
| FIM | 15PCS | ASME B18.2.2-2015 Max. 0.0270 inch | 0.0140-0.0210 inch | 15 | 0 |
| THICKNESS | 4PCS | 0.8310-0.8870 inch | 0.8600-0.8640 inch | 4 | 0 |
| WIDTH ACROSS FLATS | 4PCS | 1.4500-1.5000 inch | 1.4570-1.4610 inch | 4 | 0 |
| SURFACE DISCONTINUITIES | 29PCS | ASTM F812-2012 | PASSED | 29 | 0 |
| THREAD | 15PCS | GAGING SYSTEM 21 | PASSED | 15 | 0 |

MECHANICAL PROPERTIES : ACCORDING TO ASTM A563-2015

SAMPLED BY : GDAN LIAN

| INSPECTIONS ITEM | SAMPLE | TEST METHOD | REF | SPECIFIED | ACTUAL RESULT | ACC. | REJ. |
|------------------|--------|----------------|-----|-------------|---------------|------|------|
| CORE HARDNESS | 15PCS | ASTM F606-2014 | | 68-107 HRB | 80-82 HRB | 15 | 0 |
| PROOF LOAD | 4PCS | ASTM F606-2014 | | Min. 90 KSI | OK | 4 | 0 |

WE CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL SUPPLIER AND OUR TESTING LABORATORY .WHICH ACCREDITED BY ISO/IEC17025(CERTIFICATE NUMBER:3358.01)
WE CERTIFY THAT THE PRODUCTS SUPPLIED ARE IN COMPLIANCE WITH THE REQUIREMENTS OF THE ORDER

Quality Supervisor:

Figure C-30. 1-in. Diameter Hex Nut Material Certification, Test No. N2BR-1



STELFAST[®] INC.

22979 Stelfast Parkway
Strongsville, Ohio 44149

R#16-0217

BCT Hex Nuts

December 2015 SMT

Fastenal part#36713

Control# 210101523

CERTIFICATE OF CONFORMANCE


DESCRIPTION OF MATERIAL AND SPECIFICATIONS

- Sales Order #: 129980
- Part No: AFH2G0625C
- Cust Part No: 36713
- Quantity (PCS): 1200
- Description: 5/8-11 Fin Hx Nut Gr2 HDG/TOS 0.020
- Specification: SAE J995(99) - GRADE 2 / ANSI B18.2.2
- Stelfast I.D. NO: 595689-O201087
- Customer PO: 210101523
- Warehouse: DAL

The data in this report is a true representation of the information provided by the material supplier certifying that the product meets the mechanical and material requirements of the listed specification. This certificate applies to the product shown on this document, as supplied by STELFAST INC. Alterations to the product by our customer or a third party shall render this certificate void.

This document may only be reproduced unaltered and only for certifying the same or lesser quantity of the product specified herein. Reproduction or alteration of this document for any other purpose is prohibited.

Stelfast certifies parts to the above description. The customer part number is only for reference purposes.


David Biss
Quality Manager

December 07, 2015

Page 1 of 1

Figure C-31. 5/8-in. Dia. Hex Nut Certificate of Conformance, Test No. N2BR-1



No. 4682 P. 3

Certificate of Compliance

Sold To:

UNL TRANSPORTATION

Purchase Order:

Job:

TL-2 and Bullnose

Invoice Date:

03/27/2018

THIS IS TO CERTIFY THAT WE HAVE SUPPLIED YOU WITH THE FOLLOWING PARTS.
THESE PARTS WERE PURCHASED TO THE FOLLOWING SPECIFICATIONS.

5 PCS 7/8"-9 x 8" ASTM A307 Grade A Hot Dipped Galvanized Hex Bolt SUPPLIED UNDER OUR TRACE NUMBER lln35042 AND UNDER PART NUMBER 92005

20 PCS 7/8"-9 Hot Dip Galvanized Finish Grade A Finished Hex Nut SUPPLIED UNDER OUR TRACE NUMBER 110254885 AND UNDER PART NUMBER 36717

5 PCS 7/8"-9 x 8" ASTM A307 Grade A Hot Dipped Galvanized Hex Bolt SUPPLIED UNDER OUR TRACE NUMBER lln35042 AND UNDER PART NUMBER 92005


5 PCS 7/8"-9 x 8" ASTM A307 Grade A Hot Dipped Galvanized Hex Bolt SUPPLIED UNDER OUR TRACE NUMBER lln35042 AND UNDER PART NUMBER 92005

5 PCS 7/8"-9 x 8" ASTM A307 Grade A Hot Dipped Galvanized Hex Bolt SUPPLIED UNDER OUR TRACE NUMBER lln35042 AND UNDER PART NUMBER 92005

This is to certify that the above document is true
and accurate to the best of my knowledge.



Fastenal Account Representative Signature



Printed Name

4/12/18

Date

Please check current revision to avoid using obsolete copies.

This document was printed on 04/12/2018 and was current at that time.

Fastenal Store Location/Address

3201 N. 23rd Street STE 1
LINCOLN, NE 68521
Phone #: (402)476-7900
Fax #: 402/476-7958

Page 1 of 1

Figure C-32. 7/8-in. Dia. 8-in. Long Hex Head Bolt and Nut Certificate of Compliance, Test No. N2BR-1

CERTIFIED MATERIAL TEST REPORT FOR ASTM A307, GRADE A - MACHINE BOLTS

FACTORY: NINGBO ECONOMIC & TECHNICAL DEVELOPMENT REPORT DATE:2016/12/29
ZONE YONGGANG FASTENERS CO., LTD. R#17-507 H#816070039
ADDRESS: FuShan South Road No.17, BeiLun NingBo China BCT Cable Bracket Bolts
MANUFACTURE DATE:2016/12/2
TEL#(852)25423366
CUSTOMER: FASTENAL MFG LOT NUMBER:M-2016HT927-9
SAMPLE SIZE: ACC.TO Dimension:ASME B18.18-11;Mechanical Properties:ASTM F1470-12
MANU QTY: 4800PCS SHIPPED QTY: 4800PCS
SIZE: 5/8-11X1 1/2 HDG
HEADMARKS: 307A PLUS NY PO NUMBER:220023115
PART NO:1191919

STEEL PROPERTIES:
MATERIAL TYPE:Q195 HEAT NUMBER: 816070039

| | | | | |
|----------------------|---------|----------|----------|----------|
| CHEMISTRY SPEC: | C %*100 | Mn%*100 | P %*1000 | S %*1000 |
| Grade A ASTM A307-12 | 0.29max | 1.20 max | 0.04max | 0.15max |
| TEST: | 0.07 | 0.28 | 0.016 | 0.003 |

| DIMENSIONAL INSPECTIONS | Unit:inch | SPECIFICATION: ASME B18.2.1 - 2012 | | |
|-------------------------|------------------------------|------------------------------------|------|------|
| CHARACTERISTICS | SPECIFIED | ACTUAL RESULT | ACC. | REJ. |
| VISUAL | ASTM F788-2013 | PASSED | 22 | 0 |
| THREAD | ASME B1.1-2003,3A GO,2A NOGO | PASSED | 15 | 0 |
| WIDTH FLATS | 0.906-0.938 | 0.915-0.928 | 4 | 0 |
| WIDTH A/C | 1.033-1.083 | 1.048-1.057 | 4 | 0 |
| HEAD HEIGHT | 0.378-0.444 | 0.394-0.424 | 4 | 0 |
| THREAD LENGTH | 1.420-1.560 | 1.435-1.541 | 15 | 0 |
| LENGTH | 1.420-1.560 | 1.435-1.541 | 15 | 0 |

| MECHANICAL PROPERTIES: | SPECIFICATION: ASTM A307-2012 GR-A | | | |
|------------------------|------------------------------------|-------------------------------|------------------|-----------|
| CHARACTERISTICS | TEST METHOD | SPECIFIED | ACTUAL RESULT | ACC. REJ. |
| CORE HARDNESS : | ASTM F606-2014 | 69-100 HRB | 76-79 HRB | 4 0 |
| WEDGE TENSILE: | ASTM F606-2014 | Min 60 KSI | 65-69 KSI | 4 0 |
| CHARACTERISTICS | TEST METHOD | SPECIFIED | ACTUAL RESULT | ACC. REJ. |
| COATINGS OF ZINC: | | SPECIFICATION:ASTM F2329-2013 | | |
| HOT DIP GALVANIZED | ASTM B568-98(2104) | Min 0.0017" | 0.0017" -0.0018" | 4 0 |

ALL TESTS IN ACCORDANCE WITH THE METHODS PRESCRIBED IN THE APPLICABLE
ASTM SPECIFICATION. WE CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF
INFORMATION PROVIDED BY THE MATERIAL SUPPLIER AND OUR TESTING LABORATORY.

Maker's ISO# 00109Q16722R3M/3302

NINGBO ECONOMIC & TECHNICAL DEVELOPMENT
ZONE YONGGANG FASTENERS CO., LTD
(SIGNATURE) (NAME OF MANUFACTURER)

Figure C-33. 5/8-in. Dia. 1 1/2-in. Long Hex Head Bolt Certificate of Conformance, Test No. N2BR-1

JINAN STAR FASTENER CO., LTD
NO.75 CUIPING STREET PINGYIN JINAN CHINA
TEL: 0086 531 87896380 FAX: 0086 531 87871032
E-mail: zhangyuhua@star-fastener.com
CERTIFICATE OF INSPECTION
HY038.1.3-12

Manufacturing Date: 2016-7-10

DATE: 2016-7-17

| | | | | | | | | | | |
|---|---|---------------------|-----------------|----------|-------------------|-----------------------|-----------|------------|-------|--|
| Customer Part Number客户编码 | 91830 | | | | | | | | | |
| Customer Control (PO) Number客户订单号 | 120263056 | | | | | | | | | |
| Product Description产品描述 | 5/16-18x1-1/4 307A G | | | | | | | | | |
| Surface Condition表面处理 | HDG | | | | | | | | | |
| Head Marking头部标记 | 307A and 01RL | | | | | | | | | |
| Lot Size (Manufactured QTY)生产数量 | 17870pcs | | | | | | | | | |
| Lot Size (QTY Shipped)装运数量 | 17860pcs | | | | | | | | | |
| Lot Number订单号 | FAS16161 | | | | | | | | | |
| Mechanical properties机械性能要求 | ASTM A307-2014 GrA | | | | | | | | | |
| Material type原材料名称: | Q235 | | | | Heat Number | | G4604921 | | | |
| | C% | Mn% | Si% | S% | P% | Ni% | Cr% | | Cu% | |
| Chemical composition化学成份:标准 | max0.33 | max1.25 | | max0.051 | max0.041 | | | | | |
| Chemical composition化学成份:实测值 | 0.14 | 0.49 | 0.17 | 0.019 | 0.026 | 0.008 | 0.034 | | 0.007 | |
| Sampling Plan Used 使用的抽样方案 | Dimensional as per ASME B18.18-2011/Mechanical Property as per F1470-2012 | | | | | | | | | |
| Specification技术要求: | specification 检测标准 | Test method 检测方法 | Standard 标准值 | 单位 | Test value 实测值 | Sampling Plan 抽样方案 | ACC 合格 | REJ 不合格 | | |
| Width across Flat对边尺寸 | ASME B18.2.1-2012 | | 0.484-0.500 | in | 0.488-0.491 | 5/0 | 5 | 0 | | |
| Width across Corners对角尺寸 | ASME B18.2.1-2012 | | 0.552-0.577 | in | 0.568-0.571 | 5/0 | 5 | 0 | | |
| Height高度 | ASME B18.2.1-2012 | | 0.195-0.235 | in | 0.205-0.209 | 5/0 | 5 | 0 | | |
| Length总长度 | ASME B18.2.1-2012 | | 1.21-1.27 | in | 1.249-1.251 | 15/0 | 15 | 0 | | |
| Radius under head头下R角 | ASME B18.2.1-2012 | | 0.01-0.03 | in | 0.012-0.014 | 15/0 | 15 | 0 | | |
| Head Chamfer头部顶圆角度 | ASME B18.2.1-2012 | | 15-30° | ° | 22.5-22.7 | 5/0 | 5 | 0 | | |
| Concentricity 同轴度 | ASME B18.2.1-2012 | | 0.03 | in | 0.011-0.013 | 5/0 | 5 | 0 | | |
| Max Distance from under head to thread 头下间距max | ASME B18.2.1-2012 | | 0.139 | in | 0.106-0.108 | 15/0 | 15 | 0 | | |
| Major 大径 | ANSI B1.1-2003 | | 0.303-0.311 | in | 0.305-0.306 | 15/0 | 15 | 0 | | |
| Thread 螺纹 | ANSI B1.1-2003 | | NUT GO | | NUT GO | 15/0 | 15 | 0 | | |
| Core Hardness芯部硬度 | ASTM A307-2014 | ASTM F606-2016 | 69-100 | HRB | 91.5-93.3 | 15/0 | 15 | 0 | | |
| Tensile Strength抗拉强度 | ASTM A307-2014 | ASTM F606-2016 | min60 | KSI | 89.3-91.5 | 5/0 | 5 | 0 | | |
| Plating thickness镀层厚度 | ASTM F2329-2013 | | 0.002 | in | 0.0030-0.0047 | 29/0 | 29 | 0 | | |
| Appearance外观 | ASTM F788-2013 | | Visual | | OK | 29/0 | 29 | 0 | | |

Parts are manufactured and tested according to above specification, we certify that this is a true representation of information provided by manufacturer
产品是按照上述要求进行生产和检测的, 我们证明厂家提供的信息是真实的

Signature: Fu Yan Jun
Title: Quality Manager

The requirements are fulfilled
Inspector (终检员): 马付彬

Figure C-34. ⁵/₁₆-in. 1¹/₄-in. Long Hex Head Bolt Material Certification, Test No. N2BR-1

**Certified Material Test Report to BS EN 10204-2004 3.1
FOR ASTM A563, GRADE A HEX FIN NUTS**

FACTORY: IFI & Morgan Ltd, Haiyan Office
ADDRESS: Haiyan, Zhejiang, China

DATE: 29.Oct.2014

MFG LOT NUMBER: GL14023-2

CUSTOMER: FASTELNAL

PO NUMBER:120200536

SAMPLE PLAN : ACC. TO ASME B18.18 - 2011

SIZE: 5/16"-18 HDG QNTY: 75000 PCS

PART NO: 1136703

STEEL PROPERTIES

STEEL GRADE: Q195

HEAT NUMBER: 183425

CHEMISTRY SPEC:

| C %*100 | Mn%*100 | P %*1000 | S %*1000 |
|---------|---------|----------|----------|
| 0.55max | min | 0.12max | 0.15max |
| 0.09 | 0.41 | 0.022 | 0.035 |

TEST:

DIMENSIONAL INSPECTIONS

SPECIFICATION: ASME B18.2.2-2010

| CHARACTERISTICS | TEST METHOD | SPECIFIED | ACTUAL RESULT | ACC. | REJ. |
|-----------------|--------------------|-------------|---------------|------|------|
| APPEARANCE | ASTM F812/F812M-07 | | PASSED | 100 | 0 |
| THREAD | ASME B1.3 | | PASSED | 32 | 0 |
| WIDTH A/F | | 0.500-0.489 | 0.497-0.491 | 32 | 0 |
| WIDTH A/C | | 0.577-0.557 | 0.571-0.563 | 8 | 0 |
| HEIGHT | | 0.273-0.258 | 0.269-0.260 | 8 | 0 |
| MARK | NO MARKING | | PASSED | 100 | 0 |

MECHANICAL PROPERTIES: 1/4" to 1 1/2"

SPECIFICATION: ASTM A563-07a GR-A

| CHARACTERISTICS | TEST METHOD | SPECIFIED | ACTUAL RESULT | ACC. | REJ. |
|-----------------|-----------------|---------------------|---------------|------|------|
| HARDNESS : | ASTM F606-2010a | B68-C32 Max(107HRB) | 86-88HRB | 8 | 0 |
| PROOF LOAD : | ASTM F606-2010a | Min80 Ksi | PASSED | 4 | 0 |

| CHARACTERISTICS | TEST METHOD | SPECIFIED | ACTUAL RESULT | ACC. | REJ. |
|--------------------|---------------|-------------|---------------|------|------|
| HOT DIP GALVANIZED | ASTM F2329-05 | MIN 0.0017" | 0.0021" | 4 | 0 |

ALL TESTS IN ACCORDANCE WITH THE METHODS PRESCRIBED IN THE APPLICABLE ASTM OR SAE SPECIFICATION. WE CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL SUPPLIER AND OUR TESTING LABORATORY.


(SIGNATURE OF Q.A/ LAB MGR.)
(NAME OF MANUFACTURER)

Figure C-35. 5/16-in. Hex Nut Material Certification, Test No. N2BR-1



Certificate of Compliance

600 N County Line Rd
Elmhurst IL 60126-2081
630-600-3600
chi.sales@mcmaster.com

University of Nebraska
Midwest Roadside Safety Facility
M W R S F
4630 Nw 36TH St
Lincoln NE 68524-1802
Attention: Shaun M Tighe
Midwest Roadside Safety Facility

Purchase Order
E000357170

Order Placed By
Shaun M Tighe

McMaster-Carr Number
2098331-01

Page 1 of 1

| Line | Product | Ordered | Shipped |
|------|--|------------|---------|
| 1 | 97812A109 Steel Double-Headed Nail Size 16D, 3" Length, .16" Shank Diameter, 200 Pieces/Pack, Packs of 5 | 5 Packs | 5 |

Certificate of compliance

This is to certify that the above items were supplied in accordance with the description and as illustrated in the catalog. Your order is subject only to our terms and conditions, available at www.mcmaster.com or from our Sales Department.


Sarah Weinberg
Compliance Manager

Figure C-36. 16D Double Head Nail Certificate of Compliance, Test No. N2BR-1



SPS Coil Processing Tulsa
5275 Bird Creek Ave.
Port of Catoosa, OK 74015

METALLURGICAL TEST REPORT

PAGE 1 of 1
DATE 07/12/2017
TIME 18:07:21
USER J.DUBOIS

S
O
L
D
T
O

S
H
I
P
T
O

17238
Longview Warehouse
4750 West Marshall Ave
LONGVIEW TX 75604

Washers

| Order | Material No. | Description | Quantity | Weight | Customer Part | Customer PO | Ship Date |
|---------------|--------------|-----------------------------------|----------|--------|---------------|-------------|------------|
| 40288806-0030 | 80117296TM | 11GA 72 X 96 A1011-CS-TYB TEMP HS | 21 | 5,040 | | | 07/12/2017 |

Chemical Analysis

| Heat No. | Vendor | STEEL DYNAMICS COLUMBUS | DOMESTIC | MILL | STEEL DYNAMICS COLUMBUS | Melted and Manufactured in the USA | | | | | | | | | |
|----------|-----------|-------------------------|----------|---------|-------------------------|------------------------------------|------------|--------|--------|----------|----------|----------|-----------|----------|--------|
| Carbon | Manganese | Phosphorus | Sulphur | Silicon | Nickel | Chromium | Molybdenum | Boron | Copper | Aluminum | Titanium | Vanadium | Columbium | Nitrogen | Tin |
| 0.0500 | 0.3200 | 0.0100 | 0.0030 | 0.0200 | 0.0300 | 0.0500 | 0.0100 | 0.0001 | 0.1100 | 0.0220 | 0.0020 | 0.0020 | 0.0030 | 0.0063 | 0.0060 |

Mechanical / Physical Properties

| Mill Coil No. | Tensile | Yield | Elong | Rckwl | Grain | Charpy | Charpy Dr | Charpy Sz | Temperature | Olsen |
|------------------|---------|----------|-------|-------|-------|--------|-----------|-----------|-------------|-------|
| 17B759735 | | | | | | | | | | |
| Batch 0004845086 | 21 EA | 5,040 LB | | | | | | | | |

THE CHEMICAL, PHYSICAL, OR MECHANICAL TESTS REPORTED ABOVE ACCURATELY REFLECT INFORMATION AS CONTAINED IN THE RECORDS OF THE CORPORATION.
The material is in compliance with EN 10204 Section 4.1 Inspection Certificate Type 3.1

Figure C-37. 1 $\frac{3}{4}$ -in. x 1 $\frac{3}{4}$ -in. x $\frac{1}{8}$ -in. Square Washer, Test No. N2BR-1

Apr. 12. 2018 4:32PM Fastenal-NELIN
FASTENAL®

No. 4682 P. 2

Certificate of Compliance

Sold To:

UNL TRANSPORTATION

Purchase Order:

Job:

TL-2 and Bullnose

Invoice Date:


03/27/2018


THIS IS TO CERTIFY THAT WE HAVE SUPPLIED YOU WITH THE FOLLOWING PARTS.
THESE PARTS WERE PURCHASED TO THE FOLLOWING SPECIFICATIONS.

40 PCS 7/8" x 2.250" OD Low Carbon Hot Dipped Galvanized Finish Steel USS General Purpose Flat Washer SUPPLIED UNDER
OUR TRACE NUMBER 170077928 AND UNDER PART NUMBER 33187

This is to certify that the above document is true
and accurate to the best of my knowledge.


Fastenal Account Representative Signature


Printed Name


Date

Please check current revision to avoid using obsolete copies.

This document was printed on 04/12/2018 and was current at that
time.

Fastenal Store Location/Address

3201 N. 23rd Street STE 1
LINCOLN, NE 68521
Phone #: (402)476-7900
Fax #: 402/476-7958

Page 1 of 1

Figure C-38. 7/8-in. Diameter Plain Round Washer Certificate of Compliance, Test No. N2BR-1

| CUSTOMER NAME | | CUSTOMER ORDER NUMBER | | | | DATE | | |
|---|--------|---|-----|------|------|--------------------|------|---------------|
| Portland Bolt & Mfg. Co. | | 30701 | | | | 11/30/2017 | | |
| PART NUMBER - CUSTOMER LOT NO. | | LOT NUMBER | | | | QUANTITY | | |
| 7/8" F436 Hdg 16447 | | 0917-627 | | | | 2,400 | | |
| STEEL GRADE | HEAT | C | MN | P | S | SI | AL | REVISION |
| | 173583 | .52 | .82 | .012 | .002 | .239 | .027 | ASTM F-436-10 |
| SPECIFICATION | | ACTUAL | | | | GAUGE | | |
| O.D - 1.718 - 1.782 | | 1.722 - 1.725 | | | | CALIPER | | |
| I.D - .938 - .970 | | .948 - .951 | | | | CALIPER, PIN GAUGE | | |
| THICKNESS- .136 - .177 | | .142 - .145 | | | | MICROMETER | | |
| FLAT- Max .010 | | .002 | | | | CALIPER | | |
| HEAT TREAT - 38 - 45 HRC | | 41 - 44 | | | | | | |
| PLATING- | | See Attached Cert | | | | | | |
| OTHER | | N/A | | | | | | |
| | | | | | | | | |
| <p>WE HEREBY CERTIFY THIS PRODUCT WAS PRODUCED UNDER A ISO-9001:2008 QUALITY ASSURANCE SYSTEM. ISO-9001:2008 CERTIFICATION NUMBER-1265 - DATE OF REGIS. JAN. 3, 2003</p> <p>ALL MATERIALS ARE MADE AND MELTED IN THE U.S.A. THIS PRODUCT WAS MANUFACTURED IN CHESTERFIELD, MICHIGAN, U.S.A. THIS PRODUCT CONFORMS TO ALL REQUIREMENTS FOR WASHERS AS PRODUCED ACCORDING TO A.S.T.M. F-436-10. THE ABOVE TEST RESULTS APPLY ONLY TO THE ITEMS TESTED. THIS TEST REPORT MUST NOT BE REPRODUCED EXCEPT IN FULL WITHOUT PRIOR WRITTEN APPROVAL.</p> | | | | | | | | |
| <p>CERTIFIED ISO 9001:</p> | | <p><i>Shirley Mickon</i> AUTHORIZED SIGNATURE</p> | | | | | | |

2017-3008 Rev. 2 11/26/01

Figure C-39. 7/8-in. Diameter Hardened Flat Washer Material Certification, Test No. N2BR-1



Feb 15th 2017

SOLD TO:
GREGORY INDUSTRIES, INC.
4100 13TH ST. SW
CANTON, OH. 44710

SHIP TO:
HIGHWAY – FINISHED GOODS
GREGORY INDUSTRIES, INC.
ATTN: STEVE PENNINGTON
CANTON, OH 44710

R#17-700

CERTIFICATION BCT Cables Yellow Paint

CGLP ORDER# 256284
GREGORY PO# 36454

THIS LETTER AND THE ENCLOSED ATTACHMENTS ARE TO CERTIFY THAT THE
FOLLOWING ITEMS WERE 100% MANUFACTURED IN THE UNITED STATES OF AMERICA.

1,330 PCS, PART# 3012G, 3/4" X 6FT 6IN DOUBLE SWAGE GUARD RAIL ASSEMBLYS.

THEY SHOW THE DOMESTICITY OF ALL MATERIAL USED, 100% MELTED &
MANUFACTURED IN THE USA. THESE ITEMS ARE HOT DIPPED GALVANIZED TO ASTM-153
SPECIFICATIONS AND STANDARDS, GALV PROCESS ALSO TOOK PLACE IN THE U.S.A.

ATTACHMENTS:

(WIRE ROPE) WIRECO WORLD GROUP REEL# 428-671806-1; HEAT#
.15R582807; 16R584001; 72987C; 16R586548; 73253F; 16R588160; 16R584967; 16R585464;
16R586547; 14R574048; 14R371682; 16R586549; 16R586401; (ROCKY MOUNTAIN STEEL /
EVRAZ)

(END FITTINGS) REMLINGER MFG: HEAT#S 75063022; 75062074;
765063075 (GERDAU NORTH AMERICA)

VERY TRULY YOURS

BILL KOTARSKI
GEN MGR CLEV OFFICE

HEADQUARTERS

12801 UNIVERSAL DRIVE
TAYLOR, MI 48180
NEW PH# (734) 947-4000
NEW FAX# (734) 947-4004

FLINT

BRANCH

G2427 E. JUDD ROAD
BURTON, MI 48529
PH# (810) 744-4540
FAX# (810) 744-1588

CLEVELAND

BRANCH

5213 GRANT AVE
CLEVELAND, OH 44105
PH# (216) 641-4100
FAX# (216) 641-1814

Figure C-40. BCT Anchor Cable End Swaged Fitting and 3/4-in. Diameter 6x19 24 1/2-in. Long
IWRC IPS Wire Rope Material Certification, Test No. N2BR-1

GREGORY HIGHWAY PRODUCTS, INC.
4100 13th St. SW
Canton, Ohio 44710


MIDWEST MACHINERY & SUPPLY CO.
P. O. BOX 703
MILFORD, NE 68405

Test Report
Ship Date: 11/17/2017
Customer P.O.: 3515
Shipped to: MIDWEST MACHINERY & SUPPLY CO.
Project:
GHP Order No: 128AA

| HT # code | LOT# | C. | Mn. | P. | S. | Si. | Tensile | Yield | Elong. | Quantity | Class | Type | Description |
|-----------|------|------|------|-------|-------|-------|---------|-------|--------|----------|-------|------|--|
| A74070 | | 0.21 | 0.46 | 0.012 | 0.002 | 0.03 | 76100 | 58800 | 25.2 | 4 | A | 2 | 12GA TB TRANS |
| 4181496 | | 0.24 | 0.84 | 0.014 | 0.01 | 0.01 | 72400 | 44800 | 34 | 4 | | 2 | 5/8IN X 8IN X 8IN BRG. PL |
| 4181489 | | 0.09 | 0.45 | 0.012 | 0.004 | 0.01 | 58000 | 43100 | 27 | 4 | | 2 | 350 STRUT & YOKE |
| 196828BM | | 0.04 | 0.84 | 0.014 | 0.003 | | 76000 | 74000 | 25 | | | 2 | 350 STRUT & YOKE |
| E22985 | | 0.17 | 0.51 | 0.013 | 0.008 | 0.008 | 72510 | 64310 | 29.5 | 4 | | 2 | 2IN X 5 1/2IN PIPE SLEEVE |
| 811T08220 | | 0.22 | 0.81 | 0.013 | 0.006 | 0.005 | 71412 | 56323 | 35 | 8 | | 2 | 3/16IN X 6IN X 8IN X 6FT OIN TUBE SLEEVE |


All Galvanizing has occurred in the United States
All steel used in the manufacture is of Domestic Origin, "Made and Melted in the United States"
All Steel used meets Title 23CFR 635.410 - Buy America
All Guardrail and Terminal Sections meets AASHTO M-180, All structural steel meets AASHTO M-183 & M270
All Bolts and Nuts are of Domestic Origin
All material fabricated in accordance with Nebraska Department of Transportation
All controlled oxidized/corrosion resistant Guardrail and terminal sections meet ASTM A606, Type 4.

By: 

STATE OF OHIO: COUNTY OF STARK
Sworn to and subscribed before me, a Notary Public, by
Andrew Afta this 21 day of November, 2017

Notary Public, State of Ohio

James P. Dehnke
Notary Public, State of Ohio
My Commission Expires 10-19-2019

Figure C-41. 8-in. x 8-in. x 5/8-in. Anchor Bearing Plate Material Certification, Test No. N2BR-1


EXLTUBE

1000 BURLINGTON STREET, NORTH KANSAS CITY, MO 64116 1-816-474-5210 TOLL FREE 1-800-892-TUBE

STEEL VENTURES, LLC dba EXLTUBE

Certified Test Report

| | | | |
|--|--|---|---------------------|
| Customer: SPS - New Century 401 New Century Parkway NEW CENTURY KS 66031-1127 | Size: 02.375 | Customer Order No: 4500269918 | Date: 07/26/2016 |
| | Gauge: .154 | Delivery No: 62799116 Lead No: 3774661 | |
| | Specifications: ASTM A500-13 Gr.B/C, ASTM A53-12 Gr.B BNT*, ASME SA53 Gr.B BNT* | | |

| | | | | |
|-------------------|----------------------|------------------------|---------------------------------|--|
| Heat No A79999 | Yield KSI 63.2 | Tensile KSI 67.3 | Elongation % 2 inch 31.00 | R#17-175 H#A79999 BCT Post Sleeves QTY 8 Oct 2016 SMT |
|-------------------|----------------------|------------------------|---------------------------------|--|

| | | | | | | | | | | |
|-------------------|-------------|--------------|-------------|-------------|--------------|--------------|--------------|--------------|--------------|-------------|
| Heat No A79999 | C 0.0700 | Mn 0.8400 | P 0.0110 | S 0.0040 | Si 0.0200 | Cu 0.1500 | Ni 0.0500 | Cr 0.0600 | Mo 0.0200 | V 0.0010 |
|-------------------|-------------|--------------|-------------|-------------|--------------|--------------|--------------|--------------|--------------|-------------|

This material was milled & manufactured in the U.S.A.
 We hereby certify that all test results shown in this report are correct as contained in the records of our company. All testing and manufacturing is in accordance to A.S.T.M. parameters encompassed within the scope of the specifications denoted in the specification and grade ties above. This product was manufactured in accordance with your purchase order requirements.
 BNT=Grade B not pressure tested - meets tensile & chemical properties ONLY.

This material has not come into direct contact with mercury, any of its compounds, or any mercury bearing devices during our manufacturing process, testing, or inspections.

This material is in compliance with EN 10204 Section 4.1 Inspection Certificate Type 3.1

This material has passed NDE (eddy current, A309) testing. This material has passed flattening tests.

Tensile test completed using test specimen with 3/4" reduced area.

STEEL VENTURES, LLC dba EXLTUBE



 Jonathan Wolfe
Quality Assurance Manager

Figure C-42. 2 $\frac{3}{8}$ -in. O.D. x 6-in. Long BCT Post Sleeve Material Certification, Test No. N2BR-1

Certified Analysis



Trinity Highway Products, LLC

2548 N.E. 28th St.

Ft Worth, TX

Customer: MIDWEST MACH. & SUPPLY CO.

P. O. BOX 81097

LINCOLN, NE 68501-1097

Project: RESALE

Order Number: 1095199

Customer PO: 2041

BOL Number: 24481

Document #: 1

Shipped To: NE

Use State: KS

As of: 6/20/08

| Qty | Part # Description | Spec | CL | TY | Heat Code/ Heat # | Yield | TS | Rlg | C | Ms | F | S | SI | Ch | Cb | Cr | Va | ACW |
|-----|----------------------------|---------|----|----|-------------------|--------|--------|------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-----|
| 25 | 6G 12X3/8 | M-180 A | | | 24964 | 64,230 | 81,300 | 25.4 | 0.180 | 0.720 | 0.012 | 0.001 | 0.040 | 0.080 | 0.060 | 0.060 | 0.000 | 4 |
| 20 | 701A .25X11.75X16 CAB ANC | A-36 | | | 4153095 | 44,900 | 60,800 | 34.0 | 0.240 | 0.790 | 0.012 | 0.003 | 0.020 | 0.020 | 0.000 | 0.040 | 0.002 | 4 |
| 10 | 742G 60 TUBE SL/18X8X6 | A-500 | | | A8P1160 | 74,000 | 87,000 | 25.2 | 0.050 | 0.670 | 0.013 | 0.005 | 0.030 | 0.220 | 0.000 | 0.060 | 0.021 | 4 |
| 20 | 782G 5/8"X3"X8" BEAR PL/OF | A-36 | | | 6106195 | 46,700 | 69,900 | 23.5 | 0.190 | 0.830 | 0.010 | 0.005 | 0.020 | 0.230 | 0.000 | 0.070 | 0.006 | 4 |
| 40 | 907G 12/BUFFER/ROLLED | M-180 A | | | L0049 | 54,200 | 73,300 | 25.0 | 0.160 | 0.700 | 0.011 | 0.008 | 0.020 | 0.200 | 0.000 | 0.100 | 0.000 | 4 |

Upon delivery, all materials subject to Trinity Highway Products, LLC Storage Stain Policy No. LG-002.

ALL STEEL USED WAS MELTED AND MANUFACTURED IN USA AND COMPLIES WITH THE BUY AMERICA ACT.

ALL GUARDRAIL MBETS AASHTO M-180, ALL STRUCTURAL STEEL MBETS ASTM A36

ALL OTHER GALVANIZED MATERIAL CONFORMS WITH ASTM-123.

BOLTS COMPLY WITH ASTM A-307 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM A-153, UNLESS OTHERWISE STATED.

NUTS COMPLY WITH ASTM A-563 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM A-153, UNLESS OTHERWISE STATED.

3/4" DIA CABLE 6X19 ZINC COATED SWAGED END AISI C-1035 STEEL ANNEALED STUD 1" DIA ASTM 449 AASHTO M30, TYPE II BREAKING

STRENGTH - 49100 LB

State of Texas, County of Tarrant. Sworn and subscribed before me this 20th day of June, 2008


Notary Public:
Commission ExpiresTrinity Highway Products, LLC
Certified By:

Figure C-43. Anchor Bracket Assembly Material Certification, Test No. N2BR-1

Certified Analysis



Trinity Highway Products, LLC

550 East Robb Ave.

Lima, OH 45801 Phn:(419) 227-1296

Customer: MIDWEST MACH.& SUPPLY CO.

P. O. BOX 703

MILFORD, NE 68405

Project: RESALE

Order Number: 1275017

Prod Ln Grp: 3-Guardrail (Dom)

Customer PO: 3400

BOL Number: 99202

Document #: 1

Shipped To: NE

Use State: NE

Ship Date:

As of: 3/22/17


| Qty | Part # | Description | Spec | CL | TY | Heat Code/ Heat | Yield | TS | Elg | C | Mn | P | S | Si | Cu | Ch | Cr | Va | ACW |
|-----|--------|-------------------------|-------|----|----|-----------------|--------|--------|------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-----|
| 400 | 3380G | 5/8"X1.5" HEX BOLT A307 | HW | | | 0052429-113200 | | | | | | | | | | | | | |
| 600 | 3400G | 5/8"X2" GR BOLT | HW | | | 29221 | | | | | | | | | | | | | |
| 500 | 3480G | 5/8"X8" GR BOLT A307 | HW | | | 29369 | | | | | | | | | | | | | |
| 450 | 3500G | 5/8"X10" GR BOLT A307 | HW | | | 29550-B | | | | | | | | | | | | | |
| 700 | 3540G | 5/8"X14" GR BOLT A307 | HW | | | 29567 | | | | | | | | | | | | | |
| 300 | 3580G | 5/8"X18" GR BOLT A307 | HW | | | 29338 | | | | | | | | | | | | | |
| 600 | 4235G | 3/16"X1.75"X3" WSHR | HW | | | C7001 | | | | | | | | | | | | | |
| 10 | 9852A | STRUT & YOKE ASSY | A-36 | | | 195070 | 52,940 | 69,970 | 31.1 | 0.190 | 0.520 | 0.014 | 0.004 | 0.020 | 0.110 | 0.000 | 0.050 | 0.000 | 4 |
| | 9852A | | A-36 | | | A82292 | 54,000 | 73,300 | 31.0 | 0.200 | 0.460 | 0.010 | 0.003 | 0.020 | 0.150 | 0.000 | 0.060 | 0.001 | 4 |
| | 9852A | | A-36 | | | 645887 | 39,900 | 62,500 | 32.0 | 0.190 | 0.400 | 0.009 | 0.015 | 0.009 | 0.054 | 0.001 | 0.038 | 0.001 | 4 |
| | 9852A | | A-36 | | | 645887 | 39,900 | 62,500 | 32.0 | 0.190 | 0.400 | 0.009 | 0.015 | 0.009 | 0.054 | 0.001 | 0.038 | 0.001 | 4 |
| | 9852A | | HW | | | 15056184 | | | | | | | | | | | | | |
| 20 | 12173G | T12/63/4@1'6.75"/S | | | 2 | L35216 | | | | | | | | | | | | | |
| | | | M-180 | A | 2 | 209331 | 62,090 | 81,500 | 28.1 | 0.190 | 0.720 | 0.013 | 0.002 | 0.020 | 0.110 | 0.000 | 0.070 | 0.002 | 4 |
| | | | M-180 | A | 2 | 209332 | 61,400 | 81,290 | 25.3 | 0.190 | 0.730 | 0.014 | 0.003 | 0.020 | 0.120 | 0.000 | 0.060 | 0.001 | 4 |
| | | | M-180 | A | 2 | 209333 | 61,200 | 80,050 | 25.8 | 0.200 | 0.740 | 0.016 | 0.005 | 0.010 | 0.120 | 0.000 | 0.070 | 0.002 | 4 |



2 of 4

Figure C-44. Ground Strut Assembly Material Certification, Test No. N2BR-1

RM
Ready Mixed Concrete Company
6200 Cornhusker Hwy, Lincoln, NE 68529
Phone: (402) 434-1844 Fax: (402) 434-1877

Customer's Signature: _____

| PLANT | TRUCK | DRIVER | CUSTOMER | PROJECT | TAX | PO NUMBER | DATE | TIME | TICKET |
|--|------------------------|---------------------|---|--------------------------------|-----|--|--|--------------------|---------------------------------------|
| 01 | 0118 | 3058 | 3 | 3 | | TL2 | 3/13/18 | 11:45 AM | 1222277 |
| Customer CIA---MIDWEST ROADSIDE SAFETY | | | Delivery Address 4630 NW 36TH STREET | | | Special Instructions NORTH OF THE GOODYEAR HANGER | | | |
| LOAD QUANTITY | CUMULATIVE QUANTITY | ORDERED QUANTITY | PRODUCT CODE | PRODUCT DESCRIPTION | | UOM | UNIT PRICE | EXTENDED PRICE | |
| 5.50 | 5.50 | 5.50 | 48503000 | PR 8 1/2 SK 3 | | yd | \$134.00 | \$737.00 | |
| | | | | MINIMUM HAUL WINTER SERVICE | | | | \$15.00 \$24.75 | |
| Water Added On Job At Customer's Request: | | SLUMP 4.00 in | Notes: | | | | TICKET SUBTOTAL SALES TAX TICKET TOTAL | | \$776.75 \$0.00 \$776.75 |
|  | | | | | | PREVIOUS TOTAL | | | |
| | | | | | | GRAND TOTAL | | \$776.75 | |

|  CAUTION FRESH CONCRETE KEEP CHILDREN AWAY  | | Terms & Conditions |
|---|--|--|
| <p>Contains Portland cement. Freshly mixed cement, mortar, concrete or grout may cause skin injury. Avoid prolonged contact with skin. Always wear appropriate Personal Protective Equipment (PPE). In case of contact with eyes or skin, flush thoroughly with water. If irritation persists, seek medical attention promptly.</p> | | <p>This concrete is produced with the ASTM standard specifications for ready mix concrete. Strengths are based on a 3' slump. Drivers are not permitted to add water to the mix to exceed this slump, except under the authorization of the customer and their acceptance of any decrease in compressive strength and any risk of loss as a result thereof. Cylinder tests must be handled according to ACI/ASTM specifications and drawn by a licensed testing lab and/or certified technician. Ready Mixed Concrete Company will not deliver any product beyond any curb lines unless expressly told to do so by customer and customer assumes all liability for any personal or property damage that may occur as a result of any such directive. The purchaser's exceptions and claims shall be deemed waived unless made in writing within 3 days from time of delivery. In such a case, seller shall be given full opportunity to investigate any such claim. Seller's liability shall in no event exceed the purchase price of the materials against which any claims are made.</p> |

| MATERIAL | DESCRIPTION | DESIGN QTY | REQUIRED | BATCHED | % VAR | % MOISTURE | ACTUAL WATER |
|----------|---------------|------------|-----------|-----------|--------|------------|--------------|
| G47B | 47B GRAVEL | 1785 lb | 10014 lb | 9980 lb | -0.34% | 2.00% M | 23 gl |
| L47B | 47B ROCK | 777 lb | 4316 lb | 4300 lb | -0.11% | 1.00% M | 5 gl |
| CEM3 | CEMENT TYPE3 | 799 lb | 4395 lb | 4405 lb | 0.24% | | |
| WATER | WATER | 40.2 GL | 198.0 GL | 196.5 GL | -0.72% | | 196.5 gl |
| LRWR | POZZ 322N LOV | 32.00 oz | 176.00 oz | 176.00 oz | 0.00% | | |
| AIR | MICRO AIR 200 | 8.40 oz | 46.20 oz | 46.00 oz | -0.43% | | |

Actual Num Batches: 1 Manual

Load: 20339 lb Design W/C: 0.42 Water/Cement: 0.43 A Design Water: 221.1 gl Actual: 225.1 gl


Slump: 4.00 in # Water in Truck: 0.0 GL Adjust Water: 0.0 GL / Load Trim Water: 0.0 GL / CYDS

Actual W/C Ratio 0.43 Actual Water: 225 gl Batched Cement: 4405 lb Allowable Water: 0 lb To Add: 0.0 gl

Figure C-45. Concrete Deck Material, Test No. N2BR-1

RM
Ready Mixed Concrete Company
6200 Cornhusker Hwy, Lincoln, NE 68529
Phone: (402) 434-1844 Fax: (402) 434-1877

Customer's Signature: _____

| PLANT | TRUCK | DRIVER | CUSTOMER | PROJECT | TAX | PO NUMBER | DATE | TIME | TICKET |
|--|------------------------|---------------------|---|--------------------------------|--|--|------------|---------------------------------------|---------|
| 01 | 0131 | 8890 | 3 | 3 | | TL2 | 3/13/18 | 12:56 PM | 1222285 |
| Customer CIA---MIDWEST ROADSIDE SAFETY | | | Delivery Address 4630 NW 36TH STREET | | | Special Instructions NORTH OF THE GOODYEAR HANGER | | | |
| LOAD QUANTITY | CUMULATIVE QUANTITY | ORDERED QUANTITY | PRODUCT CODE | PRODUCT DESCRIPTION | | UOM | UNIT PRICE | EXTENDED PRICE | |
| 1.00 | 1.00 | 1.00 | 48503000 | PR 8 1/2 SK 3 | | yd | \$134.00 | \$134.00 | |
| | | | | MINIMUM HAUL WINTER SERVICE | | | | \$60.00 \$4.50 | |
| Water Added On Job At Customer's Request: | | SLUMP 4.00 in | Notes: | | TICKET SUBTOTAL SALES TAX TICKET TOTAL | | | \$198.50 \$0.00 \$198.50 | |
|  | | | | | | PREVIOUS TOTAL | | | |
| | | | | | | GRAND TOTAL | | \$198.50 | |

CAUTION FRESH CONCRETE
KEEP CHILDREN AWAY

Contains Portland cement. Freshly mixed cement, mortar, concrete or grout may cause skin injury. Avoid prolonged contact with skin. Always wear appropriate Personal Protective Equipment (PPE). In case of contact with eyes or skin, flush thoroughly with water. If irritation persists, seek medical attention promptly.

Terms & Conditions

This concrete is produced with the ASTM standard specifications for ready mix concrete. Strengths are based on a 3" slump. Drivers are not permitted to add water to the mix to exceed this slump, except under the authorization of the customer and their acceptance of any decrease in compressive strength and any risk of loss as a result thereof. Cylinder tests must be handled according to ACI/ASTM specifications and drawn by a licensed testing lab and/or certified technician.

Ready Mixed Concrete Company will not deliver any product beyond any curb lines unless expressly told to do so by customer and customer assumes all liability for any personal or property damage that may occur as a result of any such directive. The purchaser's exceptions and claims shall be deemed waived unless made in writing within 3 days from time of delivery. In such a case, seller shall be given full opportunity to investigate any such claim. Seller's liability shall in no event exceed the purchase price of the materials against which any claims are made.

| MATERIAL | DESCRIPTION | DESIGN QTY | REQUIRED | BATCHED | % VAR | % MOISTURE | ACTUAL WATER |
|----------|---------------|------------|----------|----------|---------|------------|--------------|
| G47B | 47B GRAVEL | 1785 lb | 1821 lb | 2000 lb | + 9.96% | 2.00% M | 5 gl |
| L47B | 47B ROCK | 777 lb | 785 lb | 780 lb | -0.17% | 1.00% M | 1 gl |
| CEM3 | CEMENT TYPE3 | 799 lb | 799 lb | 810 lb | 1.38% | | |
| WATER | WATER | 40.2 GL | 36.0 GL | 36.0 GL | -0.11% | | 36.0 gl |
| LRWR | POZZ 322N LOV | 32.00 oz | 32.00 oz | 33.00 oz | 3.13% | | |
| AIR | MICRO AIR 200 | 8.40 oz | 8.40 oz | 8.00 oz | -4.76% | | |

Actual Num Batches: 1 Manual

Load: 3893 lb Design W/C: 0.42 Water/Cement: 0.43 A Design Water: 40.2 gl Actual: 41.6 gl

Slump: 4.00 in # Water in Truck: 0.0 GL Adjust Water: 0.0 GL / Load Trim Water: 0.0 GL / CYDS

Actual W/C Ratio 0.43 Actual Water: 42 gl Batched Cement: 810 lb Allowable Water: 0 lb To Add: 0.0 gl

Figure C-46. Concrete Deck Material, Test No. N2BR-1



Ready Mixed Concrete Company
6200 Cornhusker Hwy, Lincoln, NE 68529
Phone: (402) 434-1844 Fax: (402) 434-1877

Customer's Signature: _____

| PLANT | TRUCK | DRIVER | CUSTOMER | PROJECT | TAX | PO NUMBER | DATE | TIME | TICKET |
|--|------------------------|---------------------|---|--------------------------------|-----|----------------------|-----------------|-------------------|----------|
| 4 | 0241 | 6580 | 00003 | 3 | | BUNKY 560-1716 | 2/1/18 | 10:48 AM | 4202504 |
| Customer CIA--MIDWEST ROADSIDE SAFETY | | | Delivery Address 4630 NW 36TH STREET | | | Special Instructions | | | |
| LOAD QUANTITY | CUMULATIVE QUANTITY | ORDERED QUANTITY | PRODUCT CODE | PRODUCT DESCRIPTION | | UOM | UNIT PRICE | EXTENDED PRICE | |
| 2.50 | 2.50 | 2.50 | 470031PF | 47BD (1PF) WO/R | | yd | \$118.91 | \$297.28 | |
| | | | | MINIMUM HAUL WINTER SERVICE | | | | \$45.00 | |
| | | | | | | | | \$11.25 | |
| Water Added On Job At Customer's Request: | | SLUMP 4.00 in | Notes: | | | | TICKET SUBTOTAL | | \$353.53 |
| | | | | | | | SALES TAX | | \$0.00 |
| | | | | | | | TICKET TOTAL | | \$353.53 |
| | | | | | | | PREVIOUS TOTAL | | |
| | | | | | | | GRAND TOTAL | | \$353.53 |

CAUTION FRESH CONCRETE
KEEP CHILDREN AWAY

Contains Portland cement. Freshly mixed cement, mortar, concrete or grout may cause skin injury. Avoid prolonged contact with skin. Always wear appropriate Personal Protective Equipment (PPE). In case of contact with eyes or skin, flush thoroughly with water. If irritation persists, seek medical attention promptly.

Terms & Conditions

This concrete is produced with the ASTM standard specifications for ready mix concrete. Strengths are based on a 3" slump. Drivers are not permitted to add water to the mix to exceed this slump, except under the authorization of the customer and their acceptance of any decrease in compressive strength and any risk of loss as a result thereof. Cylinder tests must be handled according to ACI/ASTM specifications and drawn by a licensed testing lab and/or certified technician. Ready Mixed Concrete Company will not deliver any product beyond any curb lines unless expressly told to do so by customer and customer assumes all liability for any personal or property damage that may occur as a result of any such directive. The purchaser's exceptions and claims shall be deemed waived unless made in writing within 3 days from time of delivery. In such a case, seller shall be given full opportunity to investigate any such claim. Seller's liability shall in no event exceed the purchase price of the materials against which any claims are made.

| MATERIAL | DESCRIPTION | DESIGN QTY | REQUIRED | BATCHED | % VAR | % MOISTURE | ACTUAL WATER |
|----------|------------------|------------|-----------|-----------|--------|------------|--------------|
| G47B | 47B GRAVEL | 1975.0 lb | 5020.2 lb | 5040.0 lb | 0.39% | 1.68% A | 10.0 gl |
| L47B | 47B ROCK | 840.0 lb | 2128.5 lb | 2140.0 lb | 0.16% | 1.36% A | 3.4 gl |
| CEM1PF | 1PF CEMENT | 658.0 lb | 1645.0 lb | 1640.0 lb | -0.30% | | |
| WATER | WATER | 31.6 gl | 68.2 gl | 68.5 gl | -0.74% | | 68.5 gl |
| LRWR | POZZ 322N LOV | 20.0 oz | 50.0 oz | 50.0 oz | 0.00% | | |
| AIR | MB AE 200 air ei | 5.9 oz | 14.8 oz | 14.0 oz | -5.08% | | |

Actual Num Batches: 1 Manual

Load: 9396 lb Design W/C: 0.40 Water/Cement: 0.42 A Design Water: 79.0 gl Actual: 81.9 gl

Slump: 4.00 in # Water in Truck: 0.0 gl Adjust Water: 0.0 gl / Load Trim Water: 0.0 gl / CYDS

Actual W/C Ratio 0.42 Actual Water: 82 gl Batched Cement: 1640 lb Allowable Water: 0 lb To Add: 0.0 gl

Figure C-47. Grade Beam Concrete, Test No. N2BR-1



LINCOLN OFFICE
825 "M" Street Suite 100
Lincoln, NE 68508
Phone: (402) 479-2200
Fax: (402) 479-2276

COMPRESSION TEST OF CYLINDRICAL CONCRETE SPECIMENS - 6x12

ASTM Designation: C 39

Client Name: Midwest Roadside Safety Facility
Project Name: Miscellaneous Concrete Testing
Placement Location: TL2, Test A (Grade Beam)

Date 03-Apr-18

Mix Designation: N/A

Required Strength: N/A

Laboratory Test Data

| Laboratory Identification | Field Identification | Date Cast | Date Received | Date Tested | Days Cured in Field | Days Cured in Laboratory | Age of Test, Days | Length of Specimen, in. | Diameter of Specimen, in. | Cross-Sectional Area, sq.in. | Maximum Load, lbf | Compressive Strength, psi. | Required Strength, psi. | Type of Fracture | ASTM Practice for Capping Specimen |
|---------------------------|----------------------|-----------|---------------|-------------|---------------------|--------------------------|-------------------|-------------------------|---------------------------|------------------------------|-------------------|----------------------------|-------------------------|------------------|------------------------------------|
| URR- 54 | | 2/1/2018 | 4/2/2018 | 4/3/2018 | 60 | 1 | 61 | 12 | 5.98 | 28.09 | 161,742 | 5,760 | | 6 | C 1231 |

1 cc: Ms. Karla Lechtenberg
Midwest Roadside Safety Facility

Remarks:

All concrete test data in this report was produced by Benesch personnel using ASTM Standard Methods and Practices unless otherwise noted.


Test results presented relate only to the concrete sampled by Benesch personnel as referenced above.

This report shall not be reproduced except in full, without the written approval of Alfred Benesch & Company.

Report Number 2147370069

Page 1

Sketches of Types of Fractures



Type 1
Reasonably well-formed cones on both ends, less than 1 in. [25 mm] of cracking through caps



Type 2
Well-formed cone on one end, vertical cracks running through caps, no well-defined cone on other end



Type 3
Columnar vertical cracking through both ends, no well-formed cones



Type 4
Diagonal fracture with no cracking through ends; top with hammer to distinguish from Type 1



Type 5
Side fractures at top or bottom (occur commonly with unbonded caps)



Type 6
Similar to Type 5 but end of cylinder is pointed

**ALFRED BENESCH & COMPANY
CONSTRUCTION MATERIALS LABORATORY**

By Brant Wells
Brant Wells, Field/Lab Operations Manager

Figure C-48. Concrete Grade Beam Material Certification, Test No. N2BR-1



LINCOLN OFFICE
825 "M" Street Suite 100
Lincoln, NE 68508
Phone: (402) 479-2200
Fax: (402) 479-2276

COMPRESSION TEST OF CYLINDRICAL CONCRETE SPECIMENS - 6x12

ASTM Designation: C 39

Client Name: Midwest Roadside Safety Facility

Date 11-Apr-18

Project Name: Miscellaneous Concrete Testing

Placement Location: TL2 Test B Deck

Mix Designation:

Required Strength:

Laboratory Test Data

| Laboratory Identification | Field Identification | Date Cast | Date Received | Date Tested | Days Cured in Field | Days Cured in Laboratory | Age of Test, Days | Length of Specimen, in. | Diameter of Specimen, in. | Cross-Sectional Area, sq.in. | Maximum Load, lbf | Compressive Strength, psi. | Required Strength, psi. | Type of Fracture | ASTM Practice for Capping Specimen |
|---------------------------|----------------------|-----------|---------------|-------------|---------------------|--------------------------|-------------------|-------------------------|---------------------------|------------------------------|-------------------|----------------------------|-------------------------|------------------|------------------------------------|
| URR- 56 | TestB Deck | 3/13/2018 | 4/11/2018 | 4/11/2018 | 29 | 0 | 29 | 12 | 5.99 | 28.15 | 166,071 | 5,900 | | 5 | C 1231 |
| URR- 57 | TestC Deck | 3/13/2018 | 4/11/2018 | 4/11/2018 | 29 | 0 | 29 | 12 | 5.98 | 28.11 | 159,963 | 5,690 | | 4 | C 1231 |

1 cc: Ms. Karla Lechtenberg
Midwest Roadside Safety Facility

Remarks:

All concrete test data in this report was produced by Benesch personnel using ASTM Standard Methods and Practices unless otherwise noted.


Test results presented relate only to the concrete sampled by Benesch personnel as referenced above.

This report shall not be reproduced except in full, without the written approval of Alfred Benesch & Company.

Report Number 2147370078

Page 1

Sketches of Types of Fractures



ALFRED BENESCH & COMPANY
CONSTRUCTION MATERIALS LABORATORY

By Brant Wells
Brant Wells, Field/Lab Operations Manager

Figure C-49. Concrete Deck Material Certification, Test No. N2BR-1

Appendix D. Vehicle Center of Gravity Determination

| | | |
|------------------------|--------------------------|-------------------------------|
| Date: <u>4/12/2018</u> | Test Name: <u>2NBR-1</u> | VIN: <u>1D7RB1DG4BS514230</u> |
| Year: <u>2011</u> | Make: <u>Dodge</u> | Model: <u>Ram 1500</u> |

Vehicle CG Determination

| VEHICLE | Equipment | Weight (lb.) | Vertical CG (in.) | Vertical M (lb.-in.) |
|--|-----------------------------------|--------------|-------------------|----------------------|
| + | Unballasted Truck (Curb) | 5111 | 28 3/8 | 145053.13 |
| + | Hub | 19 | 15 | 285 |
| + | Brake activation cylinder & frame | 7 | 27 | 189 |
| + | Pneumatic tank (Nitrogen) | 28 | 26 | 728 |
| + | Strobe/Brake Battery | 5 | 25 | 125 |
| + | Brake Receiver/Wires | 5 | 51 | 255 |
| + | CG Plate including DAS | 38 | 24 | 912 |
| - | Battery | -46 | 41 | -1886 |
| - | Oil | -13 | 19 | -247 |
| - | Interior | -87 | 32 | -2784 |
| - | Fuel | -166 | 20 | -3320 |
| - | Coolant | -11 | 31 | -341 |
| - | Washer fluid | 0 | 31 | 0 |
| + | Water Ballast (In Fuel Tank) | 63 | 17 | 1071 |
| + | Onboard Supplemental Battery | 12 | 26 | 312 |
| + | Smart Barrier Stuff | 10 | 25 | 250 |
| + | TDAS | 17 | 25 | 425 |
| Note: (+) is added equipment to vehicle, (-) is removed equipment from vehicle | | | | 141027.13 |

| | |
|------------------------------|---------|
| Estimated Total Weight (lb.) | 4992 |
| Vertical CG Location (in.) | 28.2506 |

Vehicle Dimensions for C.G. Calculations

| | |
|--------------------------------|--------------------------------------|
| Wheel Base: <u>140 3/8</u> in. | Front Track Width: <u>67 3/4</u> in. |
| | Rear Track Width: <u>67 3/4</u> in. |

| Center of Gravity | 2270P MASH Targets | Test Inertial | Difference |
|----------------------------|--------------------|---------------|------------|
| Test Inertial Weight (lb.) | 5000 ± 110 | 4999 | -1.0 |
| Longitudinal CG (in.) | 63 ± 4 | 60.878776 | -2.12122 |
| Lateral CG (in.) | NA | -0.386252 | NA |
| Vertical CG (in.) | 28 or greater | 28.25 | 0.25063 |

Note: Long. CG is measured from front axle of test vehicle
Note: Lateral CG measured from centerline - positive to vehicle right (passenger) side

| | Left | Right |
|-------|------|-------|
| Front | 1457 | 1437 |
| Rear | 1123 | 1094 |
| | | |
| FRONT | 2894 | lb. |
| REAR | 2217 | lb. |
| TOTAL | 5111 | lb. |

| | Left | Right |
|-------|------|-------|
| Front | 1451 | 1380 |
| Rear | 1077 | 1091 |
| | | |
| FRONT | 2831 | lb. |
| REAR | 2168 | lb. |
| TOTAL | 4999 | lb. |

Figure D-1. Vehicle Mass Distribution, Test No. N2BR-1

Appendix E. Static Soil Tests




Figure E-1. Soil Strength, Initial Calibration Tests




Figure E-2. Static Soil Test, Test No. N2BR-1

Appendix F. Vehicle Deformation Records




Figure F-1. Floor Pan Deformation Data – Set 1, Test No. N2BR-1




Figure F-2. Floor Pan Deformation Data – Set 2, Test No. N2BR-1

| | | | | | |
|-------|-----------|------------|--------|--------|-------------------|
| Date: | 4/12/2018 | Test Name: | 2NBR-1 | VIN: | 1D7RB1DG4B0514230 |
| Year: | 2011 | Make: | Dodge | Model: | Ram 1500 |

| VEHICLE DEFORMATION | | | | | | | | | | | | | |
|----------------------------------|-------|-----------------------|-----------------------|-----------------------|---------------------|---------------------|---------------------|-----------------------|-----------------------|-----------------------|-------------------------|-----------------------------|---|
| INTERIOR CRUSH - SET 1 | | | | | | | | | | | | | |
| | POINT | Pretest X (in.) | Pretest Y (in.) | Pretest Z (in.) | Posttest X (in.) | Posttest Y (in.) | Posttest Z (in.) | ΔX^A (in.) | ΔY^A (in.) | ΔZ^A (in.) | Total Δ (in.) | Crush ^B (in.) | Directions for Crush ^C |
| DASH (X, Y, Z) | 1 | 37.9 | 0.5 | -27.6 | 38.0 | 0.5 | -27.7 | -0.2 | 0.0 | -0.1 | 0.2 | 0.2 | X, Y, Z |
| | 2 | 38.0 | 11.3 | -27.6 | 38.1 | 11.1 | -27.7 | -0.1 | 0.2 | -0.1 | 0.3 | 0.3 | X, Y, Z |
| | 3 | 38.6 | 26.9 | -26.7 | 38.7 | 26.9 | -26.9 | -0.1 | 0.0 | -0.2 | 0.2 | 0.2 | X, Y, Z |
| | 4 | 32.0 | 0.4 | -21.9 | 32.2 | 0.4 | -21.9 | -0.2 | 0.0 | -0.1 | 0.2 | 0.2 | X, Y, Z |
| | 5 | 35.6 | 11.3 | -24.5 | 35.8 | 11.2 | -24.6 | -0.2 | 0.0 | -0.1 | 0.2 | 0.2 | X, Y, Z |
| | 6 | 36.0 | 27.0 | -24.3 | 36.1 | 27.0 | -24.5 | -0.1 | 0.0 | -0.2 | 0.2 | 0.2 | X, Y, Z |
| SIDE PANEL (Y) | 7 | 42.1 | 33.7 | -4.4 | 42.0 | 33.5 | -4.6 | 0.1 | 0.2 | -0.2 | 0.3 | 0.2 | Y |
| | 8 | 42.6 | 33.7 | -0.1 | 42.5 | 33.6 | -0.3 | 0.0 | 0.1 | -0.2 | 0.3 | 0.1 | Y |
| | 9 | 46.5 | 33.7 | -3.2 | 46.4 | 33.7 | -3.3 | 0.1 | 0.0 | -0.2 | 0.2 | 0.0 | Y |
| IMPACT SIDE DOOR (Y) | 10 | 33.7 | 34.7 | -22.5 | 33.4 | 34.4 | -22.7 | 0.3 | 0.3 | -0.2 | 0.4 | 0.3 | Y |
| | 11 | 23.7 | 34.4 | -22.7 | 23.4 | 34.2 | -22.9 | 0.3 | 0.2 | -0.2 | 0.4 | 0.2 | Y |
| | 12 | 9.5 | 34.1 | -23.0 | 9.2 | 34.0 | -23.1 | 0.2 | 0.1 | -0.1 | 0.3 | 0.1 | Y |
| | 13 | 30.1 | 36.1 | 1.2 | 29.9 | 36.6 | 1.1 | 0.2 | 0.4 | -0.2 | 0.5 | 0.4 | Y |
| | 14 | 22.8 | 35.8 | 1.2 | 22.5 | 35.4 | 1.0 | 0.3 | 0.4 | -0.2 | 0.5 | 0.4 | Y |
| | 15 | 9.5 | 35.1 | 0.9 | 9.3 | 34.8 | 0.8 | 0.3 | 0.3 | -0.1 | 0.4 | 0.3 | Y |
| ROOF - (Z) | 16 | 29.9 | 0.8 | -42.6 | 30.0 | 0.7 | -42.6 | -0.1 | 0.2 | 0.0 | 0.2 | 0.0 | Z |
| | 17 | 29.6 | 6.4 | -42.6 | 29.7 | 6.3 | -42.6 | -0.1 | 0.1 | -0.1 | 0.1 | -0.1 | Z |
| | 18 | 29.0 | 11.3 | -42.5 | 29.1 | 11.2 | -42.6 | -0.1 | 0.1 | 0.0 | 0.2 | 0.0 | Z |
| | 19 | 28.0 | 16.2 | -42.4 | 28.1 | 16.0 | -42.5 | -0.1 | 0.2 | -0.1 | 0.2 | -0.1 | Z |
| | 20 | 26.5 | 21.4 | -42.2 | 26.6 | 21.3 | -42.3 | 0.0 | 0.2 | -0.1 | 0.2 | -0.1 | Z |
| | 21 | 24.1 | 0.4 | -45.2 | 24.2 | 0.2 | -45.3 | -0.1 | 0.2 | 0.0 | 0.2 | 0.0 | Z |
| | 22 | 23.7 | 5.3 | -45.3 | 23.9 | 5.1 | -45.3 | -0.1 | 0.1 | 0.0 | 0.2 | 0.0 | Z |
| | 23 | 23.1 | 10.0 | -45.2 | 23.2 | 9.8 | -45.3 | -0.1 | 0.2 | -0.1 | 0.2 | -0.1 | Z |
| | 24 | 21.8 | 14.9 | -45.2 | 21.9 | 14.8 | -45.3 | 0.0 | 0.2 | -0.1 | 0.2 | -0.1 | Z |
| | 25 | 20.9 | 19.5 | -45.0 | 20.8 | 19.4 | -45.1 | 0.1 | 0.1 | -0.1 | 0.2 | -0.1 | Z |
| | 26 | 21.6 | 0.8 | -45.8 | 21.7 | 0.6 | -45.8 | -0.1 | 0.2 | 0.0 | 0.2 | 0.0 | Z |
| | 27 | 21.2 | 5.3 | -45.8 | 21.2 | 5.2 | -45.8 | 0.0 | 0.2 | 0.0 | 0.2 | 0.0 | Z |
| | 28 | 20.9 | 9.7 | -45.7 | 20.9 | 9.6 | -45.8 | -0.1 | 0.2 | -0.1 | 0.2 | -0.1 | Z |
| | 29 | 19.9 | 14.7 | -45.6 | 20.0 | 14.5 | -45.7 | 0.0 | 0.2 | -0.1 | 0.2 | -0.1 | Z |
| | 30 | 18.8 | 19.2 | -45.4 | 18.7 | 19.0 | -45.5 | 0.0 | 0.2 | -0.1 | 0.2 | -0.1 | Z |
| A-PILLAR Maximum (X, Y, Z) | 31 | 42.4 | 32.4 | -28.4 | 42.5 | 32.4 | -28.6 | 0.0 | 0.0 | -0.2 | 0.2 | 0.0 | Y |
| | 32 | 40.5 | 31.9 | -29.9 | 40.6 | 31.9 | -30.1 | 0.0 | 0.1 | -0.2 | 0.2 | 0.1 | Y |
| | 33 | 38.9 | 31.5 | -31.0 | 39.0 | 31.5 | -31.2 | -0.1 | 0.0 | -0.2 | 0.2 | 0.0 | Y |
| | 34 | 35.9 | 30.8 | -33.7 | 36.0 | 30.8 | -33.9 | -0.1 | 0.0 | -0.2 | 0.2 | 0.0 | Y |
| | 35 | 33.7 | 30.2 | -35.2 | 33.7 | 30.2 | -35.4 | -0.1 | 0.1 | -0.2 | 0.2 | 0.1 | Y |
| | 36 | 31.3 | 29.6 | -36.9 | 31.3 | 29.5 | -37.0 | -0.1 | 0.1 | -0.1 | 0.2 | 0.1 | Y |
| A-PILLAR Lateral (Y) | 31 | 42.4 | 32.4 | -28.4 | 42.5 | 32.4 | -28.6 | 0.0 | 0.0 | -0.2 | 0.2 | 0.0 | Y |
| | 32 | 40.5 | 31.9 | -29.9 | 40.6 | 31.9 | -30.1 | 0.0 | 0.1 | -0.2 | 0.2 | 0.1 | Y |
| | 33 | 38.9 | 31.5 | -31.0 | 39.0 | 31.5 | -31.2 | -0.1 | 0.0 | -0.2 | 0.2 | 0.0 | Y |
| | 34 | 35.9 | 30.8 | -33.7 | 36.0 | 30.8 | -33.9 | -0.1 | 0.0 | -0.2 | 0.2 | 0.0 | Y |
| | 35 | 33.7 | 30.2 | -35.2 | 33.7 | 30.2 | -35.4 | -0.1 | 0.1 | -0.2 | 0.2 | 0.1 | Y |
| | 36 | 31.3 | 29.6 | -36.9 | 31.3 | 29.5 | -37.0 | -0.1 | 0.1 | -0.1 | 0.2 | 0.1 | Y |
| B-PILLAR Maximum (X, Y, Z) | 37 | 0.6 | 27.7 | -39.4 | 0.7 | 27.3 | -39.5 | -0.2 | 0.4 | -0.1 | 0.4 | 0.4 | Y |
| | 38 | 0.9 | 29.0 | -36.2 | 1.1 | 28.6 | -36.2 | -0.1 | 0.4 | -0.1 | 0.4 | 0.4 | Y |
| | 39 | 1.4 | 30.3 | -32.6 | 1.5 | 30.0 | -32.6 | -0.1 | 0.3 | 0.0 | 0.4 | 0.3 | Y |
| | 40 | 1.7 | 31.3 | -29.0 | 1.8 | 30.9 | -29.0 | -0.1 | 0.3 | 0.0 | 0.3 | 0.3 | Y |
| B-PILLAR Lateral (Y) | 37 | 0.6 | 27.7 | -39.4 | 0.7 | 27.3 | -39.5 | -0.2 | 0.4 | -0.1 | 0.4 | 0.4 | Y |
| | 38 | 0.9 | 29.0 | -36.2 | 1.1 | 28.6 | -36.2 | -0.1 | 0.4 | -0.1 | 0.4 | 0.4 | Y |
| | 39 | 1.4 | 30.3 | -32.6 | 1.5 | 30.0 | -32.6 | -0.1 | 0.3 | 0.0 | 0.4 | 0.3 | Y |
| | 40 | 1.7 | 31.3 | -29.0 | 1.8 | 30.9 | -29.0 | -0.1 | 0.3 | 0.0 | 0.3 | 0.3 | Y |

^A Positive values denote deformation as inward toward the occupant compartment, negative values denote deformations outward away from the occupant compartment.

^B Crush calculations that use multiple directional components will disregard components that are negative and only include positive values where the component is deforming inward toward the occupant compartment.

^C Direction for Crush column denotes which directions are included in the crush calculations. If no direction listed, then no intrusion is recorded, and Crush will be 0.

Figure F-3. Occupant Compartment Deformation Data – Set 1, Test No. N2BR-1

| | | | | | |
|-------|-----------|------------|--------|--------|-------------------|
| Date: | 4/12/2018 | Test Name: | 2NBR-1 | VIN: | 1D7RB1DG4B0514230 |
| Year: | 2011 | Make: | Dodge | Model: | Ram 1500 |

VEHICLE DEFORMATION
INTERIOR CRUSH - SET 2

| | POINT | Pretest X (In.) | Pretest Y (In.) | Pretest Z (In.) | Posttest X (In.) | Posttest Y (In.) | Posttest Z (In.) | ΔX^A (In.) | ΔY^A (In.) | ΔZ^A (In.) | Total Δ (In.) | Crush ^B (In.) | Directions for Crush ^C |
|----------------------------------|-------|-----------------------|-----------------------|-----------------------|---------------------|---------------------|---------------------|-----------------------|-----------------------|-----------------------|-------------------------|-----------------------------|---|
| DASH (X, Y, Z) | 1 | 38.1 | 18.3 | -31.8 | 38.3 | 18.5 | -31.8 | -0.2 | -0.2 | -0.1 | 0.3 | 0.3 | X, Y, Z |
| | 2 | 38.7 | 29.1 | -31.8 | 38.9 | 29.1 | -31.9 | -0.2 | 0.0 | -0.1 | 0.3 | 0.3 | X, Y, Z |
| | 3 | 40.0 | 44.7 | -30.9 | 40.2 | 44.8 | -31.1 | -0.2 | -0.1 | -0.2 | 0.3 | 0.3 | X, Y, Z |
| | 4 | 32.2 | 18.5 | -26.0 | 32.5 | 18.6 | -26.1 | -0.3 | -0.1 | -0.1 | 0.3 | 0.3 | X, Y, Z |
| | 5 | 36.3 | 29.2 | -28.7 | 36.6 | 29.3 | -28.8 | -0.3 | -0.1 | -0.1 | 0.3 | 0.3 | X, Y, Z |
| | 6 | 37.5 | 44.9 | -28.5 | 37.7 | 45.0 | -28.7 | -0.2 | -0.1 | -0.2 | 0.3 | 0.3 | X, Y, Z |
| SIDE PANEL (Y) | 7 | 43.8 | 51.2 | -8.6 | 43.8 | 51.3 | -8.8 | 0.0 | 0.0 | -0.2 | 0.2 | 0.0 | Y |
| | 8 | 44.3 | 51.2 | -4.3 | 44.3 | 51.3 | -4.5 | 0.0 | -0.1 | -0.2 | 0.3 | -0.1 | Y |
| | 9 | 48.2 | 51.1 | -7.3 | 48.2 | 51.2 | -7.5 | 0.1 | -0.1 | -0.2 | 0.2 | -0.1 | Y |
| IMPACT SIDE DOOR (Y) | 10 | 35.5 | 52.7 | -26.6 | 35.3 | 52.6 | -26.9 | 0.2 | 0.1 | -0.3 | 0.3 | 0.1 | Y |
| | 11 | 25.5 | 52.8 | -26.9 | 25.3 | 52.8 | -27.2 | 0.2 | 0.0 | -0.3 | 0.4 | 0.0 | Y |
| | 12 | 11.2 | 53.2 | -27.2 | 11.1 | 53.3 | -27.4 | 0.1 | 0.0 | -0.2 | 0.2 | 0.0 | Y |
| | 13 | 31.9 | 54.2 | -3.0 | 31.7 | 54.0 | -3.2 | 0.2 | 0.3 | -0.2 | 0.4 | 0.3 | Y |
| | 14 | 24.6 | 54.3 | -3.0 | 24.4 | 54.1 | -3.3 | 0.2 | 0.2 | -0.3 | 0.4 | 0.2 | Y |
| | 15 | 11.4 | 54.2 | -3.3 | 11.1 | 54.1 | -3.5 | 0.2 | 0.1 | -0.2 | 0.3 | 0.1 | Y |
| ROOF - (Z) | 16 | 30.1 | 19.0 | -46.8 | 30.4 | 19.0 | -46.8 | -0.2 | 0.0 | -0.1 | 0.3 | -0.1 | Z |
| | 17 | 30.1 | 24.6 | -46.7 | 30.3 | 24.6 | -46.8 | -0.2 | -0.1 | -0.1 | 0.2 | -0.1 | Z |
| | 18 | 29.7 | 29.5 | -46.7 | 30.0 | 29.5 | -46.8 | -0.2 | 0.0 | -0.1 | 0.3 | -0.1 | Z |
| | 19 | 29.0 | 34.4 | -46.6 | 29.2 | 34.4 | -46.7 | -0.2 | 0.0 | -0.1 | 0.3 | -0.1 | Z |
| | 20 | 27.7 | 39.7 | -46.4 | 27.9 | 39.7 | -46.6 | -0.2 | 0.0 | -0.2 | 0.2 | -0.2 | Z |
| | 21 | 24.3 | 18.8 | -49.4 | 24.6 | 18.8 | -49.5 | -0.2 | 0.1 | -0.1 | 0.2 | -0.1 | Z |
| | 22 | 24.2 | 23.7 | -49.4 | 24.5 | 23.7 | -49.5 | -0.2 | 0.0 | -0.1 | 0.3 | -0.1 | Z |
| | 23 | 23.8 | 28.5 | -49.4 | 24.0 | 28.4 | -49.5 | -0.2 | 0.1 | -0.1 | 0.2 | -0.1 | Z |
| | 24 | 22.8 | 33.4 | -49.4 | 22.9 | 33.4 | -49.5 | -0.1 | 0.0 | -0.1 | 0.2 | -0.1 | Z |
| | 25 | 22.0 | 38.1 | -49.2 | 22.1 | 38.1 | -49.3 | -0.1 | 0.0 | -0.1 | 0.2 | -0.1 | Z |
| | 26 | 21.8 | 19.3 | -50.0 | 22.0 | 19.3 | -50.0 | -0.2 | 0.0 | -0.1 | 0.2 | -0.1 | Z |
| | 27 | 21.7 | 23.9 | -50.0 | 21.8 | 23.9 | -50.1 | -0.2 | 0.0 | -0.1 | 0.2 | -0.1 | Z |
| | 28 | 21.5 | 28.3 | -49.9 | 21.7 | 28.3 | -50.0 | -0.2 | 0.0 | -0.1 | 0.2 | -0.1 | Z |
| | 29 | 20.8 | 33.3 | -49.8 | 21.0 | 33.2 | -49.9 | -0.2 | 0.1 | -0.1 | 0.2 | -0.1 | Z |
| | 30 | 19.9 | 37.8 | -49.6 | 20.0 | 37.8 | -49.8 | -0.1 | 0.0 | -0.1 | 0.2 | -0.1 | Z |
| A-PILLAR Maximum (X, Y, Z) | 31 | 44.1 | 50.0 | -32.6 | 44.3 | 50.1 | -32.8 | -0.2 | -0.1 | -0.2 | 0.3 | 0.0 | |
| | 32 | 42.2 | 49.6 | -34.1 | 42.3 | 49.7 | -34.3 | -0.2 | -0.1 | -0.2 | 0.3 | 0.0 | |
| | 33 | 40.6 | 49.2 | -35.2 | 40.8 | 49.3 | -35.4 | -0.2 | -0.1 | -0.3 | 0.3 | 0.0 | |
| | 34 | 37.6 | 48.7 | -37.9 | 37.8 | 48.8 | -38.1 | -0.2 | -0.1 | -0.2 | 0.3 | 0.0 | |
| | 35 | 35.3 | 48.2 | -39.4 | 35.5 | 48.3 | -39.6 | -0.2 | -0.1 | -0.2 | 0.3 | 0.0 | |
| | 36 | 32.8 | 47.7 | -41.1 | 33.0 | 47.7 | -41.2 | -0.2 | 0.0 | -0.2 | 0.2 | 0.0 | |
| A-PILLAR Lateral (Y) | 31 | 44.1 | 50.0 | -32.6 | 44.3 | 50.1 | -32.8 | -0.2 | -0.1 | -0.2 | 0.3 | -0.1 | Y |
| | 32 | 42.2 | 49.6 | -34.1 | 42.3 | 49.7 | -34.3 | -0.2 | -0.1 | -0.2 | 0.3 | -0.1 | Y |
| | 33 | 40.6 | 49.2 | -35.2 | 40.8 | 49.3 | -35.4 | -0.2 | -0.1 | -0.3 | 0.3 | -0.1 | Y |
| | 34 | 37.6 | 48.7 | -37.9 | 37.8 | 48.8 | -38.1 | -0.2 | -0.1 | -0.2 | 0.3 | -0.1 | Y |
| | 35 | 35.3 | 48.2 | -39.4 | 35.5 | 48.3 | -39.6 | -0.2 | -0.1 | -0.2 | 0.3 | -0.1 | Y |
| | 36 | 32.8 | 47.7 | -41.1 | 33.0 | 47.7 | -41.2 | -0.2 | 0.0 | -0.2 | 0.2 | 0.0 | Y |
| B-PILLAR Maximum (X, Y, Z) | 37 | 2.1 | 47.2 | -43.6 | 2.4 | 46.9 | -43.8 | -0.3 | 0.2 | -0.2 | 0.4 | 0.2 | Y |
| | 38 | 2.5 | 48.4 | -40.4 | 2.7 | 48.2 | -40.6 | -0.3 | 0.2 | -0.2 | 0.4 | 0.2 | Y |
| | 39 | 3.0 | 49.8 | -36.8 | 3.3 | 49.6 | -36.9 | -0.2 | 0.2 | -0.1 | 0.3 | 0.2 | Y |
| | 40 | 3.4 | 50.7 | -33.2 | 3.5 | 50.5 | -33.3 | -0.2 | 0.1 | -0.1 | 0.3 | 0.1 | Y |
| B-PILLAR Lateral (Y) | 37 | 2.1 | 47.2 | -43.6 | 2.4 | 46.9 | -43.8 | -0.3 | 0.2 | -0.2 | 0.4 | 0.2 | Y |
| | 38 | 2.5 | 48.4 | -40.4 | 2.7 | 48.2 | -40.6 | -0.3 | 0.2 | -0.2 | 0.4 | 0.2 | Y |
| | 39 | 3.0 | 49.8 | -36.8 | 3.3 | 49.6 | -36.9 | -0.2 | 0.2 | -0.1 | 0.3 | 0.2 | Y |
| | 40 | 3.4 | 50.7 | -33.2 | 3.5 | 50.5 | -33.3 | -0.2 | 0.1 | -0.1 | 0.3 | 0.1 | Y |

^A Positive values denote deformation as inward toward the occupant compartment, negative values denote deformations outward away from the occupant compartment.


^B Crush calculations that use multiple directional components will disregard components that are negative and only include positive values where the component is deforming inward toward the occupant compartment.

^C Direction for Crush column denotes which directions are included in the crush calculations. If no direction listed, then no intrusion is recorded, and Crush will be 0.

Figure F-4. Occupant Compartment Deformation Data – Set 2, Test No. N2BR-1

Date: 4/12/2018 Test Name: 2NBR-1 VIN: 1D7RB1DG4BS514230

Year: 2011 Make: Dodge Model: Ram 1500



| | in. | (mm) |
|--|---------|--------|
| Distance from C.G. to reference line - L _{REF} : | 114 1/4 | (2902) |
| Total Vehicle Width: | 76 | (1930) |
| Width of contact and induced crush - Field L: | 54 | (1372) |
| Crush measurement spacing interval (L/5) - I: | 10 3/4 | (273) |
| Distance from center of vehicle to center of Field L - D _{FL} : | 0 | () |
| Width of Contact Damage: | 20 1/2 | (521) |
| Distance from center of vehicle to center of contact damage - D _C : | 48 1/4 | (1226) |


NOTE: Enter "NA" for crush measurement if distance can not be measured (i.e., side of vehicle has been pushed inward)

NOTE: All values must be filled out above before crush measurements are filled out.

| Crush Measurement | | | Lateral Location | | Original Profile Measurement | | Dist. Between Ref. Lines | | Actual Crush | |
|-------------------|--------|-------|------------------|--------|------------------------------|-------|--------------------------|-------|--------------|-------|
| | in. | (mm) | in. | (mm) | in. | (mm) | in. | (mm) | in. | (mm) |
| C ₁ | 15 1/4 | (387) | -27 | -(686) | 7 1/2 | (191) | 9 1/4 | (235) | -1 1/2 | -(38) |
| C ₂ | 14 1/4 | (362) | -16 1/4 | -(413) | 5 | (127) | | | 0 | () |
| C ₃ | 13 1/3 | (338) | -5 1/2 | -(140) | 4 1/8 | (105) | | | -0 | -(2) |
| C ₄ | 13 1/4 | (337) | 5 1/4 | (133) | 4 1/8 | (105) | | | - 1/8 | -(3) |
| C ₅ | 14 1/4 | (362) | 16 | (406) | 5 | (127) | | | 0 | () |
| C ₆ | 25 1/2 | (648) | 26 3/4 | (679) | 7 3/8 | (187) | | | 8 7/8 | (225) |
| C _{MAX} | 25 1/2 | (648) | 26 3/4 | (679) | 7 3/8 | (187) | | | 8 7/8 | (225) |

Figure F-5. Exterior Vehicle Crush (NASS) - Front, Test No. N2BR-1

Date: 4/12/2018 Test Name: 2NBR-1 VIN: 1D7RB1DG4BS514230
Year: 2011 Make: Dodge Model: Ram 1500



Distance from centerline to reference line - L_{REF}: 76 in. (1930) mm
Total Vehicle Length: 229 1/2 (5829)
Distance from vehicle c.g. to 1/2 of Vehicle total length: -7 1/8 -(181)
Width of contact and induced crush - Field L: 70 1/2 (1791)
Crush measurement spacing interval (L/5) - I: 14 1/8 (359)
Distance from vehicle c.g. to center of Field L - D_{FL}: 66 1/4 (1683)
Width of Contact Damage: 64 1/2 (1638)
Distance from vehicle c.g. to center of contact damage - D_C: 69 1/4 (1759)

NOTE: Enter "NA" for crush measurement if distance can not be measured (i.e., front of vehicle has been pushed inward or tire has been removed)
NOTE: All values must be filled out above before crush measurements are filled out.

| Crush Measurement | Longitudinal Location | | Original Profile Measurement | | Dist. Between Ref. Lines | | Actual Crush | |
|-------------------|-----------------------|--------|------------------------------|--------|--------------------------|-------|--------------|-------|
| | in. | (mm) | in. | (mm) | in. | (mm) | in. | (mm) |
| C ₁ | 35 3/4 | (908) | 31 | (787) | 5 1/8 | (130) | -1 3/8 | -(35) |
| C ₂ | na | NA | 45 1/8 | (1146) | 5 1/8 | (130) | NA | NA |
| C ₃ | na | NA | 59 1/4 | (1505) | 5 1/2 | (140) | NA | NA |
| C ₄ | 45 3/4 | (1162) | 73 3/8 | (1864) | 5 7/8 | (149) | 7 7/8 | (200) |
| C ₅ | 48 1/2 | (1232) | 87 1/2 | (2223) | 5 7/8 | (149) | 10 5/8 | (270) |
| C ₆ | 57 1/4 | (1454) | 101 5/8 | (2581) | 12 1/2 | (318) | 12 3/4 | (324) |
| C _{MAX} | 57 1/4 | (1454) | 101 5/8 | (2581) | 12 1/2 | (318) | 12 3/4 | (324) |

Figure F-6. Exterior Vehicle Crush (NASS) - Side, Test No. N2BR-1

Appendix G. Accelerometer and Rate Transducer Data Plots, Test No. N2BR-1




Figure G-1. Longitudinal CFC-180 10-msec Extracted Average Acceleration (SLICE-1), Test No. N2BR-1




Figure G-2. Longitudinal Change in Velocity (SLICE-1), Test No. N2BR-1




Figure G-3. Longitudinal Change in Displacement (SLICE-1), Test No. N2BR-1




Figure G-4. Lateral CFC-180 10-msec Extracted Average Acceleration (SLICE-1), Test No. N2BR-1




Figure G-5. Lateral Change in Velocity (SLICE-1), Test No. N2BR-1




Figure G-6. Lateral Change in Displacement (SLICE-1), Test No. N2BR-1




Figure G-7. Vehicle Angular Displacements (SLICE-1), Test No. N2BR-1




Figure G-8. Acceleration Severity Index (SLICE-1), Test No. N2BR-1




Figure G-9. 10-ms Average Longitudinal Deceleration (DTS), Test No. N2BR-1




Figure G-10. Longitudinal Occupant Impact Velocity (DTS), Test No. N2BR-1




Figure G-11. Longitudinal Occupant Displacement (DTS), Test No. N2BR-1




Figure G-12. 10-ms Average Lateral Deceleration (DTS), Test No. N2BR-1




Figure G-13. Lateral Occupant Impact Velocity (DTS), Test No. N2BR-1




Figure G-14. Lateral Occupant Displacement (DTS), Test No. N2BR-1




Figure G-15. Vehicle Angular Displacements (DTS), Test No. N2BR-1





Figure G-16. Acceleration Severity Index (DTS), Test No. N2BR-1

Appendix H. Example Calculations for Minimum Installation Lengths

The following pages contain a few example calculations for the length of MGS required adjacent to the bridge rail based on the forces applied to the W-beam guardrail by a compression terminal. Please note that these calculations are only for the resistance needed to support proper function of a compression and do not include consideration for the length of need required to shield the hazard, terminal stroke length, or guardrail anchorage requirements. All of these factors should be considered when determining the minimum MGS length adjacent to the bridge rail.

EXAMPLE #1



- TL-2 installation
- 25-ft bridge
 - 31.25 ft of bridge rail (between W6x8.5 posts)
 - (4) S3x5.7 bridge rail posts
- MSKT on upstream end of guardrail
 - TL-2 stroke length of 25 ft
- 25 ft of guardrail upstream of bridge rail
- Downstream MGS posts to utilize 12-in. blockouts

Compression load from Table 18 in Section 10.5:

For an MSKT, $C = 12.6$ kips

Post capacities from Table 17 in Section 10.5:

S3x5.7 bridge posts, $P_s = 1.2$ kips


W6x8.5 MGS posts with 12" blockout, $P_w = 2.4$ kips

Use equation from Section 10.5 to find minimum number of MGS posts downstream of bridge

$$\begin{aligned}
 N_s P_s + N_w P_w &> C \\
 (4)(1.2) + N_w(2.4) &> 12.6 \\
 N_w &> 3.25 \text{ posts}
 \end{aligned}$$

TL-2 MSKT has a stroke length of 25 ft, so all of the posts on the upstream side of the bridge rail are within the stroke length and should not be counted as resisting the terminal compression force. Thus, four W6x8.5 MGS posts are required on the downstream end of the bridge rail to resist the terminal compression forces. This corresponds to 18.75-ft of MGS beginning at post no. 10 of the installation.

EXAMPLE #2



- TL-2 installation
- 45-ft bridge
 - 50 ft of bridge rail (between W6x8.5 posts)
 - (7) S3x5.7 bridge rail posts
- MSKT on upstream end of guardrail
 - TL-2 stroke length of 25 ft
- 37.5-ft of guardrail upstream of bridge rail
- Downstream MGS posts to utilize 12-in. blockouts

Compression load from Table 18 in Section 10.5:

For an MSKT, $C = 12.6$ kips

Post capacities from Table 17 in Section 10.5:

S3x5.7 bridge posts, $P_s = 1.2$ kips


W6x8.5 MGS posts with 12" blockout, $P_w = 2.4$ kips

Use equation from Section 10.5 to find minimum number of MGS posts downstream of bridge

$$\begin{aligned}
 N_s P_s + N_w P_w &> C \\
 (7)(1.2) + N_w(2.4) &> 12.6 \\
 N_w &> 1.75 \text{ posts}
 \end{aligned}$$

TL-2 MSKT has a stroke length of 25 ft, so two of the posts on the upstream side of the bridge rail are outside the stroke length and would resist the terminal compression force. Thus, the additional 12.5-ft of MGS installed adjacent to the TL-2 MSKT and the 50-ft long bridge rail are sufficient to resist the terminal compression forces. No additional MGS is required on the downstream end to account for terminal compression forces, so the length of the MGS required on the downstream end would be likely be determined from anchorage requirements (see Section 10.5).

EXAMPLE #3



- TL-3 installation
- 35-ft bridge
 - 37.5 ft of bridge rail (between W6x8.5 posts)
 - (9) S3x5.7 bridge rail posts
- MSKT on upstream end of guardrail
 - TL-3 stroke length of 50 ft
- 50-ft of guardrail upstream of bridge rail
- Downstream MGS posts to utilize 12-in. blockouts

Compression load from Table 18 in Section 10.5:
For an MSKT, $C = 12.6$ kips

Post capacities from Table 17 in Section 10.5:
S3x5.7 bridge posts, $P_s = 1.2$ kips
W6x8.5 MGS posts with 12" blockout, $P_w = 2.4$ kips

Use equation from Section 10.5 to find minimum number of MGS posts downstream of bridge

$$\begin{aligned}
 N_s P_s + N_w P_w &> C \\
 (9)(1.2) + N_w(2.4) &> 12.6 \\
 N_w &> 0.75 \text{ posts}
 \end{aligned}$$

TL-3 MSKT has a stroke length of 50 ft, so all of the posts on the upstream side of the bridge rail are within the stroke length and should not be counted as resisting the terminal compression force. Thus, only one W6x8.5 MGS post is required on the downstream end to account for terminal compression forces. As such, the length of MGS required on the downstream end would be likely be determined from anchorage requirements (see Section 10.5).

EXAMPLE #4

What length of bridge rail would be sufficient to resist the terminal compression forces of an MSKT? In such an installation, the length of the MGS on downstream end of the installation would be determined by anchorage requirements only.

$$\begin{aligned} N_s P_s + N_w P_w &> C \\ N_s(1.2) + (0)(2.4) &> 12.6 \\ N_s &> 10.5 \text{ posts} \end{aligned}$$

Eleven posts spaced at 6.25 ft intervals would cover a distance of 62.5 ft. Assuming there was at least 1 ft of distance between the outer posts and the ends of the bridge, any bridge longer than 65 ft should have enough posts to resist the compression forces in an MSKT terminal.

END OF DOCUMENT