

Test Report No. 619551-01



**EVALUATION OF *MASH* TL-3 TRANSITION DESIGN WITH A
STORM DRAIN – CRASH TEST OF 1100C VEHICLE (SMALL CAR)**

Sponsored by
Roadside Safety Pooled Fund

TEXAS A&M TRANSPORTATION INSTITUTE PROVING GROUND

Roadside Safety & Physical Security
Texas A&M University System RELLIS Campus
Building 7091
1254 Avenue A
Bryan, TX 77807

1. Report No.		2. Government Accession No.		3. Recipient's Catalog No.	
4. Title and Subtitle EVALUATION OF MASH TL-3 TRANSITION DESIGN WITH A STORM DRAIN – CRASH TEST OF 1100C VEHICLE (SMALL CAR)				5. Report Date October 2023	
				6. Performing Organization Code	
7. Author(s) Akram Abu-Odeh, Ph.D. and William J. L. Schroeder				8. Performing Organization Report No. TRNo 619551-01	
9. Performing Organization Name and Address Texas A&M Transportation Institute Proving Ground 3135 TAMU College Station, Texas 77843-3135				10. Work Unit No. (TRAIS)	
				11. Contract or Grant No. Project T1969	
12. Sponsoring Agency Name and Address Roadside Safety Pooled Fund Research Office MS 47372 Transportation Building Olympia, WA 98504-7372				13. Type of Report and Period Covered Technical Report: June 2023 - October 2023	
				14. Sponsoring Agency Code	
15. Supplementary Notes Name of Contacting Representative: Derwood Sheppard					
16. Abstract <p>The purpose of the tests reported herein was to assess the performance of the TL-3 Transition with a Storm Drain Inlet according to the safety-performance evaluation guidelines included in the second edition of the American Association of State Highway and Transportation Officials (AASHTO) <i>Manual for Assessing Safety Hardware (MASH)</i> (1). The crash test was performed in accordance with <i>MASH</i> Test 3-20:</p> <p>1. MASH Test 3-20: An 1100C vehicle weighing 2420 lb impacting the Longitudinal Barrier while travelling at 62 mi/h and 25 degrees.</p> <p>This report provides details on the TL-3 Transition with a Storm Drain Inlet, the crash tests and results, and the performance assessment of the TL-3 Transition with a Storm Drain Inlet for <i>MASH</i> TEST 3-20 Longitudinal Barrier evaluation criteria.</p> <p>The TL-3 Transition with a Storm Drain Inlet met the performance criteria for <i>MASH</i> TEST 3-20 Longitudinal Barrier. The installation was developed and tested to <i>MASH</i> Test 3-21 in Test Report No. 615251-01.</p>					
17. Key Words Transition, Drop Inlet, MASH, Crash Testing, Longitudinal Barrier, Concrete			18. Distribution Statement No restrictions. This document is available to the public through NTIS: National Technical Information Service Alexandria, Virginia 22312 http://www.ntis.gov		
19. Security Classification. (of this report) Unclassified		20. Security Classification. (of this page) Unclassified		21. No. of Pages 96	22. Price

Form DOT F 1700.7 (8-72) Reproduction of completed page authorized.

EVALUATION OF *MASH* TL-3 TRANSITION DESIGN WITH A STORM
DRAIN – CRASH TEST OF 1100C VEHICLE (SMALL CAR)

by

Akram Abu-Odeh, Ph.D.
Research Scientist
Texas A&M Transportation Institute

Sun Hee Park, Ph.D.
Associate Transportation Researcher
Texas A&M Transportation Institute

and

William J. L. Schroeder
Research Engineering Associate
Texas A&M Transportation Institute

Report 619551-01
Contract No.: T1969

Sponsored by the
Roadside Safety Pooled Fund

October 2023

TEXAS A&M TRANSPORTATION INSTITUTE
College Station, Texas 77843-3135

DISCLAIMER

The contents of this report reflect the views of the authors, who are solely responsible for the facts and accuracy of the data, and the opinions, findings, and conclusions presented herein. The contents do not necessarily reflect the official views or policies of the Roadside Safety Pooled Fund, The Texas A&M University System, or the Texas A&M Transportation Institute (TTI). This report does not constitute a standard, specification, or regulation. In addition, the above listed agencies/companies assume no liability for its contents or use thereof. The names of specific products or manufacturers listed herein do not imply endorsement of those products or manufacturers.

The results reported herein apply only to the article tested. The full-scale crash test was performed according to TTI Proving Ground quality procedures and American Association of State Highway and Transportation Officials (AASHTO) Manual for Assessing Safety Hardware, Second Edition (*MASH*) guidelines and standards.

The Proving Ground Laboratory within TTI's Roadside Safety and Physical Security Division ("TTI Lab") strives for accuracy and completeness in its crash test reports. On rare occasions, unintentional or inadvertent clerical errors, technical errors, omissions, oversights, or misunderstandings (collectively referred to as "errors") may occur and may not be identified for corrective action prior to the final report being published and issued. If, and when, the TTI Lab discovers an error in a published and issued final report, the TTI Lab will promptly disclose such error to Roadside Safety Pooled Fund, and both parties shall endeavor in good faith to resolve this situation. The TTI Lab will be responsible for correcting the error that occurred in the report, which may be in the form of errata, amendment, replacement sections, or up to and including full reissuance of the report. The cost of correcting an error in the report shall be borne by the TTI Lab. Any such errors or inadvertent delays that occur in connection with the performance of the related testing contract will not constitute a breach of the testing contract.

THE TTI LAB WILL NOT BE LIABLE FOR ANY INDIRECT, CONSEQUENTIAL, PUNITIVE, OR OTHER DAMAGES SUFFERED BY THE ROADSIDE SAFETY POOLED FUND OR ANY OTHER PERSON OR ENTITY, WHETHER SUCH LIABILITY IS BASED, OR CLAIMED TO BE BASED, UPON ANY NEGLIGENT ACT, OMISSION, ERROR, CORRECTION OF ERROR, DELAY, OR BREACH OF AN OBLIGATION BY THE TTI LAB.

ACKNOWLEDGEMENTS

This research project was performed under a pooled fund program between the following States and Agencies. The authors acknowledge and appreciate their guidance and assistance.

Roadside Safety Research Pooled Fund Committee

Revised May 2023

ALABAMA

Wade Henry, P.E.

Assistant State Design Engineer
Design Bureau, Final Design Division
Alabama Dept. of Transportation
1409 Coliseum Boulevard, T-205
Montgomery, AL 36110
(334) 242-6464
henryw@dot.state.al.us

Stanley (Stan) C. Biddick, P.E.

State Design Engineer
Design Bureau, Final Design Division
Alabama Dept. of Transportation
1409 Coliseum Boulevard, T-205
Montgomery, AL 36110
(334) 242-6833
biddicks@dot.state.al.us

ALASKA

Mary F. McRae

Design and Construction Standards
Engineer
Alaska Depart. of Transportation & Public
Facilities
3132 Channel Drive
P.O. Box 112500
Juneau, AK 99811-2500
(907) 465-1222
mary.mcrae@alaska.gov

Cole Carnahan

Design and Construction Standards
Engineering Assistant
Alaska Depart. of Transportation & Public
Facilities
3132 Channel Drive
P.O. Box 112500
Juneau, AK 99811-2500
(907) 465-6955
cole.carnahan@alaska.gov

CALIFORNIA

Bob Meline, P.E.

Caltrans
Office of Materials and Infrastructure
Division of Research and Innovation
5900 Folsom Blvd
Sacramento, CA 95819
(916) 227-7031
Bob.Meline@dot.ca.gov

John Jewell, P.E.

Senior Crash Testing Engineer
Office of Safety Innovation & Cooperative
Research
(916) 227-5824
John.Jewell@dot.ca.gov

COLORADO

Andy Pott, P.E.

Senior Bridge Design and Construction
Engineer
Division of Project Support, Staff Bridge
Design and Construction Management
Colorado Dept. of Transportation (CDOT)
4201 E Arkansas Ave, 4th Floor
Denver, CO 80222
303-512-4020
andrew.pott@state.co.us

Shawn Yu, P.E.

Miscellaneous (M) Standards and
Specifications Unit Manager
Division of Project Support, Construction
Engineering Services (CES) Branch
Colorado Dept. of Transportation (CDOT)
4201 E Arkansas Ave, 4th Floor
Denver, CO 80222
303-757-9474
shawn.yu@state.co.us

David Kosmiski, P.E.

Miscellaneous (M) Standards Engineer
Division of Project Support, Construction
Engineering Services (CES) Branch
Colorado Dept. of Transportation (CDOT)
4201 E Arkansas Ave, 4th Floor
Denver, CO 80222
303-757-9021
david.kosmiski@state.co.us

Amin Fakhimalizad

Assistant Miscellaneous (M) Standards
Engineer
Division of Project Support, Construction
Engineering Services (CES) Branch
Colorado Dept. of Transportation (CDOT)
303-757-9229
amin.fakhimalizad@state.co.us

CONNECTICUT**David Kilpatrick**

State of Connecticut Depart. of
Transportation
2800 Berlin Turnpike
Newington, CT 06131-7546
(806) 594-3288
David.Kilpatrick@ct.gov

DELAWARE**Craig Blowers**

Construction Resource Engineer
Construction Section
Delaware DOT
(302)760-2336
Craig.Blowers@delaware.gov

James Osborne

Traffic Safety Programs Manager
Traffic Operations
Delaware DOT
(302)659-4651
James.Osborne@delaware.gov

FLORIDA**Richard Stepp**

Florida Department of Transportation
Richard.Stepp@dot.state.fl.us

Derwood C. Sheppard, Jr., P.E.

State Roadway Design Engineer
Florida Depart. of Transportation
Roadway Design Office
605 Suwannee Street, MS-32
Tallahassee, FL 32399-0450
(850) 414-4334
Derwood.Sheppard@dot.state.fl.us

IDAHO**Marc Danley, P.E.**

Technical Engineer
(208) 334-8558
Marc.danley@itd.idaho.gov

Kevin Sablan

Design/Traffic Engineer
Idaho Transportation Department
(208) 334-8558
Kevin.sablan@itd.idaho.gov

ILLINOIS**Martha A. Brown, P.E.**

Safety Design Bureau Chief
Bureau of Safety Programs and Engineering
Illinois Depart. of Transportation
2300 Dirksen Parkway, Room 005
Springfield, IL 62764
(217) 785-3034
Martha.A.Brown@illinois.gov

Edgar Galofre

Safety Design Engineer
(217) 558-9089
edgar.glofre@illinois.gov

IOWA**Daniel Harness**

Office of Design – Methods
Iowa Department of Transportation
Daniel.Harness@iowadot.us

Chris Poole

State Traffic Engineer
Traffic and Safety Bureau
Iowa Department of Transportation
Chris.Poole@iowadot.us

LOUISIANA

Chris Guidry

Bridge Manager
Louisiana Transportation Center
Bridge & Structural Design Section
P.O. Box 94245
Baton Rouge, LA 79084-9245
(225) 379-1933
Chris.Guidry@la.gov

Carl Gaudry

Bridge Design Manager
Bridge & Structural Design Section
Louisiana Department of Transportation &
Development
Carl.Gaudry@la.gov

MARYLAND

Matamba Kabengele

Traffic Engineer
Office of Traffic and Safety
Maryland State Highway Administration
MKabengele@mdot.maryland.gov

MASSACHUSETTS

Alex Bardow

Director of Bridges and Structure
Massachusetts Depart. of Transportation
10 Park Plaza, Room 6430
Boston, MA 02116
(517) 335-9430
Alexander.Bardow@state.ma.us

James Danila

State Traffic Engineer
(857) 368-9640
James.danilla@state.ma.us

MICHIGAN

Carlos Torres, P.E.

Crash Barrier Engineer
Geometric Design Unit, Design Division
Michigan Depart. of Transportation
P. O. Box 30050
Lansing, MI 48909
(517) 335-2852
TorresC@michigan.gov

MINNESOTA

Khamsai Yang

Design Standards Engineer
Office of Project Management and
Technical Support
(651) 366-4622
Khamsai.Yang@state.mn.us

Brian Tang

Assistant Design Standards Engineer
Office of Project Management and
Technical Support
Minnesota Department of Transportation
(651) 366-4684
brian.tang@state.mn.us

MISSOURI

Sarah Kleinschmit, P.E.

Policy and Innovations Engineer,
Missouri Department of Transportation
P.O. Box 270
Jefferson City, MO 65102
(573) 751-7412
sarah.kleinschmit@modot.mo.gov

Kaitlyn (Katy) Bower

Roadside Design Specialist
Missouri Department of Transportation
573-472-9028
kaitlyn.bower@modot.mo.gov

NEW MEXICO

Brad Julian

Traffic Technical Support Engineer
(505) 827-3263
Brad.Julian@state.nm.us

OHIO

Don P. Fisher, P.E.

Ohio Depart. of Transportation
1980 West Broad Street
Mail Stop 1230
Columbus, OH 43223
(614) 387-6214
Don.fisher@dot.ohio.gov

OREGON

Christopher Henson

Senior Roadside Design Engineer
Oregon Depart. of Transportation
Technical Service Branch
4040 Fairview Industrial Drive, SE
Salem, OR 97302-1142
(503) 986-3561

Christopher.S.Henson@odot.state.or.us

PENNSYLVANIA

James A. Borino, Jr., P.E.

Chief, Standards and Criteria Unit
Highway Design and Technology Division
Pennsylvania DOT
(717) 612-4791

jborino@pa.gov

Evan Pursel

Senior Civil Engineer
Highway Design and Technology Division
Pennsylvania DOT
(717) 705-8535

epursel@pa.gov

Nina Ertel

Project Development Engineer
Highway Design and Technology Division
Pennsylvania DOT
(717) 425-7679

nerTEL@pa.gov

TEXAS

Chris Lindsey

Transportation Engineer
Design Division
Texas Department of Transportation
125 East 11th Street
Austin, TX 78701-2483
(512) 416-2750

Christopher.Lindsey@txdot.gov

Taya Retterer

TxDOT Bridge Standards Engineer
Bridge Division
Texas Department of Transportation
(512) 416-2719

Taya.Retterer@txdot.gov

UTAH

Shawn Debenham

Traffic and Safety Division
Utah Depart. of Transportation
4501 South 2700 West
PO Box 143200
Salt Lake City UT 84114-3200
(801) 965-4590

sdebenham@utah.gov

WASHINGTON

Mustafa Mohamedali

Assistant Research Project Manager
P.O. Box 47372
Olympia, WA 98504-7372
(360) 704-6307

mohamem@wsdot.wa.gov

Tim Moeckel

Roadside Safety Engineer
Washington State Department of
Transportation
Development Division
P.O. Box 47329
Olympia, WA 98504-7246
(360) 704-6377

moecket@wsdot.wa.gov

WEST VIRGINIA

Donna J. Hardy, P.E.

Safety Programs Engineer
West Virginia Depart. of
Transportation – Traffic Engineering
Building 5, Room A-550
1900 Kanawha Blvd E.
Charleston, WV 25305-0430
(304) 558-9576

Donna.J.Hardy@wv.gov

Ted Whitmore

Traffic Services Engineer
Traffic Engineering
WV Division of Highways
(304)414-7373

Ted.J.Whitmore@wv.gov

WISCONSIN

Erik Emerson, P.E.

Standards Development Engineer –
Roadside Design
Wisconsin Department of Transportation
Bureau of Project Development
4802 Sheboygan Avenue, Room 651
P. O. Box 7916
Madison, WI 53707-7916
(608) 266-2842
Erik.Emerson@wi.gov

CANADA – ONTARIO

Kenneth Shannon, P. Eng.

Senior Engineer, Highway Design (A)
Ontario Ministry of Transportation
301 St. Paul Street
St. Catharines, ON L2R 7R4
CANADA
(904) 704-3106
Kenneth.Shannon@ontario.ca

FEDERAL HIGHWAY ADMINISTRATION (FHWA)

WebSite: safety.fhwa.dot.gov

Richard B. (Dick) Albin, P.E.

Safety Engineer
FHWA Resource Center Safety & Design
Technical Services Team
711 S. Capital
Olympia, WA 98501
(303) 550-8804
Dick.Albin@dot.gov

Eduardo Arispe

Research Highway Safety Specialist
U.S. Department of Transportation
Federal Highway Administration
Turner-Fairbank Highway Research Center
Mail Code: HRDS-10
6300 Georgetown Pike
McLean, VA 22101
(202) 493-3291
Eduardo.arispe@dot.gov

Christine Black

Highway Safety Engineer
Central Federal Lands Highway Division
12300 West Dakota Ave.
Lakewood, CO 80228
(720) 963-3662
Christine.black@dot.gov

TR No. 619551-01

Isbel Ramos-Reyes

Lead Safety and Transportation Operations
Engineer
(703) 948-1442
isbel.ramos-reyes@dot.gov

Matt Hinshaw, M.S., P.E.

Highway Safety Engineer
Central Federal Lands Highway Division
(360)619-7677
matthew.hinshaw@dot.gov

TEXAS A&M TRANSPORTATION INSTITUTE (TTI)

WebSite: tti.tamu.edu
www.roadsidepooledfund.org

D. Lance Bullard, Jr., P.E.

Senior Research Engineer
Roadside Safety & Physical Security Div.
Texas A&M Transportation Institute
3135 TAMU
College Station, TX 77843-3135
(979) 317-2855
L-Bullard@tti.tamu.edu

Roger P. Bligh, Ph.D., P.E.

Senior Research Engineer
(979) 317-2703
R-Bligh@tti.tamu.edu

Nauman Sheikh

Research Scientist
Roadside Safety and Physical Security
Texas A&M Transportation Institute
n-sheikh@tti.tamu.edu

Ariel Sheil

Research Assistant
Roadside Safety and Physical Security
Texas A&M Transportation Institute
A-Sheil@tti.tamu.edu

REPORT AUTHORIZATION

REPORT REVIEWED BY:



Glenn Schroeder
Research Specialist
Drafting & Reporting




Ken Reeves
Research Specialist
Electronics Instrumentation



Adam Mayer
Research Specialist
Construction



Richard Badillo
Research Specialist
Photographic Instrumentation



Robert Kocman
Research Specialist
Mechanical Instrumentation



William J. L. Schroeder
Research Engineering Associate
Research Evaluation and Reporting



Bill L. Griffith
Research Specialist
Quality Manager



Matthew N. Robinson
Research Specialist
Test Facility Manager & Technical
Manager



Akram Abu-Odeh, Ph.D.
Research Scientist

TABLE OF CONTENTS

	Page
Chapter 1. Introduction.....	1
Chapter 2. System Details	3
2.1. Test Article and Installation Details	3
2.2. Design Modifications during Tests	3
2.3. Material Specifications	8
2.4. Soil Conditions	8
Chapter 3. Test Requirements and Evaluation Criteria.....	9
3.1. Crash Test Performed/Matrix	9
3.2. Evaluation Criteria.....	9
Chapter 4. Test Conditions.....	11
4.1. Test Facility	11
4.2. Vehicle Tow and Guidance System	11
4.3. Data Acquisition Systems	11
4.3.1. Vehicle Instrumentation and Data Processing	11
4.3.2. Anthropomorphic Dummy Instrumentation.....	12
4.3.3. Photographic Instrumentation Data Processing.....	13
Chapter 5. MASH Test 3-20 (Crash Test 619551-01-1).....	15
5.1. Test Designation and Actual Impact Conditions.....	15
5.2. Weather Conditions	17
5.3. Test Vehicle	17
5.4. Test Description	19
5.5. Damage to Test Installation	19
5.6. Damage to Test Vehicle.....	21
5.7. Occupant Risk Factors.....	24
5.8. Test Summary.....	24
Chapter 6. Summary and Conclusions.....	27
6.1. Assessment of Test Results.....	27
6.2. Conclusions	27
References	29
Appendix A. Details of TL-3 Transition with a Storm Drain Inlet.....	31
Appendix B. Supporting Certification Documents	57
Appendix C. MASH Test 3-20 (Crash Test 619551-01-1).....	87
C.1. Vehicle Properties and Information	87
C.2. Sequential Photographs.....	90
C.3. Vehicle Angular Displacements	93
C.4. Vehicle Accelerations.....	95

LIST OF FIGURES

	Page
Figure 2.1. Details of TL-3 Transition with a Storm Drain Inlet.....	4
Figure 2.2. TL-3 Transition with a Storm Drain Inlet prior to Testing.....	5
Figure 2.3. TL-3 Transition with a Storm Drain Inlet at the Transition prior to Testing.....	5
Figure 2.4. In-line View of the TL-3 Transition with a Storm Drain Inlet prior to Testing.....	6
Figure 2.5. Field Side View of the TL-3 Transition with a Storm Drain Inlet prior to Testing.....	6
Figure 2.6. Post 16 of the TL-3 Transition with a Storm Drain Inlet prior to Testing.....	7
Figure 2.7. Posts of the TL-3 Transition with a Storm Drain Inlet at the Transition prior to Testing.....	7
Figure 3.1. Target CIP for <i>MASH</i> Test 3-20 Tests on TL-3 Transition with a Storm Drain Inlet.....	9
Figure 5.1. TL-3 Transition with a Storm Drain Inlet/Test Vehicle Geometrics for Test 619551-01-1.....	16
Figure 5.2. TL-3 Transition with a Storm Drain Inlet/Test Vehicle Impact Location 619551-01-1.....	16
Figure 5.3. Impact Side of Test Vehicle before Test 619551-01-1.....	17
Figure 5.4. Opposite Impact Side of Test Vehicle before Test 619551-01-1.....	18
Figure 5.5. Traffic Side of the TL-3 Transition with a Storm Drain Inlet at Impact Location after Test 619551-01-1.....	20
Figure 5.6. Field Side of the TL-3 Transition with a Storm Drain Inlet at Impact Location after Test 619551-01-1.....	20
Figure 5.7. Impact Side of Test Vehicle after Test 619551-01-1.....	21
Figure 5.8. Rear Impact Side of Test Vehicle after Test 619551-01-1.....	21
Figure 5.9. Overall Interior of Test Vehicle after Test 619551-01-1.....	22
Figure 5.10. Interior of Test Vehicle on Impact Side after Test 619551-01-1.....	22
Figure 5.11. Summary of Results for <i>MASH</i> Test 3-20 on TL-3 Transition with a Storm Drain Inlet.....	25
Figure C.2. Exterior Crush Measurements for Test 619551-01-1.....	88
Figure C.3. Occupant Compartment Measurements for Test 619551-01-1.....	89
Figure C.4. Sequential Photographs for Test 619551-01-1 (Overhead Views).....	90
Figure C.5. Sequential Photographs for Test 619551-01-1 (Frontal Views).....	91
Figure C.6. Sequential Photographs for Test 619551-01-1 (Rear Views).....	92
Figure C.7. Vehicle Angular Displacements for Test 619551-01-1.....	94
Figure C.8. Vehicle Longitudinal Accelerometer Trace for Test 619551-01-1 (Accelerometer Located at Center of Gravity).....	96
Figure C.9. Vehicle Lateral Accelerometer Trace for Test 619551-01-1 (Accelerometer Located at Center of Gravity).....	97
Figure C.10. Vehicle Vertical Accelerometer Trace for Test 619551-01-1 (Accelerometer Located at Center of Gravity).....	98

LIST OF TABLES

	Page
Table 2.1. Concrete Strength.....	8
Table 2.2. Soil Strength.....	8
Table 3.1. Test Conditions and Evaluation Criteria Specified for <i>MASH</i> Test 3-20 Longitudinal Barrier.....	9
Table 3.2. Evaluation Criteria Required for <i>MASH</i> Testing.....	10
Table 5.1. Impact Conditions for <i>MASH TEST 3-20</i> , Crash Test 619551-01-1.....	15
Table 5.2. Exit Parameters for <i>MASH TEST 3-20</i> , Crash Test 619551-01-1.....	15
Table 5.3. Weather Conditions 619551-01-1.....	17
Table 5.4. Vehicle Measurements for Test 619551-01-1.....	18
Table 5.5. Events during Test 619551-01-1.....	19
Table 5.6. Deflection and Working Width of the TL-3 Transition with a Storm Drain Inlet for Test 619551-01-1.....	19
Table 5.7. Occupant Compartment Deformation 619551-01-1.....	23
Table 5.8. Exterior Vehicle Damage 619551-01-1.....	23
Table 5.9. Occupant Risk Factors for Test 619551-01-1.....	24
Table 8.1. Assessment Summary for <i>MASH</i> Test 3-20 Tests on TL-3 Transition with a Storm Drain Inlet.....	27

SI* (MODERN METRIC) CONVERSION FACTORS

APPROXIMATE CONVERSIONS TO SI UNITS

Symbol	When You Know	Multiply By	To Find	Symbol
LENGTH				
in	inches	25.4	millimeters	mm
ft	feet	0.305	meters	m
yd	yards	0.914	meters	m
mi	miles	1.61	kilometers	km
AREA				
in ²	square inches	645.2	square millimeters	mm ²
ft ²	square feet	0.093	square meters	m ²
yd ²	square yards	0.836	square meters	m ²
ac	acres	0.405	hectares	ha
mi ²	square miles	2.59	square kilometers	km ²
VOLUME				
fl oz	fluid ounces	29.57	milliliters	mL
gal	gallons	3.785	liters	L
ft ³	cubic feet	0.028	cubic meters	m ³
yd ³	cubic yards	0.765	cubic meters	m ³
NOTE: volumes greater than 1000L shall be shown in m ³				
MASS				
oz	ounces	28.35	grams	g
lb	pounds	0.454	kilograms	kg
T	short tons (2000 lb)	0.907	megagrams (or metric ton")	Mg (or "t")
TEMPERATURE (exact degrees)				
°F	Fahrenheit	5(F-32)/9 or (F-32)/1.8	Celsius	°C
FORCE and PRESSURE or STRESS				
lbf	poundforce	4.45	newtons	N
lbf/in ²	poundforce per square inch	6.89	kilopascals	kPa

APPROXIMATE CONVERSIONS FROM SI UNITS

Symbol	When You Know	Multiply By	To Find	Symbol
LENGTH				
mm	millimeters	0.039	inches	in
m	meters	3.28	feet	ft
m	meters	1.09	yards	yd
km	kilometers	0.621	miles	mi
AREA				
mm ²	square millimeters	0.0016	square inches	in ²
m ²	square meters	10.764	square feet	ft ²
m ²	square meters	1.195	square yards	yd ²
ha	hectares	2.47	acres	ac
km ²	Square kilometers	0.386	square miles	mi ²
VOLUME				
mL	milliliters	0.034	fluid ounces	oz
L	liters	0.264	gallons	gal
m ³	cubic meters	35.314	cubic feet	ft ³
m ³	cubic meters	1.307	cubic yards	yd ³
MASS				
g	grams	0.035	ounces	oz
kg	kilograms	2.202	pounds	lb
Mg (or "t")	megagrams (or "metric ton")	1.103	short tons (2000lb)	T
TEMPERATURE (exact degrees)				
°C	Celsius	1.8C+32	Fahrenheit	°F
FORCE and PRESSURE or STRESS				
N	newtons	0.225	poundforce	lbf
kPa	kilopascals	0.145	poundforce per square inch	lb/in ²

*SI is the symbol for the International System of Units

Chapter 1. INTRODUCTION

The purpose of the test reported herein was to complete the assessment of the performance of the Sponsor's TL-3 Transition with a Storm Drain Inlet according to the safety-performance evaluation guidelines included in the American Association of State Highway and Transportation Officials (AASHTO) *Manual for Assessing Safety Hardware (MASH)*, Second Edition (1). The TL-3 Transition with a Storm Drain Inlet pass the *MASH* evaluation criteria under *MASH* Test 3-21 conducted in earlier project (2). The crash test was performed in accordance with *MASH* Test 3-20.

Chapter 2. SYSTEM DETAILS


2.1. TEST ARTICLE AND INSTALLATION DETAILS

The installation consisted of a 50-foot-long length of need W-beam guardrail embedded in crushed concrete, which transitioned to a single W-beam guard rail mounted to wingwall posts. From there the rail transitioned to a section of Thrie-beam rail before terminating into a concrete parapet mounted on a moment slab. The wingwall posts for the W-beam and Thrie-beam were mounted onto concrete, with a drain inlet placed at posts 16 and 17. The rails were held at a consistent height of 31 inches to the top of the rail, and the parapet was 32 inches tall, 12 inches wide, and 16 feet long. On the upstream end, the length of need rail terminated with a steel rail terminal.

Figure 2.1 presents the overall information on the TL-3 Transition with a Storm Drain Inlet, and Figure 2.2 thru Figure 2.7 provide photographs of the installation. Appendix A provides further details on the TL-3 Transition with a Storm Drain Inlet. Drawings were provided by the Texas A&M Transportation Institute (TTI) Proving Ground, and construction was performed by MBC Management Inc. and supervised by TTI Proving Ground personnel.

2.2. DESIGN MODIFICATIONS DURING TESTS

No modifications were made to the installation during the testing phase.



S:\Accreditation-17025-2017\EIR-000 Project Files\619551-01 - Transition with Inlet - Akram\Drafting, 619551\619551 Drawing

Figure 2.1. Details of TL-3 Transition with a Storm Drain Inlet.



Figure 2.2. TL-3 Transition with a Storm Drain Inlet prior to Testing.



Figure 2.3. TL-3 Transition with a Storm Drain Inlet at the Transition prior to Testing.



Figure 2.4. In-line View of the TL-3 Transition with a Storm Drain Inlet prior to Testing.



Figure 2.5. Field Side View of the TL-3 Transition with a Storm Drain Inlet prior to Testing.



Figure 2.6. Post 16 of the TL-3 Transition with a Storm Drain Inlet prior to Testing.



Figure 2.7. Posts of the TL-3 Transition with a Storm Drain Inlet at the Transition prior to Testing.

2.3. MATERIAL SPECIFICATIONS

Appendix B provides material certification documents for the materials used to install/construct the TL-3 Transition with a Storm Drain Inlet. Table 2.1 shows the average compressive strengths of the concrete on 2023-06-27, the day of the test. Other concrete structures for this project were repurposed from project 615251, which tested the same system to MASH 3-21 standards. At the time of the 3-21 testing, all concrete met or exceeded the desired design strength. Further details for that concrete can be found in Appendix B of this report.

Table 2.1. Concrete Strength.

Location	Design Strength (psi)	Avg. Strength (psi)	Age (days)	Detailed Location
Beams	3600	3740	25	Straight beam and repaired a section of the tapered beam

2.4. SOIL CONDITIONS

The test installation was installed in standard soil meeting Type 1 Grade D of AASHTO standard specification M147-17 “Materials for Aggregate and Soil Aggregate Subbase, Base, and Surface Courses.”

In accordance with Appendix B of *MASH*, soil strength was measured the day of the crash test. During installation of the TL-3 Transition with a Storm Drain Inlet for full-scale crash testing, two 6-ft long W6×16 posts were installed in the immediate vicinity of the TL-3 Transition with a Storm Drain Inlet using the same fill materials and installation procedures used in the test installation and the standard dynamic test.

On the day of Test 3-20, 2023-06-27, loads on the post at deflections were as follows: the backfill material in which the TL-3 Transition with a Storm Drain Inlet was installed met/did not meet minimum *MASH* requirements for soil strength. Displacement was not measured at 10 and 15 inches as the actual load at 5 inches greatly exceeded the minimum load value required.

Table 2.2. Soil Strength.

Displacement (in)	Minimum Load (lb)	Actual Load (lb)
5	4420	11,000*
10	4981	n/a
15	5282	n/a

Chapter 3. TEST REQUIREMENTS AND EVALUATION CRITERIA

3.1. CRASH TEST PERFORMED/MATRIX

Table 3.1 shows the test conditions and evaluation criteria for *MASH* Test 3-20 for Longitudinal Barrier. The target critical impact points (CIPs) for each test were determined using the information provided in *MASH* Section 2.2.1 and Section 2.3.2. Figure 3.1 shows the target CIP for *MASH* Test 3-20 on the TL-3 Transition with a Storm Drain Inlet.

Table 3.1. Test Conditions and Evaluation Criteria Specified for *MASH* Test 3-20 Longitudinal Barrier.

Test Designation	Test Vehicle	Impact Speed	Impact Angle	Evaluation Criteria
3-20	1100C	62 mi/h	25°	A, D, F, H, I




Figure 3.1. Target CIP for *MASH* Test 3-20 Tests on TL-3 Transition with a Storm Drain Inlet.

The crash tests and data analysis procedures were in accordance with guidelines presented in *MASH*. Chapter 4 presents brief descriptions of these procedures.

3.2. EVALUATION CRITERIA

The appropriate safety evaluation criteria from Tables 2.2 and 5.1 of *MASH* were used to evaluate the crash test reported herein. Table 3.1 lists the test conditions and evaluation criteria required for *MASH* Test 3-20, and Table 3.2 provides detailed information on the evaluation criteria.

Table 3.2. Evaluation Criteria Required for *MASH* Testing.

Evaluation Factors	Evaluation Criteria
A.	Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.
D.	Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present undue hazard to other traffic, pedestrians, or personnel in a work zone. Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of <i>MASH</i> .
F.	The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.
H.	Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.
I.	The occupant ridedown accelerations should satisfy the following: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.

Chapter 4. TEST CONDITIONS

4.1. TEST FACILITY

The full-scale crash test reported herein was performed at the TTI Proving Ground, an International Standards Organization (ISO)/International Electrotechnical Commission (IEC) 17025-accredited laboratory with American Association for Laboratory Accreditation (A2LA) Mechanical Testing Certificate 2821.01. The full-scale crash test was performed according to TTI Proving Ground quality procedures, as well as *MASH* guidelines and standards.

The test facilities of the TTI Proving Ground are located on The Texas A&M University System RELLIS Campus, which consists of a 2000-acre complex of research and training facilities situated 10 mi northwest of the flagship campus of Texas A&M University. The site, formerly a United States Army Air Corps base, has large expanses of concrete runways and parking aprons well suited for experimental research and testing in the areas of vehicle performance and handling, vehicle-roadway interaction, highway pavement durability and efficacy, and roadside safety hardware and perimeter protective device evaluation. The sites selected for construction and testing are along the edge of an out-of-service apron/runway. The apron/runway consists of an unreinforced jointed-concrete pavement in 12.5-ft × 15-ft blocks nominally 6 inches deep. The aprons were built in 1942, and the joints have some displacement but are otherwise flat and level.

4.2. VEHICLE TOW AND GUIDANCE SYSTEM

For the 1100C vehicle, it was towed into the test installation using a steel cable guidance and reverse tow system. A steel cable for guiding the test vehicle was tensioned along the path, anchored at each end, and threaded through an attachment to the front wheel of the test vehicle. An additional steel cable was connected to the test vehicle, passed around a pulley near the impact point and through a pulley on the tow vehicle, and then anchored to the ground such that the tow vehicle moved away from the test site. A 2:1 speed ratio between the test and tow vehicle existed with this system. Just prior to impact with the installation, the test vehicle was released and ran unrestrained. The vehicle remained freewheeling (i.e., no steering or braking inputs) until it cleared the immediate area of the test site.

4.3. DATA ACQUISITION SYSTEMS

4.3.1. Vehicle Instrumentation and Data Processing

The test vehicle was instrumented with a self-contained onboard data acquisition system. The signal conditioning and acquisition system is a multi-channel data acquisition system (DAS) produced by Diversified Technical Systems Inc. The accelerometers, which measure the x, y, and z axis of vehicle acceleration, are strain gauge type with linear millivolt output proportional to acceleration. Angular rate sensors,

measuring vehicle roll, pitch, and yaw rates, are ultra-small, solid-state units designed for crash test service. The data acquisition hardware and software conform to the latest SAE J211, Instrumentation for Impact Test. Each of the channels is capable of providing precision amplification, scaling, and filtering based on transducer specifications and calibrations. During the test, data are recorded from each channel at a rate of 10,000 samples per second with a resolution of one part in 65,536. Once data are recorded, internal batteries back these up inside the unit in case the primary battery cable is severed. Initial contact of the pressure switch on the vehicle bumper provides a time zero mark and initiates the recording process. After each test, the data are downloaded from the DAS unit into a laptop computer at the test site. The Test Risk Assessment Program (TRAP) software then processes the raw data to produce detailed reports of the test results.

Each DAS is returned to the factory annually for complete recalibration and to ensure that all instrumentation used in the vehicle conforms to the specifications outlined by SAE J211. All accelerometers are calibrated annually by means of an ENDEVCO® 2901 precision primary vibration standard. This standard and its support instruments are checked annually and receive a National Institute of Standards Technology (NIST) traceable calibration. The rate transducers used in the data acquisition system receive calibration via a Genisco Rate-of-Turn table. The subsystems of each data channel are also evaluated annually, using instruments with current NIST traceability, and the results are factored into the accuracy of the total data channel per SAE J211. Calibrations and evaluations are also made anytime data are suspect. Acceleration data are measured with an expanded uncertainty of ± 1.7 percent at a confidence factor of 95 percent ($k = 2$).

TRAP uses the DAS-captured data to compute the occupant/compartiment impact velocities, time of occupant/compartiment impact after vehicle impact, and highest 10-millisecond (ms) average ridedown acceleration. TRAP calculates change in vehicle velocity at the end of a given impulse period. In addition, maximum average accelerations over 50-ms intervals in each of the three directions are computed. For reporting purposes, the data from the vehicle-mounted accelerometers are filtered with an SAE Class 180-Hz low-pass digital filter, and acceleration versus time curves for the longitudinal, lateral, and vertical directions are plotted using TRAP.

TRAP uses the data from the yaw, pitch, and roll rate transducers to compute angular displacement in degrees at 0.0001-s intervals, and then plots yaw, pitch, and roll versus time. These displacements are in reference to the vehicle-fixed coordinate system with the initial position and orientation being initial impact. Rate of rotation data is measured with an expanded uncertainty of ± 0.7 percent at a confidence factor of 95 percent ($k = 2$).

4.3.2. Anthropomorphic Dummy Instrumentation

An Alderson Research Laboratories Hybrid II, 50th percentile male anthropomorphic dummy, restrained with lap and shoulder belts, was placed in the front seat on the impact side of the 1100C vehicle. The dummy was not instrumented.

4.3.3. Photographic Instrumentation Data Processing

Photographic coverage of the test included three digital high-speed cameras:

- One located overhead with a field of view perpendicular to the ground and directly over the impact point.
- One placed upstream from the installation at an angle to have a field of view of the interaction of the rear of the vehicle with the installation.
- A third placed with a field of view parallel to and aligned with the installation at the downstream end.

A flashbulb on the impacting vehicle was activated by a pressure-sensitive tape switch to indicate the instant of contact with the TL-3 Transition with a Storm Drain Inlet. The flashbulb was visible from each camera. The video files from these digital high-speed cameras were analyzed to observe phenomena occurring during the collision and to obtain time-event, displacement, and angular data. A digital camera recorded and documented conditions of each test vehicle and the installation before and after the test.

Chapter 5. MASH TEST 3-20 (CRASH TEST 619551-01-1)

5.1. TEST DESIGNATION AND ACTUAL IMPACT CONDITIONS

See Table 5.1 for details of *MASH* impact conditions for this test and Table 5.2 for the exit parameters. Figure 5.1 and Figure 5.2 depict the target impact setup.

Table 5.1. Impact Conditions for *MASH TEST 3-20*, Crash Test 619551-01-1.

Test Parameter	Specification	Tolerance	Measured
Impact Speed (mi/h)	62	±2.5 mi/h	62.6
Impact Angle (deg)	25	±1.5°	25.3
Impact Severity (kip-ft)	51	≥51 kip-ft	58.3
Impact Location	123 inches upstream from the downstream edge of the concrete	±1 ft	121.3 inches upstream from the downstream edge of the concrete

Table 5.2. Exit Parameters for *MASH TEST 3-20*, Crash Test 619551-01-1.

Exit Parameter	Measured
Speed (mi/h)	49.1
Trajectory (deg)	10.8
Heading (deg)	10.3
Brakes applied post impact (s)	1.75
Vehicle at rest position	215 ft downstream of impact point 55 ft to the traffic side facing 10° left
Comments:	Vehicle remained upright and stable Vehicle crossed the exit box at 42 ft downstream from loss of contact

^a Not less than 32.8 ft downstream from loss of contact for cars and pickups is optimal.



Figure 5.1. TL-3 Transition with a Storm Drain Inlet/Test Vehicle Geometrics for Test 619551-01-1.



Figure 5.2. TL-3 Transition with a Storm Drain Inlet/Test Vehicle Impact Location 619551-01-1.

5.2. WEATHER CONDITIONS

Table 5.3 provides the weather conditions for 619551-01-1.

Table 5.3. Weather Conditions 619551-01-1.

Date of Test	2023-06-27
Wind Speed (mi/h)	8
Wind Direction (deg)	186
Temperature (°F)	89
Relative Humidity (%)	72
Vehicle Traveling (deg)	195

5.3. TEST VEHICLE

Figure 5.3 and Figure 5.4 show the 2017 Nissan Versa used for the crash test. Table 5.4 shows the vehicle measurements. Figure C.1 in Appendix C.1 gives additional dimensions and information on the vehicle.



Figure 5.3. Impact Side of Test Vehicle before Test 619551-01-1.



Figure 5.4. Opposite Impact Side of Test Vehicle before Test 619551-01-1.

Table 5.4. Vehicle Measurements for Test 619551-01-1.

Test Parameter	Specification	Tolerance	Measured
Dummy (if applicable) ^a (lb)	165	N/A	165
Inertial Weight (lb)	2420	±55	2437
Gross Static ^a (lb)	2585	±55	2602
Wheelbase (inches)	98	±5	102.4
Front Overhang (inches)	35	±4	32.5
Overall Length (inches)	169	±8	175.4
Overall Width (inches)	65	±3	66.7
Hood Height (inches)	28	±4	30.5
Track Width ^b (inches)	59	±2	58.4
CG aft of Front Axle ^c (inches)	39	±4	41.1
CG above Ground ^{c,d} (inches)	N/A	N/A	N/A

Note: N/A = not applicable; CG = center of gravity.

^a If a dummy is used, the gross static vehicle mass should be increased by the mass of the dummy.

^b Average of front and rear axles.

^c For test inertial mass.

^d 2270P vehicle must meet minimum CG height requirement.

5.4. TEST DESCRIPTION

Table 5.5 lists events that occurred during Test 619551-01-1. Figures C.4, C.5, and C.6 in Appendix C.2 present sequential photographs during the test.

Table 5.5. Events during Test 619551-01-1.

Time (s)	Events
0.0000	Vehicle impacted the installation
0.0140	Post 16 began to lean toward field side
0.0200	Post 15, 17, and 18 began to lean toward field side
0.0380	Vehicle began to redirect
0.0630	Windshield began to crack due to flexing of vehicle body
0.0860	Front passenger side window breaks due to dummy head contact
0.1500	Vehicle was parallel with installation
0.2520	49.1 mi/h at a trajectory/heading of 10.8 and 10.3 degrees respectively

5.5. DAMAGE TO TEST INSTALLATION

The concrete was damaged at post 15, and the rail was scuffed and deformed between posts 15 and 18. The drop inlet top was pushed back 0.5-inch. Post 15 was leaning 1 degree to the field side, and posts 16 and 17 were leaning 2 degrees. Table 5.6 describes the deflection and working width of the TL-3 Transition with a Storm Drain Inlet. Figure 5.5 and Figure 5.6 show the damage to the TL-3 Transition with a Storm Drain Inlet.

Table 5.6. Deflection and Working Width of the TL-3 Transition with a Storm Drain Inlet for Test 619551-01-1.

Test Parameter	Measured
Permanent Deflection/Location	1 inch toward field side, at post 16
Dynamic Deflection	1.9 inches toward field side between posts 16 and 17
Working Width ^a and Height	52.3 inches, at a height of 0.0 inches at the traffic side of the rail to the field side edge of the inlet cover

^a Per *MASH*, "The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article." In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.



Figure 5.5. Traffic Side of the TL-3 Transition with a Storm Drain Inlet at Impact Location after Test 619551-01-1.



Figure 5.6. Field Side of the TL-3 Transition with a Storm Drain Inlet at Impact Location after Test 619551-01-1.

5.6. DAMAGE TO TEST VEHICLE

Figure 5.7 and Figure 5.8 show the damage sustained by the vehicle. Figure 5.9 and Figure 5.10 show the interior of the test vehicle. Table 5.7 and Table 5.8 provide details on the occupant compartment deformation and exterior vehicle damage. Figures C.2 and C.3 in Appendix C.1 provide exterior crush and occupant compartment measurements.



Figure 5.7. Impact Side of Test Vehicle after Test 619551-01-1.



Figure 5.8. Rear Impact Side of Test Vehicle after Test 619551-01-1.



Figure 5.9. Overall Interior of Test Vehicle after Test 619551-01-1.



Figure 5.10. Interior of Test Vehicle on Impact Side after Test 619551-01-1.

Table 5.7. Occupant Compartment Deformation 619551-01-1.

Test Parameter	Specification (inches)	Measured (inches)
Roof	≤4.0	0.0
Windshield	≤3.0	2.75
A and B Pillars	≤5.0 overall/≤3.0 lateral	0.75
Foot Well/Toe Pan	≤9.0	1.0
Floor Pan/Transmission Tunnel	≤12.0	0.0
Side Front Panel	≤12.0	0.75
Front Door (above Seat)	≤9.0	0.0
Front Door (below Seat)	≤12.0	2.0

Table 5.8. Exterior Vehicle Damage 619551-01-1.

Side Windows	The front right side window shattered, but it was not caused by penetration by the test article.
Maximum Exterior Deformation	9 inches in the front plane at the right corner at bumper height
VDS	01RFQ5
CDC	01FREW3
Fuel Tank Damage	None
Description of Damage to Vehicle:	The bumper, grill, right front fender, right front wheel, right front control arm, frame rail, headlights, windshield, right front a-pillar, right doors, right quarter fender, right tail light, and right front side window were damaged. The top of the right front door had a 2.75-inch gap. The windshield had extensive cracking due to flexing of the body, but there were no holes and no tearing in the laminate.

5.7. OCCUPANT RISK FACTORS

Data from the accelerometers were digitized for evaluation of occupant risk, and the results are shown in Table 5.9. Figure C.7 in Appendix C.3 shows the vehicle angular displacements, and Figures C.8 through C.10 in Appendix C.4 show acceleration versus time traces.

Table 5.9. Occupant Risk Factors for Test 619551-01-1.

Test Parameter	Specification ^a	Measured	Time
OIV, Longitudinal (ft/s)	≤40.0 <i>30.0</i>	20	0.0787 seconds on right side of interior
OIV, Lateral (ft/s)	≤40.0 <i>30.0</i>	33.7	0.0787 seconds on right side of interior
Ridedown, Longitudinal (g)	≤20.49 <i>15.0</i>	4.9	0.0787 - 0.0887 seconds
Ridedown, Lateral (g)	≤20.49 <i>15.0</i>	10.5	0.1791 - 0.1891 seconds
Theoretical Head Impact Velocity (THIV) (m/s)	N/A	11.9	0.0773 seconds on right side of interior
Acceleration Severity Index (ASI)	N/A	2.63	0.0516 - 0.1016 seconds
50-ms Moving Avg. Accelerations (MA) Longitudinal (g)	N/A	-11.3	0.0360 - 0.0860 seconds
50-ms MA Lateral (g)	N/A	-19.7	0.0207 - 0.0707 seconds
50-ms MA Vertical (g)	N/A	2.4	0.0097 - 0.0597 seconds
Roll (deg)	≤75	3.9	0.0559 seconds
Pitch (deg)	≤75	2.9	0.1585 seconds
Yaw (deg)	N/A	39.9	0.6031 seconds

^a. Values in italics are the preferred MASH values

5.8. TEST SUMMARY

Figure 5.11 summarizes the results of MASH Test 619551-01-1.







 <p style="text-align: center;">0.000 s</p>	Test Agency	Texas A&M Transportation Institute (TTI)					
	Test Standard/Test No.	MASH 2016, Test 3-20					
	TTI Project No.	619551-01-1					
	Test Date	2023-06-27					
 <p style="text-align: center;">0.100 s</p>	TEST ARTICLE						
	Type	Longitudinal Barrier					
	Name	TL-3 Transition with a Storm Drain Inlet					
	Length	102 feet 10 inches					
 <p style="text-align: center;">0.200 s</p>	Key Materials	Thrie-beam & W-beam rail, 72-inch wide-flange guardrail post, wingwall post, pre-cast drop inlet, Concrete parapet					
	Soil Type and Condition	Type D Grade 1 crushed concrete, damp					
	TEST VEHICLE						
	Type/Designation	1100C					
 <p style="text-align: center;">0.300 s</p>	Year, Make and Model	2017 Nissan Versa					
	Inertial Weight (lb)	2437					
	Dummy (lb)	165					
	Gross Static (lb)	2602					
IMPACT CONDITIONS							
Impact Speed (mi/h)	62.6						
Impact Angle (deg)	25.3						
Impact Location	121.3 inches upstream from the downstream edge of the concrete						
Impact Severity (kip-ft)	58.3						
EXIT CONDITIONS							
Exit Speed (mi/h)	49.1						
Trajectory/Heading Angle (deg)	10.8 / 10.3						
Exit Box Criteria	Vehicle crossed the exit box a 42 ft downstream from loss of contact.						
Stopping Distance	215 ft downstream 55 ft to the traffic side						
TEST ARTICLE DEFLECTIONS							
Dynamic (inches)	1.9						
Permanent (inches)	1						
Working Width / Height (inches)	52.3 / 0.0						
VEHICLE DAMAGE							
VDS	01RFQ5						
CDC	01FREW3						
Max. Ext. Deformation (inches)	9						
Max Occupant Compartment Deformation	2.75 inches in the windshield						
OCCUPANT RISK VALUES							
Long. OIV (ft/s)	20	Long. Ridedown (g)	4.9	Max 50-ms Long. (g)	-11.3	Max Roll (deg)	3.9
Lat. OIV (ft/s)	33.7	Lat. Ridedown (g)	10.5	Max 50-ms Lat. (g)	-19.7	Max Pitch (deg)	2.9
THIV (m/s)	11.9	ASI	2.63	Max 50-ms Vert. (g)	2.4	Max Yaw (deg)	39.9
							

Figure 5.11. Summary of Results for MASH Test 3-20 on TL-3 Transition with a Storm Drain Inlet.

Chapter 6. SUMMARY AND CONCLUSIONS

6.1. ASSESSMENT OF TEST RESULTS

The crash test reported herein was performed in accordance with *MASH* Test 3-20 on the TL-3 Transition with a Storm Drain Inlet.

6.2. CONCLUSIONS

Table 6.1 shows that the TL-3 Transition with a Storm Drain Inlet met the performance criteria for *MASH* Test 3-20 Longitudinal Barrier.

Table 6.1. Assessment Summary for *MASH* Test 3-20 Tests on TL-3 Transition with a Storm Drain Inlet.

Evaluation Criteria	Description	Test 619551-01-1
A	Contain, Redirect, or Controlled Stop	S
D	No Penetration into Occupant Compartment	S
F	Roll and Pitch Limit	S
H	OIV Threshold	S
I	Ridedown Threshold	S
Overall		Pass


Note: S = Satisfactory; N/A = Not Applicable.


¹ See Table 3.2 for details


REFERENCES


1. AASHTO. *Manual for Assessing Safety Hardware*, Second Edition. American Association of State Highway and Transportation Officials, Washington, DC, 2016.
2. Abu-Odeh, Akram; Schroeder, William J.L., *MASH TL-3 Transition Design with a Storm Drain*, Texas A&M Transportation Institute, College Station, TX, 2023


**APPENDIX A. DETAILS OF TL-3 TRANSITION WITH A STORM
DRAIN INLET**















		Roadside Safety and Physical Security Division - Proving Ground
Project #619551-01 Transition with Inlet		2023-06-26
Drawn by GES	Scale 1:100	Sheet 5 of 10 Concrete






- 7a. All rebar dimensions are to center of bar unless otherwise indicated by "cvt" (cover).
- 7b. See Straight Beam (previous sheet) for all details not shown here.


		Roadside Safety and Physical Security Division - Proving Ground
Project #619551-01 Transition with Inlet		2023-06-26
Drawn by GES	Scale 1:25	Sheet 7 of 10 Tapered Beam





		Roadside Safety and Physical Security Division - Proving Ground	
Project #619551-01 Transition with Inlet		2023-06-26	
Drawn by GES	Scale 1:50	Sheet 9 of 10	Moment Slab and Parapet

Rebar Bends




10a. All bars on this sheet are grade 60 rebar.

		Roadside Safety and Physical Security Division - Proving Ground
Project #619551-01 Transition with Inlet		2023-06-26
Drawn by GES	Scale 1:10	Sheet 10 of 10 Rebar Bends


Terminal Details

#	Part Name	QTY.
1	Post Bottom	2
2	Post Top	2
3	9'-4" span Terminal Rail	1
4	Strut	1
5	Strut Spacer	2
6	Strut Bracket	2
7	Guardrail Anchor Bracket	1
8	Anchor Cable Assembly	1
9	Bearing Plate	1
10	Bolt, 7/16 x 2 1/2" hex	8
11	Washer, 7/16 F844	32
12	Nut, 7/16 heavy hex	8
13	Nut, 1/2 hex	4
14	Washer, 1/2 F844	4
15	Bolt, 5/8 x 1 1/2" hex	8
16	Washer, 5/8 F844	8
17	Recessed Guardrail Nut	10
18	1-1/4" Guardrail Bolt	2
19	Bolt, 7/8 x 8 1/2" hex	2
20	Washer, 7/8 F844	4
21	Nut, 7/8 hex	2




1a. 7/16" x 2-1/2" Bolts are ASTM A449. All other Bolts are ASTM A307. All Nuts (except Recessed Guardrail Nuts) are ASTM A563A unless otherwise indicated.
1c. All steel parts shall be galvanized.


	Roadside Safety and Physical Security Division - Proving Ground	
	Project # Terminal	2022-07-08
Drawn by GES	Scale 1:25	Sheet 1 of 6 Terminal Details



		Roadside Safety and Physical Security Division - Proving Ground
Project # Terminal		2022-07-08
Drawn by GES	Scale 1:10	Sheet 2 of 6 Post Bottom


T:\Drafting Department\Solidworks\Standard Parts\Guardrail Parts and Subs\Guardrail Drawings\Midwest Terminal






T:\Drafting Department\Solidworks\Standard Parts\Guardrail Parts and Subs\Guardrail Drawings\Midwest Terminal

		Roadside Safety and Physical Security Division - Proving Ground
Project #	Terminal	2022-07-08
Drawn by	Scale	Sheet
GES	1:10	4 of 6 - Strut Parts






29/32" x 1-1/8" Slots

9'-4" span Terminal Rail


Scale 1:20 - See 4-space W-beam Guardrail drawing for cross-section and other dimensions.



Anchor Cable Assembly





		Roadside Safety and Physical Security Division - Proving Ground
Project #	Terminal	2022-07-08
Drawn by	Scale	Sheet
GES	1:5	6 of 6 Assorted Parts B

T:\Drafting Department\Solidworks\Standard Parts\Guardrail Parts and Subs\Guardrail Drawings\Midwest Terminal





T:\Drafting Department\Solidworks\Standard Parts\Guardrail Parts and Subs\Guardrail Drawings\Guardrail Bolt

Recessed Guardrail Nut




1a. Material is ASTM A 563 Grade A.


		Roadside Safety and Physical Security Division - Proving Ground
Recessed Guardrail Nut		2022-07-18
Drawn by GES	Scale 2:1	Sheet 1 of 1







T:\Drafting Department\Solidworks\Standard Parts\Guardrail Parts and Subs\Guardrail Drawings\Washer, rect.



T:\Drafting Department\Solidworks\Standard Parts\Guardrail Parts and Subs\Guardrail Drawings\Post, 72" Wide Flange for W-beam



T:\Drafting Department\Solidworks\Standard Parts\Guardrail Parts and Subs\Guardrail Drawings\W-Beam Guardrail




Section A-A
Scale 1 : 5
Typical all Thriebeams


- 1a. 12 gauge is 0.1046" before galvanizing and 0.1084" after, and 10 gauge is 0.1345" before galvanizing and 0.1382" after.
- 1b. Not all versions shown here used in all installations.

		Roadside Safety and Physical Security Division - Proving Ground	
		Thrie-beam 2022-07-13	
Drawn by GES	Scale 1:30	Sheet 1 of 1	


Thrie-beam End Shoe

10 gauge (0.1345" before galvanizing)






		Roadside Safety and Physical Security Division - Proving Ground
Thrie-beam Terminal Connector		202-07-18
Drawn by GES	Scale 1:5	Sheet 1 of 1

Thrie to W-Beam, asymmetric 10 gauge



Elevation View



		Roadside Safety and Physical Security Division - Proving Ground
Thrie- to W-beam Asymmetric Transition		2022-07-18
Drawn by GES	Scale 1:10	Sheet 1 of 1

APPENDIX B. SUPPORTING CERTIFICATION DOCUMENTS

Certified Analysis

615251



Valtr, LLC
 2548 N.E. 28th St.
 Ft Worth (THP), TX 76111 Phn:(817) 665-1499
Customer: TEXAS A&M TRANSPORTATION INSTT
 ROADSIDE SAFETY & PHYSICA
 BUSINESS OFFICE
 3135 TAMU
 COLLEGE STATION, TX 77843-3135
Project: STOCK

Order Number: 1352772 **Prod Ln Grp:** 0-OE2.0
Customer PO: 612341
BOL Number: 89568
Document #: 1
Shipped To: TX
Use State: TX
Ship Date:

As of 11/11/22



Qty	Part #	Description	Spec	CL	TY	Heat Code/Heat	Yield	TS	Fig	C	Min	P	S	SI	Cu	Cb	Cr	Vn
4	11G	12/12/63/1.5/S			2	F13122												
	M-180		A		2	277506	65,000	84,374	24.3	0.200	0.790	0.016	0.004	0.010	0.120	0.000	0.080	0.001
	M-180		A		2	277540	59,744	76,903	26.9	0.180	0.740	0.010	0.004	0.010	0.100	0.001	0.050	0.002
	M-180		A		2	277541	61,280	79,207	25.9	0.190	0.730	0.010	0.002	0.020	0.100	0.001	0.040	0.001
					2	F13922												
	M-180		A		2	279432	63,794	82,495	22.6	0.180	0.730	0.015	0.002	0.020	0.090	0.000	0.070	0.003
	M-180		A		2	279435	64,684	84,763	23.1	0.190	0.730	0.013	0.002	0.030	0.090	0.000	0.060	0.002
	M-180		A		2	279436	63,668	82,065	23.1	0.200	0.720	0.012	0.003	0.010	0.090	0.000	0.060	0.002
	M-180		A		2	279440	53,591	83,174	24.2	0.200	0.740	0.009	0.003	0.020	0.110	0.000	0.060	0.002
	M-180		A		2	279442	60,706	78,007	24.6	0.170	0.730	0.008	0.004	0.010	0.100	0.001	0.050	0.001
						F12722												
4	211G	11/21/26/3/1.5/S				F12722												
	M-180		A			276319	61,591	79,925	24.4	0.190	0.750	0.011	0.002	0.020	0.110	0.000	0.100	0.001
	M-180		A			276319	61,591	79,925	24.4	0.190	0.750	0.011	0.002	0.020	0.110	0.000	0.100	0.001
	M-180		A			276349	60,441	80,006	25.8	0.190	0.730	0.009	0.003	0.010	0.110	0.000	0.080	0.001
	M-180		A			276349	60,441	80,006	25.8	0.190	0.730	0.009	0.003	0.010	0.110	0.000	0.080	0.001
	M-180		A			276350	60,512	80,175	23.4	0.190	0.740	0.009	0.005	0.010	0.120	0.000	0.070	0.001
	M-180		A			276350	60,512	80,175	23.4	0.190	0.740	0.009	0.005	0.010	0.120	0.000	0.070	0.001
	M-180		A			276351	60,982	80,245	23.0	0.190	0.740	0.009	0.003	0.010	0.120	0.000	0.080	0.001
	M-180		A			276351	60,982	80,245	23.0	0.190	0.740	0.009	0.003	0.010	0.120	0.000	0.080	0.001
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
9	533G	60 POST/8.5/DDR/7				A-36												
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	M-180		A			276800	60,651	80,504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.000	0.060	0.001
	M-180		A			1114803	54,500	67,500	28.3</									

Certified Analysis



Valtir, LLC

2548 NE 28th St.

Ft Worth (THP), TX 76111 Pm:(817) 665-1499

Customer: TEXAS A&M TRANSPORTATION INSTI

ROADSIDE SAFETY & PHYSICA
BUSINESS OFFICE

3135 TAMU
COLLEGE STATION, TX 77843-3135

Project: STOCK

Order Number: 13527772

Prod Ln Grp: 0-OE2.0

Customer PO: 612541

BOL Number: 89568


Ship Date:

Document #: 1

Shipped To: TX

Use State: TX

As of: 11/11/22



Qty	Part #	Description	Spec	CL	TY	Heat Code/Heat	Yield	TS	Elg	C	Ma	P	S	SI	Cu	Cb	Cr	Vn
1	975G	TI/END SHOE	M-180	B	2	270936	48.995	60.112	35.8	0.050	0.480	0.012	0.003	0.020	0.110	0.000	0.070	0.001
24	3320G	3/16"X1.75"X3" WASHER	FAST			108093												
11	4076B	WD BLK RTD 6X8X14	WOOD			4830												
10	6149B	WD BLK RTD 6X8X18	WOOD			7080												
6	14784G	70 POST/8.5#/3HTX	A-36			59106347	62.348	76.348	27.0	0.080	0.970	0.013	0.018	0.170	0.290	0.013	0.150	0.001
3	14785G	60 POST/8.5#/3HTX/7:7	A-36			59106347	62.348	76.348	27.0	0.080	0.970	0.013	0.018	0.170	0.290	0.013	0.150	0.001
1	32218G	TI0/TRAN/TB-WB/ASYM/RT	MISC			833M66260												

Upon delivery, all materials subject to Valtir, LLC Storage Stain Policy QMS-LQ-002.

ALL STEEL USED WAS MELTED AND MANUFACTURED IN USA AND COMPLIES WITH THE BUY AMERICA ACT, 23 CFR 635.410.
 ALL GUARDRAIL MEETS AASHTO M-180, ALL STRUCTURAL STEEL MEETS ASTM A36 UNLESS OTHERWISE STATED.
 ALL COATINGS PROCESSES OF THE STEEL OR IRON ARE PERFORMED IN USA AND COMPLIES WITH THE "BUY AMERICA ACT", 23 CFR 635.410.
 ALL GALVANIZED MATERIAL CONFORMS WITH ASTM A-123 (US DOMESTIC SHIPMENTS)
 ALL GALVANIZED MATERIAL CONFORMS WITH ASTM A-123 & ISO 1461 (INTERNATIONAL SHIPMENTS)
 FINISHED GOOD PART NUMBERS ENDING IN SUFFIX B,P, OR S, ARE UNCOATED

Certified Analysis



Valtir, LLC

2548 N.E. 28th St.

Ft Worth (THP), TX 76111 Phn:(817) 665-1499

Customer: TEXAS A&M TRANSPORTATION INSTI

ROADSIDE SAFETY & PHYSICA

BUSINESS OFFICE

3135 TAMU

COLLEGE STATION, TX 77843-3135

Order Number: 1352772 Prod Ln Grp: 0-OE2.0

Customer PO: 612541


BOL Number: 89568

Document #: 1

Shipped To: TX

Use State: TX

As of: 11/11/22



Project: STOCK
BOLTS COMPLY WITH ASTM A-307 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM A-153, UNLESS OTHERWISE STATED.
NUTS COMPLY WITH ASTM A-563 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM A-153, UNLESS OTHERWISE STATED.
WASHERS COMPLY WITH ASTM F-436 SPECIFICATION AND/OR F-844 AND ARE GALVANIZED IN ACCORDANCE WITH ASTM F-2329, UNLESS OTHERWISE STATED.
3/4" DIA CABLE 6X19 ZINC COATED SWAGED END AISI C-1095 STEEL ANNEALED STUD 1" DIA ASTM 449 AASHTO M30, TYPE II BREAKING STRENGTH - 46000 LB
State of Texas, County of Tarrant. Sworn and subscribed before me this 11th day of November, 2022.

Notary Public:
Commission Expires: / /

Quality Assurance

Certified By:

Valtir, LLC



Certified Analysis



Valtr, LLC

2548 N.E. 28th St.

Ft Worth (THP), TX 76111 Phn:(817) 665-1499

Customer: TEXAS A&M TRANSPORTATION INSTTI

ROADSIDE SAFETY & PHYSICA

BUSINESS OFFICE

3135 TAMU

COLLEGE STATION, TX 77843-3135

Project: STOCK

Order Number: 1353394

Prod Ln Grp: 0-OE2.0

Customer PO: 615251


BOL Number: 89569

Document #: 1

Shipped To: TX

Use State: TX

As of: 11/11/22



Qty	Part#	Description	Spec	CL	TY	Heat Code/Heat	Yield	TS	Efg	C	Ma	P	S	SI	Cu	Cb	Cr	Vn
4	11G	12/12/6/3/1.5/S			2	F13122												
	M-180		A	2		277506	65,000	84,374	24.3	0.200	0.790	0.016	0.004	0.010	0.120	0.000	0.080	0.001
	M-180		A	2		277540	59,744	76,903	26.9	0.180	0.740	0.010	0.004	0.010	0.100	0.001	0.050	0.002
	M-180		A	2		277541	61,280	79,207	25.9	0.190	0.730	0.010	0.002	0.020	0.100	0.001	0.040	0.001
	11G			2		F13222												
	M-180		A	2		2122871	58,100	81,100	23.0	0.210	0.750	0.009	0.003	0.020	0.070	0.002	0.040	0.003
	M-180		A	2		2122872	50,800	74,300	26.0	0.220	0.790	0.009	0.002	0.030	0.080	0.001	0.040	0.003
	M-180		A	2		2122872	61,000	83,300	999.0	0.220	0.790	0.009	0.002	0.030	0.080	0.000	0.040	0.003
	M-180		A	2		277506	65,000	84,374	24.3	0.200	0.790	0.016	0.004	0.010	0.120	0.000	0.080	0.001
	M-180		A	2		277540	59,744	76,903	26.9	0.180	0.740	0.010	0.004	0.010	0.100	0.001	0.050	0.002
	M-180		A	2		277541	61,280	79,207	25.9	0.190	0.730	0.010	0.002	0.020	0.100	0.001	0.040	0.001
	M-180		A	2		277542	61,872	79,516	25.8	0.200	0.760	0.009	0.005	0.010	0.100	0.000	0.050	0.001
8	533G	60 POST/8.5/DDR/7	A-36			1114803	54,500	67,500	28.3	0.070	0.840	0.007	0.022	0.230	0.130	0.015	0.040	0.002
	533G		A-36			2104723	54,000	66,200	26.0	0.070	0.800	0.013	0.020	0.200	0.100	0.014	0.040	0.002
	533G		A-36			59106347	62,348	76,348	27.0	0.080	0.970	0.013	0.018	0.170	0.290	0.013	0.150	0.001
40	3320G	3/16-X1.75-X3* WASHER	FAST			108093												
135	3340G	5/8" GR HEX NUT	FAST			22-35-011												
40	3360G	5/8-X1.25" GR BOLT	A307-3360G			A15007-8												
40	3400G	5/8-X2" GR BOLT	A307-3400G			A14956-9												
15	3500G	5/8-X1.0" GR BOLT A307	A307-3500G			A20068-2												

Certified Analysis



Valtr, LLC

2548 N.E. 28th St.

Ft Worth (THP), TX 76111 Phn:(817) 655-1499

Customer: TEXAS A&M TRANSPORTATION INSTTI

ROADSIDE SAFETY & PHYSICA

BUSINESS OFFICE

3135 TAMU

COLLEGE STATION, TX 77843-3135

Project: STOCK

Order Number: 1353394

Prod Ln Grp: 0-OE2.0

Customer PO: 615251

BOL Number: 89569

Ship Date:

As of: 11/11/22

Document #: 1

Shipped To: TX

Use State: TX



Qty	Part #	Description	Spec	CL	TY	Heat Code/Heat	Yield	TS	Elg	C	Mn	P	S	SI	Cu	Cb	Cr	Vn
14	40768	WD BLK RTD 6X8X14	WOOD			4850												
6	6149B	WD BLK RTD 6X8X18	WOOD			7080												
2	10967G	12/9/4.5/31.5/S				F14522												
			M-180	A	2	279437	53.668	82.065	23.1	0.200	0.720	0.012	0.003	0.010	0.090	0.000	0.060	0.002
			M-180	A	2	281434	61.121	79.287	26.0	0.180	0.740	0.014	0.004	0.010	0.120	0.000	0.050	0.004
			M-180	A	2	281442	61.762	80.996	25.6	0.019	0.730	0.012	0.004	0.010	0.110	0.000	0.060	0.002
			M-180	A	2	281442	61.762	80.996	25.6	0.019	0.730	0.012	0.004	0.010	0.110	0.000	0.060	0.002
						L12822												
			M-180	A	2	275639	62.212	82.063	25.3	0.190	0.073	0.014	0.003	0.020	0.140	0.000	0.080	0.002
			M-180	A	2	275642	63.291	82.357	23.2	0.190	0.740	0.015	0.005	0.010	0.120	0.000	0.100	0.002
			M-180	A	2	275875	61.764	79.897	23.9	0.190	0.730	0.011	0.001	0.010	0.110	0.000	0.060	0.002
			M-180	A	2	276471	61.104	80.038	25.5	0.190	0.720	0.011	0.003	0.010	0.110	0.000	0.050	0.001
			M-180	A	2	276472	62.468	79.978	25.4	0.200	0.730	0.011	0.002	0.010	0.110	0.000	0.050	0.001
			M-180	A	2	276474	63.174	81.018	24.8	0.190	0.720	0.009	0.002	0.020	0.100	0.000	0.060	0.001
			M-180	A	2	276477	61.527	80.001	24.7	0.190	0.720	0.012	0.005	0.010	0.100	0.000	0.060	0.001
			M-180	A	2	276478	60.258	79.671	21.8	0.200	0.740	0.010	0.005	0.010	0.110	0.000	0.050	0.002
			M-180	A	2	276480	62.278	80.531	24.5	0.200	0.720	0.010	0.004	0.010	0.100	0.001	0.050	0.002
			M-180	A	2	276481	60.277	78.610	23.2	0.190	0.740	0.009	0.004	0.010	0.110	0.000	0.050	0.001
			M-180	A	2	276800	60.651	80.504	24.4	0.190	0.720	0.008	0.003	0.020	0.090	0.001	0.060	0.000
						F14522												
			M-180	A		279437	53.668	82.065	23.1	0.200	0.720	0.012	0.003	0.010	0.090	0.000	0.060	0.002
			M-180	A		281434	61.121	79.287	26.0	0.180	0.740	0.014	0.004	0.010	0.120	0.000	0.050	0.004
			M-180	A		281442	61.762	80.996	25.6	0.019	0.730	0.012	0.004	0.010	0.110	0.000	0.060	0.002

Certified Analysis



Valtr, LLC

2548 N.E. 28th St.

Ft Worth (THP), TX 76111 Phn:(817) 665-1499

Order Number: 1353394

Prod Ln Grp: 0-OE2.0

Customer PO: 615251

As of: 11/11/22

Customer: TEXAS A&M TRANSPORTATION INSTTI

BOL Number: 89569

Ship Date:

ROADSIDE SAFETY & PHYSICA

Document #: 1


BUSINESS OFFICE

Shipped To: TX

3135 TAMU

Use State: TX

Project: STOOK



Qty	Part #	Description	Spec	CL	TY	Heat Code/Heat	Yield	TS	Elg	C	Ma	P	S	SI	Cu	Cb	Cr	Va
	12365G		M-180	A		281442	61,762	80,996	25.6	0.019	0.730	0.012	0.004	0.010	0.110	0.000	0.060	0.002
			RHC		2	L31318												
			M-180	A	2	222038	63,780	82,280	22.9	0.190	0.750	0.012	0.002	0.030	0.100	0.000	0.070	0.001
			M-180	A	2	222878	64,680	81,820	25.2	0.180	0.740	0.012	0.003	0.020	0.130	0.000	0.070	0.002
			RHC		2	L34919												
	12365G		M-180	A	2	245021	64,480	83,940	22.2	0.190	0.700	0.013	0.004	0.020	0.060	0.000	0.060	0.001
			M-180	A	2	245984	62,860	80,840	26.2	0.190	0.720	0.008	0.003	0.010	0.080	0.000	0.050	0.000
			MISC			833M66260												
	1	32218G T10/TRAN/TB-WB/ASYM/RT																

Upon delivery, all materials subject to Valtr, LLC Storage Stain Policy QMS-LQ-002.

ALL STEEL USED WAS MELTED AND MANUFACTURED IN USA AND COMPLIES WITH THE BUY AMERICA ACT, 23 CFR 635.410.
 ALL GUARDRAIL MBETS AASHTO M-180, ALL STRUCTURAL STEEL MBETS ASTM A36 UNLESS OTHERWISE STATED.
 ALL COATINGS PROCESSES OF THE STEEL OR IRON ARE PERFORMED IN USA AND COMPLIES WITH THE "BUY AMERICA ACT", 23 CFR 635.410.
 ALL GALVANIZED MATERIAL CONFORMS WITH ASTM A-123 (US DOMESTIC SHIPMENTS)
 ALL GALVANIZED MATERIAL CONFORMS WITH ASTM A-123 & ISO 1461 (INTERNATIONAL SHIPMENTS)
 FINISHED GOOD PART NUMBERS ENDING IN SUFFIX B.P, OR S, ARE UNCOATED
 BOLTS COMPLY WITH ASTM A-307 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM A-153, UNLESS OTHERWISE STATED.
 NUTS COMPLY WITH ASTM A-563 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM A-153, UNLESS OTHERWISE STATED.
 WASHERS COMPLY WITH ASTM F-436 SPECIFICATION AND/OR F-844 AND ARE GALVANIZED IN ACCORDANCE WITH ASTM F-2329, UNLESS OTHERWISE STATED.
 3/4" DIA CABLE 6X19 ZINC COATED SWAGED END AISI C-1045 STEEL ANNEALED STUD 1" DIA ASTM 449 AASHTO M30, TYPE II BREAKING STRENGTH - 46000 LB

Certified Analysis



Valtr, LLC

2548 N.E. 28th St.

Ft Worth (THP), TX 76111 Pnn.(817) 665-1499

Customer: TEXAS A&M TRANSPORTATION INSTI

ROADSIDE SAFETY & PHYSICA

BUSINESS OFFICE

3135 TAMU

COLLEGE STATION, TX 77843-3135

Project: STOCK

State of Texas, County of Tarrant. Sworn and subscribed before me this 11st day of November, 2022.

Notary Public:

Commission Expires: / /



Angela Ruth Humphrey

Order Number: 1353394 Prod Ln Grp: 0-OE2.0

Customer PO: 615251

BOL Number: 89569

Document #: 1

Shipped To: TX

Use State: TX

As of 11/11/22



Certified By: *Valtr LLC*

Quality Assurance

Valtir, LLC

2548 N.E. 28th St.

Ft Worth (THP), TX 76111 Phn:(817) 665-1499

Customer: TEXAS A&M TRANSPORTATION INSTI

ROADSIDE SAFETY & PHYSICA
BUSINESS OFFICE

3135 TAMU

COLLEGE STATION, TX 77843-3135

Project: STOCK

Certified Analysis

615251
Alex
11/15

Order Number: 1358011

Prod Ln Grp: 0-OE2.0

Customer PO: 615251

BOL Number: 91067

Ship Date:

Document #: 1

Shipped To: TX

Use State: TX

As of: 5/19/23



Qty	Part #	Description	Spec	CL	TY	Heat Code/Heat	Yield	TS	Elg	C	Mn	P	S	SI	Cu	Cb	Cr	Vn
1	975G	T10/END SHOE	M-180	B		279257	48,897	60,212	37.8	0.050	0.470	0.010	0.002	0.030	0.090	0.001	0.060	0.001
2	1245G	T12/125/6R@1% 75/5				F11523												
			M-180	A		285738	63,677	82,257	22.4	0.200	0.740	0.008	0.002	0.020	0.100	0.001	0.060	0.002
			M-180	A		285747	61,339	80,344	26.1	0.200	0.740	0.008	0.004	0.010	0.090	0.000	0.050	0.002
			M-180	A		285752	62,974	81,111	24.6	0.190	0.730	0.009	0.002	0.010	0.090	0.000	0.050	0.001
			MISC			287476												
			MISC			140456												
			M-180	B	2	C89858	59,300	81,600	24.2	0.200	0.490	0.014	0.002	0.030	0.090	0.000	0.060	0.001

Upon delivery, all materials subject to Valtir, LLC Storage Stain Policy QMS-1-Q-002.

ALL STEEL USED WAS MELTED AND MANUFACTURED IN USA AND COMPLIES WITH THE BUY AMERICA ACT, 23 CFR 635.410.

ALL GUARDRAIL MEETS AASHTO M-180, ALL STRUCTURAL STEEL MEETS ASTM A36 UNLESS OTHERWISE STATED.

ALL COATINGS PROCESSES OF THE STEEL OR IRON ARE PERFORMED IN USA AND COMPLIES WITH THE "BUY AMERICA ACT", 23 CFR 635.410.

ALL GALVANIZED MATERIAL CONFORMS WITH ASTM A-123 (US DOMESTIC SHIPMENTS)

ALL GALVANIZED MATERIAL CONFORMS WITH ASTM A-123 & ISO 1461 (INTERNATIONAL SHIPMENTS)

FINISHED GOOD PART NUMBERS ENDING IN SUFFIX B.P. OR S. ARE UNCOATED

BOLTS COMPLY WITH ASTM A-307 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM A-153, UNLESS OTHERWISE STATED.


NUTS COMPLY WITH ASTM A-563 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM A-153, UNLESS OTHERWISE STATED.

WASHERS COMPLY WITH ASTM F-436 SPECIFICATION AND/OR F-844 AND ARE GALVANIZED IN ACCORDANCE WITH ASTM F-2329, UNLESS

OTHERWISE STATED.

3/4" DIA CABLE 6X19 ZINC COATED SWAGED END AISI C-1035 STEEL, ANNEALED STUD 1" DIA ASTM 449 AASHTO M30, TYPE II BREAKING

STRENGTH - 46000 LB

	QF 7.3-01 Concrete Sampling	Doc. No. QF 7.3-01	Revision Date: 2020-07-29
	Quality Form	Revised by: B.L. Griffith Approved by: D. L. Kuhn	Revision: 7

Project No: 615251 **Casting Date:** 12/6/2022 **Mix Design (psi):** 3600

Name of Technician Taking Sample <u>Terracon</u>	Name of Technician Breaking Sample <u>Terracon</u>
Signature of Technician Taking Sample <u>Terracon</u>	Signature of Technician Breaking Sample <u>Terracon</u>

Load No.	Truck No.	Ticket No.	Location (from concrete map)
T1	Gray Cheston22	70130	Moment Slab and Parapet

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average

TEXCRETE
Ready-mix Concrete Company

TEXCRETE

129993

REMIT PAYMENT TO:
P.O. BOX 138
KURTEN, TX 77862

5222 Sandy Point RD.
Bryan, Tx 77807

17534 SH 6 South
College Station, TX 77845

18935 Circle Lake Dr.
Pinehurst, TX 77362

BCS DISPATCH - 979-316-2906
PINEHURST DISPATCH - 936-232-5815
OFFICE - 979-985-3636

MBC MANAGEMENT
WAREHOUSE RD, RELIS CAMPUS, BRYA
N TX

RT 2818, TAKE THE HWY 21 ENTRANCE INTO
RELLIS CAMPUS, LT AT "T", RT AVE. A, RT
WAREHOUSE RD

TIME	FORMULA	LOAD SIZE	YARD ORDERED	DRIVER/TRUCK	PLANT TRANSACTION#
10:38	TXC3600	7.00	7.00 PD#	GRAY CHESTON22	71942
DATE	PROJECT	LOAD#	YARDS DEL	BATCH#	TICKET NUMBER
12/6/22	TTIINLE	7.00	7.00		5.00 in 70130
QUANTITY	CODE	DESCRIPTION	UNIT PRICE	EXTENDED PRICE	
7.00 CY	TXC3600	DOTC, 3600, RG, 5",			
1.00 ea	FUEL	Fuel Charge			

Thank you for your business

LEFT PLANT	ARRIVED JOB	START UNLOADING	SLUMP	CONCRETE TEMP.	AIR TEMP
10.54	11:15	11:18			
FINISH UNLOADING	LEFT JOB	ARRIVED AT PLANT	ON SITE TESTING		
			TESTING LAB:	TERRACON GESSNER CME	OTHER
			AIR	TESTED	CYLINDERS
			<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO		

Tax
Prev. AMT
Ticket Total

ADDITIONAL CHARGE 1 _____
ADDITIONAL CHARGE 2 _____
GRAND TOTAL

WARNING
IRRITATING TO THE SKIN AND EYES
Contains Portland Cement. Wear Rubber Boots and Gloves. PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact with Skin. In Case of Contact with Skin or Eyes, Rinse Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**
CONCRETE is a PERISHABLE COMMODITY and BECOMES THE PROPERTY of the PURCHASER UPON LEAVING the PLANT. ANY CHANGES or CANCELLATION of ORIGINAL INSTRUCTIONS MUST be TELEPHONED to the OFFICE BEFORE LOADING starts. The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.
All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. - Not Responsible For Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.
A \$25.00 Service Charge and Loss of the Cash Discounted will be Collected on all Returned Checks. Damage charge after 30 min. will be \$100.00/hr.


PROPERTY DAMAGE RELEASE
(TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)
Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, driveways, curbs, etc. by the delivery of this material and that you also agree to help him remove mud from the wheels of his vehicle so that he will not litter the public streets. Further as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be claimed by anyone to have arisen out of delivery of this order SIGNED:
X _____

Excessive Water is Detrimental to Concrete Performance.
H₂O Added by Request/Authorized By: _____
GAL X _____
WEIGHMASTER
Surcharge for credit cards
NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.
LOAD RECEIVED BY
X _____

129993

CONCRETE COMPRESSIVE STRENGTH TEST REPORT

Report Number: A1171057.0257
Service Date: 12/06/22
Report Date: 01/24/23 Revision 1 -
Task: PO# 615251



6198 Imperial Loop
 College Station, TX 77845-5765
 979-846-3767 Reg No: F-3272

Client

Texas Transportation Institute
 Attn: Bill Griffith
 TTI Business Office
 3135 TAMU
 College Station, TX 77843-3135

Project

Riverside Campus
 Riverside Campus
 Bryan, TX
 Project Number: A1171057

Material Information

Specified Strength: 3,600 psi @ 28 days

Mix ID: TXC3600 DOTC, 3600, RG 5"
Supplier: Texcrete
Batch Time: **Plant:**
Truck No.: 122 **Ticket No.:** 70130

Sample Information

Sample Date: 12/06/22 **Sample Time:** 1130
Sampled By: Austin Holcomb
Weather Conditions: 70s - Mostly Cloudy
Accumulative Yards: 7 **Batch Size (cy):** 7
Placement Method: Chute
Water Added Before (gal): 5
Water Added After (gal): 0
Sample Location: Bridge Deck Footings w/ Curb Tie-in on the West Side of the Restricted Access Lot (PO# 615251 - 106)
Placement Location: Footings

Field Test Data

Test	Result	Specification
Slump (in):	5 1/4	
Air Content (%):	3.8	
Concrete Temp. (F):	79	
Ambient Temp. (F):	74	
Plastic Unit Wt. (pcf):		
Yield (Cu. Yds.):		

Laboratory Test Data

Set No.	Spec ID	Cyl. Cond.	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Max Load (lbs)	Comp Strength (psi)	Frac Type	Tested By
1	A	Good	6.00	28.27		01/02/23	27 F	102,730	3,630	5	CRM
1	B	Good	6.00	28.27		01/02/23	27 F	106,930	3,780	5	CRM
1	C	Good	6.00	28.27		01/02/23	27 F	103,410	3,660	5	CRM
1	D						Hold				

Initial Cure: Outside Plastic Lids **Final Cure:** Field Cured **Sample Description:** 6-inch diameter cylinders

Comments: Not tested for plastic unit weight. F = Field Cured

Note: Reported air content does not include Aggregate Correction Factor (ACF).
 Bridge Deck Footings w/ Curb Tie-in on the West Side of the Restricted Access Lot to be used in High-Speed & Autonomous Vehicle Testing PO# 615251 - 106 (See Drawing)

Contractors and Client were informed if any slumps, temperatures, air readings, and/or Concrete Times were recorded out of range of job specifications. The data provided is for all Concrete that has been accepted and used by the Contractors on-site.

Approximately 7 yds were poured at the Riverside Campus For the Bridge Deck Footings w/ Curb Tie-in on the West Side of the Restricted Access Lot to be used in High-Speed & Autonomous Vehicle Testing (PO# 615251 - 106)

Weather: 70s, Mostly Cloudy

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

CONCRETE COMPRESSIVE STRENGTH TEST REPORT

Report Number: A1171057.0257
Service Date: 12/06/22
Report Date: 01/24/23 Revision 1 -
Task: PO# 615251


6198 Imperial Loop
College Station, TX 77845-5765
979-846-3767 Reg No: F-3272

Client

Texas Transportation Institute
Attn: Bill Griffith
TTI Business Office
3135 TAMU
College Station, TX 77843-3135

Project

Riverside Campus
Riverside Campus
Bryan, TX
Project Number: A1171057

Samples Made By: Terracon


Services: Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).

Terracon Rep.: Austin Holcomb
Reported To: Adam w/ TTI
Contractor: MBC Management

Start/Stop: 1030-1245

Report Distribution:
(1) Texas Transportation Institute, Bill Griffith

Reviewed By:



Alexander Dunigan
Project Manager

Test Methods: ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

Photo Log

Report Number: A1171057.0257
Service Date: 12/06/22
Report Date: 01/24/23 Revision 1 -
Task: PO# 615251



6198 Imperial Loop
College Station, TX 77845-5765
979-846-3767 Reg No: F-3272



(P1) 12.06.2022-A



(P2) 12.06.2022-B

Photo Log


Report Number: A1171057.0257
Service Date: 12/06/22
Report Date: 01/24/23 Revision 1 -
Task: PO# 615251



6198 Imperial Loop
College Station, TX 77845-5765
979-846-3767 Reg No: F-3272



(P3) 12.06.2022-C



(P4) 12.06.2022-D

Photo Log

Report Number: A1171057.0257
Service Date: 12/06/22
Report Date: 01/24/23 Revision 1 -
Task: PO# 615251



6198 Imperial Loop
College Station, TX 77845-5765
979-846-3767 Reg No: F-3272



(P5) 12.06.2022-E

TEXCRETE
Redi-mix Concrete Company

REMIT PAYMENT TO:
 P.O. BOX 138
 KURTEN, TX 77862

5222 Sandy Point RD.
 Bryan, Tx 77807

TEXCRETE

17534 SH 6 South
 College Station, TX 77845

18935 Circle Lake Dr.
 Pinehurst, TX 77362

130394

BCS DISPATCH - 979-316-2906
 PINEHURST DISPATCH - 936-232-5815
 OFFICE - 979-985-3636

MBC MANAGEMENT
 WAREHOUSE RD, RELLIS CAMPUS, BRYAN TX

RT 2818, TAKE THE HWY 21 ENTRANCE INTO
 RELLIS CAMPUS, LT AT "T", RT AVE A, RT
 WAREHOUSE RD

TIME	FORMULA	LOAD SIZE	YARD ORDERED		DRIVER/TRUCK	PLANT TRANSACTION#	
10:11	TXC3600	6.00	6.00	PO#	MELVIN MASON10	72351	
DATE	PROJECT	LOAD#	YARDS DEL.	BATCH#	WATER TRIM	SLUMP	TICKET NUMBER
12/12/22	TTIINLE	6.00	6.00			5.00 in	70539

QUANTITY	CODE	DESCRIPTION	UNIT PRICE	EXTENDED PRICE
6.00 CY	TXC3600	DOTC, 3600, RG, 5"		
1.00 ea	FUEL	Fuel Charge		

Thank you for your business

LEFT PLANT	ARRIVED JOB	START UNLOADING	SLUMP	CONCRETE TEMP.	AIR TEMP.
10:15	10:37				
FINISH UNLOADING	LEFT JOB	ARRIVED AT PLANT	ON SITE TESTING		
			TESTING LAB:	TERRACON GESSNER CME	OTHER
		TESTED	AIR	CYLINDERS	
		<input type="checkbox"/> YES <input type="checkbox"/> NO			

Tax
 Prev. amt
 Ticket Total

ADDITIONAL CHARGE 1
 ADDITIONAL CHARGE 2

GRAND TOTAL

WARNING
IRRITATING TO THE SKIN AND EYES
 Contains Portland Cement, Wear Rubber Boots and Gloves. PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact with Skin. In Case of Contact with Skin or Eyes, Rinse Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**

CONCRETE is a PERISHABLE COMMODITY and BECOMES THE PROPERTY of the PURCHASER UPON LEAVING the PLANT. ANY CHANGES or CANCELLATION of ORIGINAL INSTRUCTIONS MUST be TELEPHONED to the OFFICE BEFORE LOADING starts. The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.

All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible For Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.
 A \$25.00 Service Charge and Loss of the Cash Discounted will be Collected on all Returned Checks. Damage charge after 60 min. will be \$100.00/hr.

PROPERTY DAMAGE RELEASE
 (TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)
 Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE releasing him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, driveways, curbs, etc. by the delivery of this material and that you also agree to help him remove mud from the wheels of this vehicle so that he will not litter the public streets. Further as additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises, and for adjacent property which may be claimed by anyone to have arisen out of delivery of this order SIGNED:

Excessive Water is Detrimental to Concrete Performance.
 H₂O Added by Request/Authorized By:

GAL X
 WEIGHMASTER

Surcharge for credit cards

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.

LOAD RECEIVED BY

X

X

130394

CONCRETE COMPRESSIVE STRENGTH TEST REPORT

Report Number: A1171057.0260
Service Date: 12/12/22
Report Date: 01/24/23 Revision 2 -
Task: PO# 615251



Client

Texas Transportation Institute
Attn: Bill Griffith
TTI Business Office
3135 TAMU
College Station, TX 77843-3135

Project

Riverside Campus
Riverside Campus
Bryan, TX
Project Number: A1171057

Material Information

Specified Strength: 3,600 psi @ 28 days

Mix ID: TXC3600
Supplier: Texcrete
Batch Time: 1011 **Plant:**
Truck No.: MASON10 **Ticket No.:** 70539

Sample Information

Sample Date: 12/12/22 **Sample Time:** 1050
Sampled By: Randy Rippstein
Weather Conditions: Cloudy, Heavy wind
Accumulative Yards: 6 **Batch Size (cy):** 6
Placement Method: Direct Discharge
Water Added Before (gal): 0
Water Added After (gal): 0
Sample Location: Top of beam north end
Placement Location: South West side runway

Field Test Data

Test	Result	Specification
Slump (in):	6 1/2	
Air Content (%):	1.5	
Concrete Temp. (F):	80	
Ambient Temp. (F):	64	
Plastic Unit Wt. (pcf):	147.6	
Yield (Cu. Yds.):		

Laboratory Test Data

Set No.	Spec ID	Cyl. Cond.	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Max Load (lbs)	Comp Strength (psi)	Frac Type	Tested By
1	B	Good	6.00	28.27		01/03/23	22 F	108,620	3,840	5	CRM
1	C	Good	6.00	28.27		01/03/23	22 F	111,780	3,950	5	CRM
1	D	Good	6.00	28.27		01/03/23	22 F	113,300	4,010	5	CRM
1	A	Good					Hold			3	BFM

Initial Cure: Outside Plastic Lids **Final Cure:** Field Cured **Sample Description:** 6-inch diameter cylinders

Comments: F = Field Cured
Note: Reported air content does not include Aggregate Correction Factor (ACF).

Samples Made By: Terracon

Services: Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).


Terracon Rep.: Randy Rippstein
Reported To: Bill w/ TTI
Contractor: MBC Management
Report Distribution:
(1) Texas Transportation Institute, Bill Griffith

Start/Stop: 0900-1100

Reviewed By:
Alexander Dunigan
Project Manager

Test Methods: ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

 Quality Form	QF 7.3-01 Concrete Sampling	Doc. No. QF 7.3-01	Revision Date: 2020-07-29
	Revised by: B.L. Griffith Approved by: D. L. Kuhn	Revision: 7	Page: 1 of 1

Project No: 615251 **Casting Date:** 12/21/2022 **Mix Design (psi):** 3600

Name of Technician Taking Sample _____	Name of Technician Breaking Sample _____
Signature of Technician Taking Sample _____	Signature of Technician Breaking Sample _____
Terracon	Terracon

Load No.	Truck No.	Ticket No.	Location (from concrete map)
T1	James N.131	144248	100% of Parapet and Approach Slab

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average

TEXCRETE
Redi-mix Concrete Company

REMIT PAYMENT TO:
P.O. BOX 138
KURTEN, TX 77862

5222 Sandy Point Rd.
Bryan, TX 77807

TEXCRETE

17534 SH 6 South
College Station, TX 77845

18935 Circle Lake Dr.
Pinehurst, TX 77362

144248

BCS DISPATCH - 979-316-2906
PINEHURST DISPATCH - 936-232-5815
OFFICE - 979-985-3636

MBC MANAGEMENT
WAREHOUSE RD. BRYAN TX

RT 2818, TAKE THE HWY 21 ENTRANCE INTO
RELLIS CAMPUS, LT AT "T", RT INTO GATE 5

TIME	FORMULA	LOAD SIZE	YARD ORDERED	DRIVER/TRUCK	PLANT TRANSACTION#
11:01	TXC3600	5.00	5.00 PO#	JAMES N. 131	72708
DATE	PROJECT	LOAD#	YARDS DEL.	BATCH#	TICKET NUMBER
12/21/22	TTIINLE	5.00	5.00		70902

QUANTITY	CODE	DESCRIPTION	UNIT PRICE	EXTENDED PRICE
5.00 CY	TXC3600	DOTC, 3600, RG, 5"		
1.00 ea	FUEL	Fuel Charge		

Thank you for your business

LEFT PLANT	ARRIVED JOB	START UNLOADING	SLUMP	CONCRETE TEMP	AIR TEMP
1109	1126				
FINISH UNLOADING	LEFT JOB	ARRIVED AT PLANT	ON SITE TESTING		
			TESTING LAB:	TERRACON	
				GESSNER	
				CME	OTHER
		TESTED	AIR	CYLINDERS	
		<input type="checkbox"/> YES <input type="checkbox"/> NO			

Tax
Prev. amt
Ticket Total

ADDITIONAL CHARGE 1

ADDITIONAL CHARGE 2

GRAND TOTAL

WARNING
IRRITATING TO THE SKIN AND EYES
Contains Portland Cement, Wear Rubber Boots and Gloves. PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact with Skin. In Case of Contact with Skin or Eyes, Rinse Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**

CONCRETE is a PERISHABLE COMMODITY and BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES or CANCELLATION OF ORIGINAL INSTRUCTIONS MUST be TELEPHONED to the OFFICE BEFORE LOADING starts. The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.

All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible For Reactive Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered. A \$25.00 Service Charge and Loss of the Cash Discounted will be Collected on all Returned Checks. Demerage charge after 90 min. will be \$100.00/hr.

PROPERTY DAMAGE RELEASE
(TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)
Dear Customer - The driver of this truck, in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property. If he places the material in this load where you desire it, it is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property, buildings, sidewalks, driveways, curbs, etc. by the delivery of this material and that you also agree to help him remove mud from the wheels of his vehicle so that he will not be the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property, which may be caused by anyone to have arisen out of delivery of this order SIGNED.

Excessive Water is Detrimental to Concrete Performance.
H₂O Added by Request/Authorized By:

GAL X
WEIGHMASTER

Surcharge for credit cards

NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.

LOAD RECEIVED BY


X

X

144248

CONCRETE COMPRESSIVE STRENGTH TEST REPORT

Report Number: A1171057.0262
Service Date: 12/21/22
Report Date: 01/24/23 Revision 1 - 34-day test results
Task: PO# 615251



Client

Texas Transportation Institute
Attn: Bill Griffith
TTI Business Office
3135 TAMU
College Station, TX 77843-3135

Project

Riverside Campus
Riverside Campus
Bryan, TX
Project Number: A1171057

Material Information

Specified Strength: 3,000 psi @ 28 days

Mix ID: TXC3600
Supplier: Texcrete
Batch Time: 1101
Truck No.: 131

Plant:
Ticket No.: 70902

Sample Information

Sample Date: 12/21/22 **Sample Time:** 1150
Sampled By: Austin Holcomb
Weather Conditions: 40s, Fog / Mostly Cloudy
Accumulative Yards: 5 **Batch Size (cy):** 5
Placement Method: Chute
Water Added Before (gal): 3
Water Added After (gal): 0
Sample Location: Pavement near Storm Drain & TTI Wall connected to footing PO# 615251-106 (See Drawing)
Placement Location: Pavement & TTI Wall for Crash Testing

Field Test Data

Test	Result	Specification
Slump (in):	5 3/4	
Air Content (%):	3.4	
Concrete Temp. (F):	63	
Ambient Temp. (F):	44	
Plastic Unit Wt. (pcf):		
Yield (Cu. Yds.):		

Laboratory Test Data

Set No.	Spec ID	Cyl. Cond.	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Max Load (lbs)	Comp Strength (psi)	Frac Type	Tested By
1	A	Good	6.00	28.27		01/03/23	13 F	88,010	3,110	3	CRM
1	B	Good	6.00	28.27		01/03/23	13 F	84,180	2,980	5	CRM
1	C	Good	6.00	28.27		01/03/23	13 F	79,550	2,810	5	CRM
1	D	Good	6.00	28.27		01/24/23	34 F	104,690	3,700	2	AWD

Initial Cure: Covered with Plastic **Final Cure:** Field Cured **Sample Description:** 6-inch diameter cylinders

Comments: Not tested for plastic unit weight. F = Field Cured
Note: Reported air content does not include Aggregate Correction Factor (ACF).
Lot Pavement Extension near Storm Drain and TTI Crash Wall PO# 615251 - 106

Contractors and Client were informed if any slumps, temperatures, air readings, and/or Concrete Times were recorded out of range of job specifications. The data provided is for all Concrete that has been accepted and used by the Contractors on-site.

Approximately 9 yds were poured at Riverside Campus For the Lot Pavement Extension near the Storm Drain and TTI Crash Wall PO# 615251 - 106 on the West Side of the Open Lot Near the Mobile Mini Job Trailer (See Drawing).

Weather: 40s, Fog / Mostly Cloudy

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

CONCRETE COMPRESSIVE STRENGTH TEST REPORT

Report Number: A1171057.0262
Service Date: 12/21/22
Report Date: 01/24/23 Revision 1 - 34-day test results
Task: PO# 615251


6198 Imperial Loop
College Station, TX 77845-5765
979-846-3767 Reg No: F-3272

Client
Texas Transportation Institute
Attn: Bill Griffith
TTI Business Office
3135 TAMU
College Station, TX 77843-3135


Project
Riverside Campus
Riverside Campus
Bryan, TX
Project Number: A1171057

Samples Made By: Terracon

Services: Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).

Terracon Rep.: Austin Holcomb
Reported To: Bill with TTI
Contractor: MBC Management
Report Distribution:
(1) Texas Transportation Institute, Bill Griffith

Start/Stop: 1030-1300

Reviewed By: 
Alexander Dunigan
Project Manager

Test Methods: ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

Photo Log


Report Number: A1171057.0262
Service Date: 12/21/22
Report Date: 01/24/23 Revision 1 - 34-day test results
Task: PO# 615251



6198 Imperial Loop
College Station, TX 77845-5765
979-846-3767 Reg No: F-3272



(P1) 12.21.2022-A



(P2) 12.21.2022-B

Photo Log


Report Number: A1171057.0262
Service Date: 12/21/22
Report Date: 01/24/23 Revision 1 - 34-day test results
Task: PO# 615251



6198 Imperial Loop
College Station, TX 77845-5765
979-846-3767 Reg No: F-3272



(P3) 12.21.2022-C



(P4) 12.21.2022-D

Photo Log


Report Number: A1171057.0262
Service Date: 12/21/22
Report Date: 01/24/23 Revision 1 - 34-day test results
Task: PO# 615251



6198 Imperial Loop
College Station, TX 77845-5765
979-846-3767 Reg No: F-3272



(P5) 12.21.2022-E

	QF 7.3-01 Concrete Sampling	Doc. No. QF 7.3-01	Revision Date: 2020-07-29
Quality Form	Revised by: B.L. Griffith Approved by: D. L. Kuhn	Revision: 7	Page: 1 of 1

Project No: 615251 **Casting Date:** 5/26/2023 **Mix Design (psi):** 3600

Name of Technician Taking Sample <u>Terracon</u>	Name of Technician Breaking Sample <u>Terracon</u>
Signature of Technician Taking Sample <u>Terracon</u>	Signature of Technician Breaking Sample <u>Terracon</u>

Load No.	Truck No.	Ticket No.	Location (from concrete map)
T1	Castillo, JUL8	77679	Straight beam and repaired section of tapered beam

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average

Office
DEPOT

SATURDAY

TEXCRETE
Redi-mix Concrete Company

142887

REMIT PAYMENT TO:
P.O. BOX 138
KURTEN, TX 77862

5222 Sandy Point RD.
Bryan, TX 77807

17534 SH 6 South
College Station, TX 77845

18935 Circle Lake Dr.
Pinehurst, TX 77362

BCS DISPATCH - 979-316-2906
PINEHURST DISPATCH - 936-232-5815
OFFICE - 979-985-3636

TEXCRETE

TEXAS A&M TRANSPORTATIO
RELLIS CAMPUS, BRYAN TX

RT 2818, RT HWY 21, LT SILVER HILL, RT AT
THE "T", RT HWY 47, LT INTORELLIS ENTRANCE,
STAY STRAIGHTALL THE WAY DOWN TO THE GATE

TIME	FORMULA	LOAD SIZE	YARD ORDERED		DRIVER/TRUCK	PLANT TRANSACTION#	
8:54	TXC3600	3.00	3.00	PO#	CASTILLO, JUL8	79493	
DATE	PROJECT	LOAD#	YARDS DEL.	BATCH#	WATER TRIM	SLUMP	TICKET NUMBER
5/26/23	TTIRELL	3.00	3.00			5.00 in	77679

QUANTITY	CODE	DESCRIPTION	UNIT PRICE	EXTENDED PRICE
3.00 yd	TXC3600	DOTC, 3600, RG, 5",		
1.00 ea	FUEL	Fuel Charge		

Thank you for your business

LEFT PLANT	ARRIVED JOB	START UNLOADING	SLUMP	CONCRETE TEMP.	AIR TEMP
9:06	9:24				
FINISH UNLOADING	LEFT JOB	ARRIVED AT PLANT	ON SITE TESTING		
			TESTING LAB:	TERRACON GESSNER CME	OTHER
TESTED		AIR	CYLINDERS		
<input type="checkbox"/> YES <input type="checkbox"/> NO					

Tax
Prev. AMT
Ticket Total

ADDITIONAL CHARGE 1 _____
ADDITIONAL CHARGE 2 _____
GRAND TOTAL

WARNING
IRRITATING TO THE SKIN AND EYES
Contains Portland Cement. Wear Rubber Boots and Gloves. PROLONGED CONTACT MAY CAUSE BURNS. Avoid Contact With Eyes and Prolonged Contact with Skin. In Case of Contact with Skin or Eyes, Rinse Thoroughly With Water. If Irritation Persists, Get Medical Attention. **KEEP CHILDREN AWAY.**

CONCRETE is a PERISHABLE COMMODITY and BECOMES THE PROPERTY OF THE PURCHASER UPON LEAVING THE PLANT. ANY CHANGES or CANCELLATION of ORIGINAL INSTRUCTIONS MUST BE TELEPHONED to the OFFICE BEFORE LOADING starts. The undersigned promises to pay all costs, including reasonable attorney's fees, incurred in collecting any sums owed.

All accounts not paid within 30 days of delivery will bear interest at the rate of 18% per annum. Not Responsible For Relative Aggregate or Color Quality. No Claim Allowed Unless Made at Time Material is Delivered.
A \$25.00 Service Charge and Loss of the Cash Discounted will be Collected on all Returned Checks. Demerage charge after 90 min. will be \$100.00/hr.

PROPERTY DAMAGE RELEASE
(TO BE SIGNED IF DELIVERY TO BE MADE INSIDE CURB LINE)
Dear Customer - The driver of this truck in presenting this RELEASE to you for your signature is of the opinion that the size and weight of this truck may possibly cause damage to the premises and/or adjacent property if he places the material in this load where you desire it. It is our wish to help you in every way that we can, but in order to do this the driver is requesting that you sign this RELEASE relieving him and this supplier from any responsibility from damage that may occur to the premises and/or adjacent property buildings, sidewalks, driveways, curbs, etc. by the delivery of this material and that you also agree to help him remove mud from the wheels of this vehicle so that he will not litter the public streets. Further, as an additional consideration, the undersigned agrees to indemnify and hold harmless the driver of this truck and this supplier for any and all damage to the premises and/or adjacent property which may be caused by anyone to have arisen out of delivery of this order SIGNED.

Excessive Water is Detrimental to Concrete Performance.
H₂O Added by Request/Authorized By: _____
GAL X
WEIGHMASTER
Surcharge for credit cards
NOTICE: MY SIGNATURE BELOW INDICATES THAT I HAVE READ THE HEALTH WARNING NOTICE AND SUPPLIER WILL NOT BE RESPONSIBLE FOR ANY DAMAGE CAUSED WHEN DELIVERING INSIDE CURB LINE.
LOAD RECEIVED BY _____

142887

CONCRETE COMPRESSIVE STRENGTH TEST REPORT

Report Number: A1171057.0274
Service Date: 05/26/23
Report Date: 06/21/23
Task: PO# 615251



Client

Texas Transportation Institute
Attn: Bill Griffith
TTI Business Office
3135 TAMU
College Station, TX 77843-3135

Project - A1171057

Riverside Campus
Riverside Campus
Bryan, TX
Permit No.: N/A

Material Information

Specified Strength: 3,600 psi @ 28 days

Mix ID: TXC3600
Supplier: Texcrete
Batch Time: 0854 **Plant:**
Truck No.: 8 **Ticket No.:** 77679

Sample Information

Sample Date: 05/26/23 **Sample Time:** 0936
Sampled By: David Carpio
Weather Conditions: Clear
Accumulative Yards: 5 **Batch Size (cy):** 3
Placement Method: Direct Discharge
Water Added Before (gal): 0
Water Added After (gal): 0
Sample Location: Inlet Box
Placement Location: Inlet Box
Sample Description: 6-inch diameter cylinders

Field Test Data

Test	Result	Specification
Slump (in):	4	
Air Content (%):		
Concrete Temp. (F):	84	
Ambient Temp. (F):	77	
Plastic Unit Wt. (pcf):		
Yield (Cu. Yds.):		

Laboratory Test Data

Set No.	Spec ID	Cyl. Cond.	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Max Load (lbs)	Comp Strength (psi)	Frac Type	Tested By
1	A	Good	6.00	28.27		06/20/23	25 F	107,620	3,810	2	BRR
1	B	Good	6.00	28.27		06/20/23	25 F	104,210	3,690	2	BRR
1	C	Good	6.00	28.27		06/20/23	25 F	105,310	3,720	2	BRR
1	D						Hold				

Initial Cure: Covered with Blanket **Final Cure:** Field Cured

Comments: Not tested for plastic unit weight. F = Field Cured
Note: Reported air content does not include Aggregate Correction Factor (ACF).

Samples Made By: Terracon

Services: Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).

Terracon Rep.: David Carpio
Reported To: Adam w/ TTI
Contractor: MBC Management

Start/Stop: 0800-1030

Report Distribution:
(1) Texas Transportation Institute, Bill Griffith (1) Texas Transportation Institute, Adam Mayer

Reviewed By:
Alexander Durigan, P.E.
Project Manager

Test Methods: ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

APPENDIX C. MASH TEST 3-20 (CRASH TEST 619551-01-1)

C.1. VEHICLE PROPERTIES AND INFORMATION

Date: 2023-06-27 Test No.: 619551-01-1 VIN No.: 3NICN7AP5HL808543
 Year: 2017 Make: Nissan Model: Versa
 Tire Inflation Pressure: 36 PSI Odometer: 100155 Tire Size: P185/65R15

Describe any damage to the vehicle prior to test: None

• Denotes accelerometer location.



NOTES: None

Engine Type: 4 CYL
 Engine CID: 1.6 L

Transmission Type:
 Auto or Manual
 FWD RWD 4WD

Optional Equipment:
None

Dummy Data:
 Type: 50th Percentile Male
 Mass: 165 lb
 Seat Position: IMPACT SIDE



Geometry: inches

A <u>66.70</u>	F <u>32.50</u>	K <u>12.50</u>	P <u>4.50</u>	U <u>15.50</u>
B <u>59.60</u>	G <u>0.00</u>	L <u>26.00</u>	Q <u>24.00</u>	V <u>21.25</u>
C <u>175.40</u>	H <u>41.13</u>	M <u>58.30</u>	R <u>16.25</u>	W <u>41.00</u>
D <u>40.50</u>	I <u>7.00</u>	N <u>58.50</u>	S <u>7.50</u>	X <u>79.75</u>
E <u>102.40</u>	J <u>22.50</u>	O <u>30.50</u>	T <u>64.50</u>	
Wheel Center Ht Front <u>11.50</u>	Wheel Center Ht Rear <u>11.50</u>	W-H <u>-0.13</u>		

RANGE LIMIT: A = 65 ±3 inches; C = 169 ±8 inches; E = 98 ±5 inches; F = 35 ±4 inches; H = 39 ±4 inches; O (Top of Radiator Support) = 28 ±4 inches
 (M+N)/2 = 59 ±2 inches; W-H < 2 inches or use MASH Paragraph A4.3.2

GVWR Ratings:	Mass: lb	Curb	Test Inertial	Gross Static
Front <u>1750</u>	M _{front}	<u>1435</u>	<u>1458</u>	<u>1543</u>
Back <u>1687</u>	M _{rear}	<u>986</u>	<u>979</u>	<u>1059</u>
Total <u>3389</u>	M _{Total}	<u>2421</u>	<u>2437</u>	<u>2602</u>

Allowable TIM = 2420 lb ±55 lb | Allowable GSM = 2585 lb ± 55 lb

Mass Distribution:
 lb LF: 768 RF: 690 LR: 481 RR: 498

Figure C.1. Vehicle Properties for Test 619551-01-1.

Date: 2023-06-27 Test No.: 619551-01-1 VIN No.: 3NICN7AP5HL808543
 Year: 2017 Make: Nissan Model: Versa

VEHICLE CRUSH MEASUREMENT SHEET¹

Complete When Applicable	
End Damage	Side Damage
Undeformed end width _____ Corner shift: A1 _____ A2 _____ End shift at frame (CDC) (check one) < 4 inches _____ ≥ 4 inches _____	Bowing: B1 _____ X1 _____ B2 _____ X2 _____ Bowing constant $\frac{X1 + X2}{2} = \underline{\hspace{2cm}}$

Note: Measure C₁ to C₆ from Driver to Passenger Side in Front or Rear Impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L**	C ₁	C ₂	C ₃	C ₄	C ₅	C ₆	±D
		Width*** (CDC)	Max**** Crush								
1	AT FRONT BUMPER	13	9	32	-	-	-	-	-	-	+10
2	ABOVE FRONT BUMPER	15	7.25	50	-	-	-	-	-	-	49
	Measurements recorded										
	<input checked="" type="checkbox"/> inches or <input type="checkbox"/> mm										

¹Table taken from National Accident Sampling System (NASS).

*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.




**Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).

***Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

Figure C.2. Exterior Crush Measurements for Test 619551-01-1.

Date: 2023-06-27 Test No.: 619551-01-1 VIN No.: 3NICN7AP5HL808543
 Year: 2017 Make: Nissan Model: Versa



OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT

	Before	After (inches)	Differ.
A1	67.50	67.50	0.00
A2	67.25	67.25	0.00
A3	67.75	67.75	0.00
B1	40.50	40.50	0.00
B2	39.00	39.00	0.00
B3	40.50	40.50	0.00
B4	36.25	36.25	0.00
B5	36.00	36.00	0.00
B6	36.25	36.25	0.00
C1	26.00	26.00	0.00
C2	0.00	0.00	0.00
C3	26.00	25.00	-1.00
D1	9.50	9.50	0.00
D2	0.00	0.00	0.00
D3	9.50	9.50	0.00
E1	51.50	51.50	0.00
E2	51.00	49.00	-2.00
F	51.00	50.25	-0.75
G	51.00	51.00	0.00
H	37.50	37.50	0.00
I	37.50	37.50	0.00
J*	51.00	50.25	-0.75

*Lateral area across the cab from driver's side kick panel to passenger's side kick panel.


Figure C.3. Occupant Compartment Measurements for Test 619551-01-1.

C.2. SEQUENTIAL PHOTOGRAPHS



(a) 0.000 s

(b) 0.100 s



(c) 0.200 s

(d) 0.300 s



(e) 0.400 s

(f) 0.500 s



(g) 0.600 s

(h) 0.700 s

Figure C.4. Sequential Photographs for Test 619551-01-1 (Overhead Views).



(a) 0.000 s

(b) 0.100 s



(c) 0.200 s

(d) 0.300 s



(e) 0.400 s

(f) 0.500 s



(g) 0.600 s

(h) 0.700 s

Figure C.5. Sequential Photographs for Test 619551-01-1 (Frontal Views).



(a) 0.000 s

(b) 0.100 s



(c) 0.200 s

(d) 0.300 s



(e) 0.400 s

(f) 0.500 s




(g) 0.600 s

(h) 0.700 s

Figure C.6. Sequential Photographs for Test 619551-01-1 (Rear Views).


C.3. VEHICLE ANGULAR DISPLACEMENTS

Roll, Pitch and Yaw Angles



Axes are vehicle-fixed.
Sequence for determining orientation:

1. Yaw.
2. Pitch.
3. Roll.



Test Number: 619551-01-1
 Test Standard Test Number: MASH Test 3-20
 Test Article TL-3 Transition With A Storm Drain Inlet
 Test Vehicle: 2017 Nissan Versa
 Inertial Mass: 2437 lbs
 Gross Mass: 2602 lbs
 Impact Speed: 62.6 mi/h
 Impact Angle: 25.3°

Figure C.7. Vehicle Angular Displacements for Test 619551-01-1.

C.4. VEHICLE ACCELERATIONS

X Acceleration at CG




Figure C.8. Vehicle Longitudinal Accelerometer Trace for Test 619551-01-1 (Accelerometer Located at Center of Gravity).

Y Acceleration at CG




Figure C.9. Vehicle Lateral Accelerometer Trace for Test 619551-01-1 (Accelerometer Located at Center of Gravity).

Z Acceleration at CG




Figure C.10. Vehicle Vertical Accelerometer Trace for Test 619551-01-1 (Accelerometer Located at Center of Gravity).

TR No. 619551-01

100

2023-10-16